

SAMPLE BAR REPLACEMENT

SIZE SIZE 6'-2" #3 #4 7'-4" 8'-6" #5 9'-8" #6 #7 10'-10" 12'-0" 13'-2" #9 14'-6" 15'-10"

NOTE:

SAMPLE BAR
REPLACEMENT LENGTHS
BASED ON 30" (SAMPLE
LENGTH) PLUS TWO SPLICE
LENGTHS AND fy = 60ksi.
BAR LENGTHS IN THIS
TABLE ARE A GUIDE. THE
ENGINEER SHALL APPROVE
FINAL LENGTHS BASED ON
TYPE AND LOCATION OF
SAMPLE BAR.

NOTES CONT'D:

AT THE CONTRACTOR'S OPTION, AND UPON REMOVAL OF THE CAUSEWAY, THE CLASS II RIP RAP USED IN THE CAUSEWAY MAY BE PLACED AS RIP RAP SLOPE PROTECTION. SEE SPECIAL PROVISIONS FOR CONSTRUCTION, MAINTENANCE, AND REMOVAL OF TEMPORARY ACCESS AT STATION 24+70.00 -L_LT-

AT CONTRACTOR'S OPTION, THE EXISTING STRUCTURE CONCRETE MAY BE RUBBLIZED DURING REMOVAL AND USED AS STABILIZATION/ABCM.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR GLASS FIBER REINFORCED POLYMER (GFRP) BAR, SEE SPECIAL PROVISIONS.

GENERAL NOTES:

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

FOR SUBMITTAL OF WORKING DRAWINGS. SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY. SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.

FOR LIMITS OF TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC, SEE TRAFFIC CONTROL PLANS. FOR PAY ITEM FOR TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC, SEE ROADWAY PLANS.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC-18 EVALUATING SCOUR AT BRIDGES."

THE SCOUR CRITICAL ELEVATION FOR BENT NO. 1 LEFT SIDE AND RIGHT SIDE ARE 2554 FT AND 2550 FT. RESPECTIVELY. SCOUR CRITICAL ELEVATIONS ARE USED TO MONITOR POSSIBLE SCOUR PROBLEMS DURING THE LIFE OF THE STRUCTURE.

FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION & RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

THE ELEVATIONS AND CLEARANCES SHOWN ON THE PLANS AT THE POINTS OF MINIMUM VERTICAL CLEARANCE ARE FROM THE BEST INFORMATION AVAILABLE. PRIOR TO BEGINNING BRIDGE CONSTRUCTION, VERIFY THE ELEVATIONS ON THE EXISTING PAVEMENT AND CHECK THE CLEARANCE. REPORT ANY VARIATIONS TO THE ENGINEER. ANY PLAN REVISIONS NECESSARY TO ACHIEVE THE REQUIRED MINIMUM VERTICAL CLEARANCE WILL BE PROVIDED BY THE DEPARTMENT.

INASMUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD FOR THE EXISTING STRUCTURE, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR "REMOVAL OF EXISTING STRUCTURE AT STATION 24+70.00 -L LT-".

THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH ARTICLES 1024-5 AND 1024-6 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.

THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA ON SHEET 1 OF 4 SHALL BE EXCAVATED FOR A DISTANCE OF 64 FT. LEFT OF CENTERLINE - L_LT- AND 37 FT. RIGHT OF CENTERLINE -L_LT- AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPLICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

AFTER SERVING AS A TEMPORARY STRUCTURE, THE EXISTING STRUCTURE CONSISTING OF 4 SPANS AT 50FT OF CONCRETE DECK ON ROLLED STEEL W-SHAPE GIRDERS, WITH 28.0 FT CLEAR ROADWAY WIDTH, SUPPORTED BY PILE BENT CONCRETE END BENTS AND CONCRETE POST AND BEAM BENTS ON ISOLATED SPREAD FOOTINGS, AND LOCATED AT THE PROPOSED STRUCTURE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY NOT POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, A LOAD LIMIT MAY BE POSTED AND MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR. THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

FOR CONSTRUCTION, MAINTENANCE, AND REMOVAL OF TEMPORARY ACCESS, SEE SPECIAL PROVISIONS.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED IN A MANNER THAT PREVENTS DEBRIS FROM FALLING INTO THE WATER. THE CONTRACTOR SHALL SUBMIT DEMOLITION PLANS FOR REVIEW AND REMOVE THE BRIDGE IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT 1 FT. BELOW THE GROUND LINE.

THE LOCATION OF THE ABOVE GROUND SANITARY SEWER SHOWN IS BASED ON AN APPROXIMATE SURVEY. PRIOR TO BEGINNING BRIDGE CONSTRUCTION, CONTRACTOR SHALL VERIFY THE LOCATION OF THE SANITARY SEWER AND ENSURE THAT THE UTILITY IS PROTECTED DURING THE REMOVAL OF THE EXISITNG STRUCTURE AND DURING THE CONSTRUCTION OF THE PROPOSED STRUCTURES.

PROJECT NO. B-3186 / B-5898

HAYWOOD COUNTY

STATION: 24+70.00 -L_LT-

SHEET 4 OF 4

AECOM TECHNICAL SERVICES OF NC, INC.
5438 WADE PARK BOULEVARD, SUITE 200
RALEIGH, NC 27607
(919) 854-6200
Www.aecom.com
AECOM License No. F-0342

DEPARTMENT OF TRANSPORTATION

RALETCH

GENERAL DRAWING

Doeusigned by:

04/497

259AAAAF9604452

10/13/2023

FOR BRIDGE ON US74 WB/ US23 SB OVER RICHLAND CREEK BETWEEN US276 AND US19

	SHEET NO.					
NO.	BY:	DATE:	NO.	BY:	DATE:	S3-04
1			3			TOTAL SHEETS
2			4			50

TOTAL BILL OF MATERIAL														
	CONSTRUCTION, MAINTENANCE, AND REMOVAL OF TEMPORARY ACCESS AT STA. 24+70.00 -L_LT-	REMOVAL OF EXISTING STRUCTURE AT STA. 24+70.00 -L_LT-	ASEBESTOS 4'-6" ASSESSMENT DRILLE PIERS SOIL		4'-6" Ø DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 4'-6" Ø DRILLED PIER	PDA TESTING	SID TESTING	CSL TESTING	UNCLASSIFIED STRUCTURE EXCAVATION AT STA. 24+70.00	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS		BRIDGE APPROACH SLABS
	LUMP SUM	LUMP SUM	LUMP SUM	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH	LUMP SUM	SQ. FT.	SQ. FT.	CU. YDS.	LUMP SUM
SUPERSTRUCTURE											11,758	11,619		
END BENT 1													76.2	
BENT 1				46.3	42.2	42.9		3	3				82.5	
END BENT 2													72.7	
TOTAL	LUMP SUM	LUMP SUM	LUMP SUM	46.3	42.2	42.9	1	3	3	LUMP SUM	11,758	11,619	231.4	LUMP SUM

TOTAL BILL OF MATERIAL																	
	STEEL REINFORCED COLUMN PRESTRESSED EQUIPMENT POLYMER REINFORCING CONCRETE SETUP FOR (GFRP) BAR STEEL GIRDERS HP 14X73		PILE DRIVING EQUIPMENT SETUP FOR HP 14X73 STEEL PILES	STEEL PILES		STEEL PILE POINTS	PILE REDRIVES	CONCRETE BARRIER RAIL	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	EXPANSION JOINT SEALS		TEMPORARY OVERBUILD AND REMOVAL			
	LBS.	LIN. FT.	LBS.	NO.	LIN. FT.	EACH	NO.	LIN. FT.	EACH	EACH	LIN. FT.	TON	SQ. YDS.	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM
SUPERSTRUCTURE		9,230		14	1,632.6						778.1						
END BENT 1	9,097					19	19	665	19			489	543				
BENT 1	21,930		3,903														
END BENT 2	9,029					19	19	665	19			460	511				
					_							_					
TOTAL	40,056	9,230	3,903	14	1,632.6	38	38	1,330	38	18	778.1	949	1,054	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM

DRAWN BY: A.R. VAN VUREN

CHECKED BY: D. TUTTLE

DATE: 06/2023

DESIGN ENGINEER OF RECORD: D. TUTTLE

DATE: 06/2023

O6/2023

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED