Approximate quantities only. Shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
U-5839	X-0B

Note: Quantities are approximate only. The Resident Engineer will use methods including but not limited to recross-sectioning, truck measurements, and aerial surveys to compute the final quantities for which the contractor will be paid.

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y6		
15+50.0000	1492	0
16+00.0000	1419	0
16+50.0000	1532	0
16+95.0000	1468	0
Y7		
14+20.0000	0	0
14+50.0000	9	0
15+00.0000	40	7
15+50.0000	143	7
16+00.0000	148	2
16+00.8700	1	1
Y8		
10+20.0000	0	0
10+50.0000	20	0
10+75.0000	8	0
Y9		
11+30.0000	0	0
11+50.0000	3	0
12+00.0000	16	0
12+50.0000	17	12
13+00.0000	19	42
13+50.0000	20	44
14+00.0000	18	24
14+50.0000	31	17
15+00.0000	43	8
15+50.0000	31	44
16+00.0000	18	51
16+36.6200	9	14
Y10		
10+37.9200	0	0
10+50.0000	1	0
11+00.0000	9	26
11+50.0000	11	41
12+00.0000	6	39
12+50.0000	8	27
13+00.0000	14	5
13+50.0000	15	3
13+84.0000	5	1

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y11		
11+20.0000	0	0
11+50.0000	4	1
11+78.4200	8	2
Y13		
10+35.0800	0	0
10+50.0000	10	0
11+00.0000	21	4
11+50.0000	10	6
12+00.0000	13	5
Y14		
10+72.0000	0	0
11+00.0000	8	0
11+50.0000	30	0
12+00.0000	31	3
12+50.0000	21	15
13+00.0000	9	50
13+50.0000	8	43
13+50.0000	8	43
13+66.0200	2	3
Y14A		
10+44.8000	0	0
10+50.0000	13	4
11+00.0000	94	31
11+50.0000	98	9
12+00.0000	103	0
12+50.0000	67	0
12+95.0000	29	0
Y15		
10+54.0500	0	0
11+00.0000	2	46
11+50.0000	38	30
11+74.0000	18	2
Y16		
15+95.0000	0	0
16+00.0000	0	0
16+50.0000	5	4
17+00.0000	6	18
17+50.0000	7	21

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y16		
17+62.4000	1	4
Y17		
10+35.7700	0	0
11+00.0000	31	317
11+42.2700	10	104
Y18		
10+35.7900	0	0
10+50.0000	14	1
11+00.0000	43	2
11+50.0000	41	1
11+86.0000	16	1
Y20		
11+88.0000	0	0
12+00.0000	9	0
12+16.4000	12	0
Y21RPA		
13+05.0000	0	0
13+50.0000	9	7
14+00.0000	16	19
14+50.0000	29	58
14+66.2600	15	30
Y21RPB		
13+05.0000	0	0
13+50.0000	8	11
14+00.0000	22	25
14+50.0000	44	24
15+00.0000	81	29
15+50.0000	52	60
16+00.0000	5	103
16+50.0000	6	74
16+55.2400	1	3
Y21LPB		
16+50.0000	0	0
17+00.0000	25	20
17+50.0000	19	51

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y21LPB		
18+00.0000	17	63
18+50.0000	31	41
19+00.0000	75	16
19+50.0000	60	65
19+60.8100	3	27
Y21RPD & Y21LPD		
13+75.0000	0	0
14+00.0000	15	5
14+50.0000	41	21
15+00.0000	44	17
15+50.0000	183	11
16+00.0000	487	27
16+50.0000	653	58
17+00.0000	546	118
17+50.0000	386	230
18+00.0000	230	306
18+50.0000	112	331
19+00.0000	80	200
19+50.0000	100	44
19+92.1600	98	33