


APPROACH SLAB BILL OF MATERIAL						SIDEWALK BILL OF MATERIAL						APPROACH SLAB BILL OF MATERIAL						SIDEWALK BILL OF MATERIAL					
FOR ONE APPROACH SLAB (2 REQ'D) (STAGE I)						FOR ONE APPROACH SLAB (2 REQ'D) (STAGE I)						FOR ONE APPROACH SLAB (2 REQ'D) (STAGE II)						FOR ONE APPROACH SLAB (2 REQ'D) (STAGE II)					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A1	26	#4	STR	31'-8"	550	* B3	4	#4	STR	24'-8"	66	* A3	52	#4	STR	28'-1"	976	* B3	4	#4	STR	24'-8"	66
A2	26	#4	STR	31'-8"	550							A4	52	#4	STR	27'-11"	970	* G1	25	#4	STR	5'-0"	84
* B1	64	#5	STR	24'-2"	1613	* G1	25	#4	STR	5'-0"	84	* B1	109	#5	STR	24'-2"	2747	* G1	25	#4	STR	5'-0"	84
B2	64	#6	STR	24'-8"	2371	* U1	8	#4	1	3'-4"	18	B2	109	#6	STR	24'-8"	4038	* U1	8	#4	1	3'-4"	18
* D1	17	#6	STR	3'-0"	77																		
REINFORCING STEEL LBS. 2921						REINFORCING STEEL LBS. 5009						REINFORCING STEEL LBS. 5009						REINFORCING STEEL LBS. 5009					
* EPOXY COATED REINFORCING STEEL LBS. 2240						* EPOXY COATED REINFORCING STEEL LBS. 168						* EPOXY COATED REINFORCING STEEL LBS. 3723						* EPOXY COATED REINFORCING STEEL LBS. 168					
CLASS AA CONCRETE C. Y. 36.6						CLASS AA CONCRETE C. Y. 3.1						CLASS AA CONCRETE C. Y. 56.5						CLASS AA CONCRETE C. Y. 3.1					

MONOLITHIC CONC. ISLAND BILL OF MATERIAL						MONOLITHIC CONC. ISLAND BILL OF MATERIAL					
FOR END BENT 1						FOR END BENT 2					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* B4	3	#4	STR	24'-8"	49	* B5	4	#4	STR	24'-9"	66
* G2	17	#4	STR	3'-8"	42	* G3	16	#4	STR	5'-9"	61
* EPOXY COATED REINFORCING STEEL LBS. 91						* EPOXY COATED REINFORCING STEEL LBS. 127					
CLASS AA CONCRETE C. Y. 1.8						CLASS AA CONCRETE C. Y. 2.6					



SPLICE LENGTHS		
BAR SIZE	EPOXY COATED	UNCOATED
#4	1'-11"	1'-7"
#5	2'-5"	2'-0"
#6	3'-7"	2'-5"

NOTES

FOR BRIDGE APPROACH FILL, SEE ROADWAY PLANS.

STAGE I APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE STAGE I BRIDGE DECK. STAGE II APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE STAGE II AND CLOSURE POUR OF BRIDGE DECK.



AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

THE JOINT OPENING AT THE APPROACH SLAB/DECK INTERFACE SHALL BE SAWED NO MORE THAN 12 HOURS AFTER THE APPROACH SLAB IS CAST. THE JOINT SHALL BE CLEANED OF ALL DEBRIS BEFORE THE SEALANT IS APPLIED. THE JOINT SEALER MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF SECTION 1028-3 OF THE STANDARD SPECIFICATIONS.

AT THE CONTRACTORS OPTION, "TYPE 1A - ALTERNATE APPROACH FILL" (ROADWAY STD. 423.02) MAY BE CONSTRUCTED AT NO ADDITIONAL COST TO THE DEPARTMENT IN LIEU OF "TYPE 1 - APPROACH FILL". SEE SHEET 3 OF 4 FOR DETAILS.

PAYMENT FOR SIDEWALK AND MONOLITHIC CONCRETE ISLAND SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR BRIDGE APPROACH SLAB.

ALL REINFORCING STEEL IN THE SIDEWALK AND MONOLITHIC CONCRETE ISLAND SHALL BE EPOXY COATED.



SECTION THRU SLAB
(TYPE 1 - APPROACH FILL)

PROJECT NO. U-5839
HAYWOOD COUNTY
 STATION: 31+45.00 -L- POT

SHEET 2 OF 4

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**BRIDGE APPROACH SLAB
 FOR INTEGRAL ABUTMENT
 WITH FLEXIBLE PAVEMENT**

PLANS PREPARED BY:

NV5

NV5 ENGINEERS & CONSULTANTS, INC.
 3300 REGENCY PARKWAY, SUITE 100
 CARY, NC 27518
 P: 919.851.1912 www.NV5.com
 NC License # F-1333

DocuSigned by:

Robert C. Larson

BEB2398D9220470...

**NORTH CAROLINA
 PROFESSIONAL
 ENGINEER
 SEAL
 1414
 ROBERT C. LARSON**

10/19/2023

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			49
2			4			

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

DRAWN BY: W. B. ALLEN DATE: 5/19
 CHECKED BY: Z. H. BROWN DATE: 7/19
 DESIGN ENGINEER OF RECORD: R. C. LARSON DATE: 2/23

DocuSigned by:

Robert C. Larson

BEB2398D9220470...

+

+

10/19/2023 12:39:12 PM R:\Structures\Bridge over Richard Creek\17 U5839_SMU_452_43086.dgn