

PROJECT NO.: U-5873
 COMPUTED BY: FDM
 CHECKED BY: JWM

SHEET OF
 SECTION: 620

ASPHALT BINDER FOR PLANT MIX

GRADE PG 64-22

SA-1	_____	TONS	X	0.068	=	_____	TONS
S4.75A	_____	TONS	X	0.070	=	_____	TONS
S9.5B	1,840	TONS	X	0.065	=	119.60	TONS
S9.5C	_____	TONS	X	0.059	=	_____	TONS
I19.0C	2,080	TONS	X	0.048	=	99.84	TONS
B25.0C	2,780	TONS	X	0.045	=	125.10	TONS
PADC, TYPE P-57	_____	TONS	X	0.030	=	_____	TONS
PADC, TYPE P-78M	_____	TONS	X	0.030	=	_____	TONS
PATCHING EXISTING PAVEMENT	_____	TONS	X	0.048	=	_____	TONS

SUBTOTAL TONS ASPHALT BINDER
 FOR PLANT MIX, GRADE PG 64-22 = 344.54 TONS

TOTAL TONS ASPHALT BINDER
 FOR PLANT MIX = 344.54 TONS
 SAY 345 TONS

THIS SHEET IS SHOWING RATES FROM THE 2023 QMS ASPHALT MANUAL