

Earthwork Balance Sheet

Volumes in Cubic Yards

PROJECT: U-5873

COUNTY: Mecklenburg

DATE: 11/3/2023

COMPILED BY: KIMLEY-HORN

SHEET 1 OF 3 SHEETS

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE			
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. +15%		ROCK	SUITABLE	UNSUIT.	TOTAL
SECTION 1 (PHASE 1A)																
-Y2- (RT)	13+10.00	15+66.29	474				474	0	0	0				474		474
-Y3- (LT)	10+11.00	11+30.00	16				16	3	3	3				13		13
-Y3- (RT)	10+11.00	11+30.00	11				11	3	3	3				8		8
		SUBTOTAL	501	0	0	0	501	6	0	6	7	0	0	494	0	494
SECTION 2 (PHASE 1B)																
-L- (LT)	11+95.33	14+80.00	46				46	136	136	156	110					
-CURB 1C-	10+58.18	12+23.00	21				21	588	588	676	655					
-CURB 1D-	11+25.00	12+13.23	301				301	8	8	9			292		292	
-CURB 1A-	10+50.00	13+17.45	313				313	1994	1994	2293	1980					
-CURB 1B-	10+00.00	12+77.75	0				0	3001	3001	3451	3451					
-L- (LT)	15+04.30	18+83.07	692				692	3766	3766	4331	3639					
-L- (RT)	15+07.88	19+05.39	690				690	4025	4025	4629	3939					
-L- (LT)	18+83.07	26+46.39	1030				1030	3444	3444	3961	2931					
-L- (RT)	19+05.39	26+46.39	313				313	1638	1638	1884	1571					
-Y5- (LT)	10+11.39	12+10.00	396				396	0	0	0			396		396	
-Y5- (RT)	10+11.39	12+10.00	66				66	29	29	33			33		33	
-DRW15-	10+22.00	11+02.00	8				8	287	287	330	322					
		SUBTOTAL	3876	0	0	0	3876	18916	0	18916	21753	18598	0	720	0	720
SECTION 3 (PHASE 1C)																
-Y1- (LT)	10+45.80	13+57.38	4				4	1328		1328	1527	1523				
		SUBTOTAL	4	0	0	0	4	1328	0	1328	1527	1523	0	0	0	0
SECTION 4 (PHASE 1D)																
-L- (RT)	11+95.33	14+96.00	94				94	56	56	64			30		30	
-L- (LT)	14+80.00	15+04.30	4				4	21	21	24	20					
-CURB 1A-	10+00.00	10+50.00	261				261	0	0	0			261		261	
-CURB 1C-	10+00.00	10+58.18	47				47	29	29	33			14		14	
-CURB 1D-	10+00.00	11+25.00	170				170	27	27	31			139		139	
-Y1- (RT)	9+88.00	13+52.11	51				51	380	380	437	386					
-Y2- (LT)	11+80.53	15+25.00	952				952	0	0	0			952		952	
-Y2- (RT)	11+34.94	13+10.00	61				61	163	163	187	126					
-Y2- (RT)	15+90.00	20+00.00	117				117	381	381	438	321					
-Y6- (LT)	10+11.00	11+98.00	11				11	63	63	72	61					
-Y6- (RT)	10+11.00	11+98.00	8				8	18	18	21	13					
		SUBTOTAL	1776	0	0	0	1776	1138	0	1138	1309	928	0	1395	0	1395
		SHEET TOTAL	6157	0	0	0	6157	21388	0	21388	24596	21049	0	2610	0	2610

NOTE: EARTHWORK QUANTITIES ARE CALCULATED BY THE ROADWAY DESIGN UNIT. THESE EARTHWORK QUANTITIES ARE BASED IN PART ON SUBSURFACE DATA PROVIDED BY THE GEOTECHNICAL ENGINEERING UNIT.

