



6/2/2023

| PAVEMENT SCHEDULE | |
|-------------------|---|
| A1 | 6" JOINTED CONCRETE PAVEMENT REINFORCED WITH WIRE MESH (SIZE 4x4 W3xW3). |
| A2 | 7" JOINTED CONCRETE TRUCK APRON REINFORCED WITH WIRE MESH (SIZE 4x4 W3.5xW3.5). |
| C1 | PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD. IN EACH OF TWO LAYERS. |
| D1 | PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD. |
| E1 | PROP. APPROX. 3" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD. |
| E2 | PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD. |
| R1 | 1'-6" CONCRETE CURB AND GUTTER. |
| R2 | 2'-6" CONCRETE CURB AND GUTTER. |
| R3 | 9" X 12" CONCRETE CURB. |
| R4 | 5" MONOLITHIC CONCRETE ISLAND. |
| K | PROP. 18" CLASS IV SUBGRADE STABILIZATION. |
| N | GEOTEXTILE FOR SOIL STABILIZATION. |
| S | 4" CONCRETE SIDEWALK. |
| T | EARTH MATERIAL. |
| U | EXISTING PAVEMENT. |
| V | INCIDENTAL MILLING. |
| W | VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAIL). |


NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




TYPICAL SECTION NO. 5
SEE PLANS FOR ISLAND LOCATIONS
USE TYPICAL SECTION NO. 5
-L2- STA. 87+75.00 TO -L2- STA. 88+47.55



TYPICAL SECTION NO. 6
USE -RA_X_OEOT- FOR VAR. DIMENSIONS
SEE SHEET 2B-1 FOR ALIGNMENT DATA
USE TYPICAL SECTION NO. 6
-Y1A- STA. 10+25.00 TO -Y1A- STA. 11+95.70
-Y1B- STA. 10+68.59 TO -Y1B- STA. 13+00.00



TYPICAL SECTION NO. 7
NOTE: GRADE DRIVEWAY TO DRAIN
USE TYPICAL SECTION NO. 7
-DR1- STA. 10+10.00 TO -DR1- STA. 12+12.16



TYPICAL SECTION NO. 8
*SEE PLANS FOR SIDEWALK LOCATIONS
USE TYPICAL SECTION NO. 8
-RA- STA. 10+00.00 TO -RA- STA. 13+60.16

| | |
|--|--|
| PROJECT REFERENCE NO. U-5808 | SHEET NO. 2A-3 |
| ROADWAY DESIGN ENGINEER SEAL 034381 | PAVEMENT DESIGN ENGINEER SEAL 024964 |
| 10/4/2023 | 10/4/2023 |
| DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED | |
| Mead&Hunt | |

04_OCT_2023_15:57
 R:\Projects\U5808\Relay_tup.dgn
 1784.dwg