808

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN UNION COUNTY

LOCATION: SR 1362 (CHESTNUT LANE CONNECTOR) FROM SR 1367 (MATTHEWS INDIAN TRAIL ROAD) TO SR 1368 (GRIBBLE ROAD). CONSTRUCT ROAD ON NEW LOCATION. INTERSECTION OF US 74 AND EXISTING SR 1362 (CHESTNUT LANE CONNECTOR). CONSTRUCT INTERSECTION IMPROVEMENTS.

TIP NO.	SHEET NO.	
U-5808	SIGN-1	
APPROVED: Docusigned by: 2 3 Decol	a	
DATE: 10/9/2023		
SEAL SEAL O34381 OKENO OKE		

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-1A	DETAIL 904D50 IN LIEU OF ROADWAY STD. DRAWING 904.50 SHEET 1 OF 2
SIGN-2	TYPE "E" & "F" SIGNS
SIGN-3-6	EXISTING & PROPOSED SIGNS

			CHAMADU OF OHANTITIES		
ITEM NO.			SUMMARY OF QUANTITIES		
	DESC. NO.	SECT.	ITEM DESCRIPTION	QUANTITY	UNIT
	4072000000	903	SUPPORTS, 3-LB STEEL U-CHANNEL	800	L.F.
	4102000000	904	SIGN ERECTION, TYPE E	60	EA.
	4108000000	904	SIGN ERECTION, TYPE F	6	EA.
	4116100000	904	SIGN ERECTION, RELOCATE TYPE D	1	EA.
	4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11	EA.
	4238000000	907	DISPOSAL OF SIGN, D, E, OR F	1	EA.

GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

<u>STD. NO.</u>	<u>TITLE</u>
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS
910.30	SIGNING SIGNALIZED AND UNSIGNALIZED SUPERSTREET
910.40	SINGLE/TWO LANE ROUNDABOUT WITH PEDESTRIAN

NCDOT CONTACTS	
YANNY MA, PE	DIVISION 10 DM-STIP PROJECT ENGINEER
KELVIN JORDAN	SIGNING & DELINEATION REGIONAL ENGINEER



PLAN PREPARED FOR NCDOT DIVISION 10 BY:

RICK DECOLA, PE PROJECT ENGINEER SURAJ SANGHANI, PE PROJECT DESIGN ENGINEER

Mead&Hunt

111 E. Hargett Street, Suite 300 Raleigh, North Carolina 27601 919-714-8670 | meadhunt.com NC License No. F-1235