

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.204	X-1B

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	0										
L	(cu. yd.)	(cu. yd.)	Dr	(cu. yd.)	(cu. yd.)										
17+00.00	0	0	13+50.00	217	0										
17+25.00	28	0	13+55.00	1	0										
17+50.00	87	0													
18+00.00	425	1	Station	Uncl. Exc.	Embt										
18+50.00	487	1	Dr2	(cu. yd.)	(cu. yd.)										
19+00.00	231	4	10+35.00	0	0										
19+50.00	86	4	10+50.00	25	1										
20+00.00	67	12	11+00.00	134	7										
20+50.00	98	13	11+39.82	82	3										
21+00.00	100	5													
21+50.00	51	88													
22+00.00	41	105													
22+50.00	63	87													
23+00.00	94	282													
23+50.00	54	698													
23+71.00	0	405													
						<div style="border: 1px solid black; padding: 5px; background-color: #f0f0f0;"> Approximate quantities only. Unclassified excavation, shoulder borrow, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading". </div>									
Station	Uncl. Exc.	Embt													
L	(cu. yd.)	(cu. yd.)													
25+45.00	0	0													
25+50.00	11	0													
26+00.00	835	33													
26+50.00	1414	40													
27+00.00	809	29													
27+50.00	201	24													
28+00.00	71	3													
28+50.00	95	0													
29+00.00	86	3													
29+50.00	65	27													
30+00.00	51	73													
30+50.00	37	112													
31+00.00	26	145													
31+50.00	28	163													
32+00.00	63	158													
32+25.00	39	75													
32+50.00	31	75													
33+00.00	57	144													
33+50.00	59	144													
34+00.00	61	144													
34+50.00	37	96													
35+00.00	6	29													
Station	Uncl. Exc.	0													
Dr	(cu. yd.)	(cu. yd.)													
10+12.00	0	0													
10+50.00	3246	0													
11+00.00	4623	0													
11+50.00	3424	0													
12+00.00	1166	93													
12+50.00	409	152													
13+00.00	389	60													