

STRUCTURAL STEEL NOTES

ALL INTERMEDIATE DIAPHRAGM STEEL AND CONNECTOR PLATES SHALL BE AASHTO M270 GRADE 50 OR APPROVED EQUAL.

TENSION ON THE ASTM A325 BOLTS THROUGH THE CHANNEL MEMBER SHALL BE CALIBRATED USING DIRECT TENSION INDICATOR WASHERS IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

TENSION ON THE ASTM A449 BOLTS THROUGH THE GIRDER WEB SHALL BE SNUG TIGHTENED FOLLOWED BY AN ADDITIONAL 1/4 TURN.

THE PLATES, BENT PLATES, CHANNELS, AND ANGLES SHALL BE GALVANIZED OR METALLIZED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. FOR THERMAL SPRAYED COATINGS (METALLIZATION), SEE SPECIAL PROVISIONS.

FOR METALLIZATION, APPLY A THERMAL SPRAYED COATING WITH A SEAL COAT TO ALL STEEL DIAPHRAGM SURFACES IN ACCORDANCE WITH THE DEPARTMENTS THERMAL SPRAYED COATINGS (METALLIZATION) PROGRAM. THERMAL SPRAYED COATINGS SPECIAL PROVISION AND SECTION 442 OF THE STANDARD SPECIFICATIONS.

GALVANIZE THE HIGH STRENGTH BOLTS, NUTS, WASHERS AND DIRECT TENSION INDICATORS IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

USE AN ASTM F436 HARDENED WASHER WITH STANDARD AND SLOTTED HOLES UNDER EACH BOLT HEAD AND NUT.


FOR BOLTS THROUGH THE GIRDER WEB, PROVIDE SUFFICIENT LENGTH OF THREADS ON ALL BOLTS TO ACCOMMODATE WASHERS AND THE THICKNESS OF CONNECTING MEMBER PLUS AT LEAST 1/4" PROJECTION BEYOND THE NUT.

INTERMEDIATE DIAPHRAGM ASSEMBLY SHALL COMPLY WITH SECTION 1072 OF THE STANDARD SPECIFICATIONS.

SUBMIT TWO SETS OF WORKING DRAWINGS FOR THE INTERMEDIATE DIAPHRAGM ASSEMBLY FOR REVIEW, COMMENTS AND ACCEPTANCE. AFTER REVIEW, COMMENTS, AND ACCEPTANCE, SUBMIT SEVEN SETS FOR DISTRIBUTION.

IN THE EXTERIOR BAYS, PLACE TEMPORARY STRUTS BETWEEN PRESTRESSED GIRDERS ADJACENT TO THE STEEL DIAPHRAGMS. STRUTS SHALL REMAIN IN PLACE 3 DAYS AFTER CONCRETE IS PLACED.

THE COST OF THE STEEL DIAPHRAGMS AND ASSEMBLIES SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE GIRDERS.



EXTERIOR GIRDER INTERIOR GIRDER

PART SECTION AT INTERMEDIATE DIAPHRAGM (TYPE III OR TYPE IV GIRDER SHOWN)







PLATE DETAILS CHANNEL END



DIAPHRAGM FACE CONNECTOR PLATE DETAILS



CONNECTION DETAILS




BOLT WITH DTI ASSEMBLY DETAIL

TABLE

GIRDER TYPE	CHANNEL SIZE	DIM "A"	DIM "B"	DIM "L"
III	MC 18 x 42.7	1'-5"	1'-2"	1'-6"

GIRDER	DIM. A	DIM. B	DIM. C	DIM. D
GDR. A1	46'-10 1/2"	18'-9 3/8"	-	28'-1 1/8"
GDR. A2	46'-6 5/8"	18'-8 1/4"	9'-2 5/16"	18'-7 1/16"
GDR. A3	46'-2 7/8"	18'-7 3/16"	9'-1 3/16"	18'-6 3/8"
GDR. A4	45'-11 3/8"	27'-5 1/8"	-	18'-6 1/4"
GDR. B1	75'-7 1/8"	32'-7 9/16"	-	42'-11 3/16"
GDR. B2	74'-11 3/8"	32'-4 1/16"	10'-3"	32'-3 1/16"
GDR. B3	74'-4"	32'-2"	10'-1"	32'-1"
GDR. B4	73'-9"	41'-9 1/2"	-	31'-11 1/2"
GDR. C1	46'-8 5/8"	17'-7 1/2"	-	29'-1 1/8"
GDR. C2	46'-2 7/8"	17'-5 7/8"	11'-4 3/8"	17'-4 3/8"
GDR. C3	45'-9 3/8"	17'-4 3/8"	11'-1 1/8"	17'-3 1/8"
GDR. C4	45'-4 1/8"	28'-1 3/16"	-	17'-2 5/16"



LOCATION OF BOLT HOLES IN GIRDERS - SPANS A, B & C

PROJECT NO. 17BP.14.R.204
 JACKSON COUNTY
 STATION: 24+58.00-L-
 SHEET 5 OF 5

Professional Engineer Seal for Marshall G. Dye, Sr., License No. SF80023400415, dated 11/15/2023 | 7:42 AM EST.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
 201 W. MARION ST STE 200
 SHELBY, NC 28150
 PH (704) 476-0003
 CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 INTERMEDIATE
 STEEL DIAPHRAGMS
 FOR TYPE II, III, & IV
 PRESTRESSED CONCRETE
 GIRDERS

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-19
2			4			TOTAL SHEETS 47

ASSEMBLED BY : JLA	DATE : 9/22
CHECKED BY : MGC	DATE : 10/22
DRAWN BY : TLA	REV. 5/1/06RR KMM/GM
CHECKED BY : VC	REV. 10/1/11 MAA/GM
	REV. 12/17 MAA/THC