

DRAWN BY :	M. HOGAN		DATE	: .	3/2023
CHECKED BY :	JIA XU		DATE	: .	7/2023
DESIGN ENGINEER	OF RECORD:F	ASEFNIA	DATE	:.	11/2023

AS-BUILT REPAIR QUANTITY TABLE							
	QUANTITIES						
BENT 2 SPAN B FACE	ESTIMATE		ACTUAL				
SHOTCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF			
САР	92.5	23.0					
COLUMN	60.0	15.0					
CONCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF			
САР	0.0	0.0					
EPOXY RESIN INJECTION		LN.FT.		LN.FT.			
САР		58.0					
COLUMN		2.5					
EPOXY COATING		SQ.FT.	SQ.FT.				
TOP OF BENT CAP	409.0						

## NOTES:

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIRS QUANTITY TABLE.

CLEAN AND REMOVE DEBRIS FROM THE TOP OF THE CAP AND APPLY EPOXY PROTECTIVE COATING. EPOXY COATING SHALL BE APPLIED TO THE TOP SURFACE OF THE CAP. THE CONTRACTOR SHALL NOT COAT THE AREA OF THE CAP BENEATH THE MASONARY PLATES. FOR EPOXY COATING, SEE SPECIAL PROVISIONS.

SHOTCRETE REPAIRS MAY BE REPLACED WITH CONCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR CAP AND COLUMN REPAIRS, SEE "TYPICAL CAP AND COLUMN REPAIR DETAILS", SHEET.

FOR SHOTCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR CONCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISIONS.

SHOTCRETE REPAIR (SCR)



CONCRETE REPAIR (CR)

EPOXY RESIN INJECTION (ERI)

	PROJECT NO.		I	I-5941	
	[	DURH	IAM	CO	UNTY
	BRIDGE	NO.	31	0429	
	SHEET 4 OF	10			
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED Docusigned by: Hargin Aschrite 19141A6AF2END TH CAROL SEAL 20103 MGINEER	depar Sui	stati TMENT BSTRU	e of north card OF TRAN raleigh JCTURE	NSPORTA	IR
11/13/2023	REVISIONS SHEET NO.				
3362 Six Forks Rd. Raleigh, N.C. 27609	NO. BY:	DATE:	NO. BY:	DATE:	S5-11
E.L. ROBINSON E N G I N E E R I N G E N G I N E E R I N G License: C-22 9	1		3 4		total sheets 17