


TOP OF CAP



ELEVATION

END VIEW

BENT NO. 4  
SPAN D FACE

AS-BUILT REPAIR QUANTITY TABLE				
BENT 4 SPAN D FACE	QUANTITIES			
	ESTIMATE		ACTUAL	
SHOTCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF
CAP	74.0	19.0		
COLUMN	72.0	18.0		
CONCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF
CAP	5.0	1.3		
EPOXY RESIN INJECTION	LN. FT.		LN. FT.	
CAP	7.0			
COLUMN	0.0			
EPOXY COATING	SQ. FT.		SQ. FT.	
TOP OF BENT CAP	409.0			

NOTES:

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CLEAN AND REMOVE DEBRIS FROM THE TOP OF THE CAP AND APPLY EPOXY PROTECTIVE COATING. EPOXY COATING SHALL BE APPLIED TO THE TOP SURFACE OF THE CAP. THE CONTRACTOR SHALL NOT COAT THE AREA OF THE CAP BENEATH THE MASONRY PLATES. FOR EPOXY COATING, SEE SPECIAL PROVISIONS.

SHOTCRETE REPAIRS MAY BE REPLACED WITH CONCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR CAP AND COLUMN REPAIRS, SEE "TYPICAL CAP AND COLUMN REPAIR DETAILS", SHEET.

FOR SHOTCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR CONCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISIONS.

- SHOTCRETE REPAIR (SCR)
- CONCRETE REPAIR (CR)
- EPOXY RESIN INJECTION (ERI)

PROJECT NO. I-5941  
DURHAM COUNTY  
 BRIDGE NO. 310429

SHEET 8 OF 10

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED DocuSigned by:  NORTH CAROLINA PROFESSIONAL SEAL 20103 ENGINEER FARZIN ASEFNIA 11/13/2023	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH	
	SUBSTRUCTURE REPAIR BENT 4 SPAN D FACE	
REVISIONS		SHEET NO. S5-15
NO. 1 BY: [ ] DATE: [ ]	NO. 2 BY: [ ] DATE: [ ]	TOTAL SHEETS 17

DRAWN BY : M. HOGAN DATE : 3/2023  
 CHECKED BY : JIA XU DATE : 7/2023  
 DESIGN ENGINEER OF RECORD: F. ASEFNIA DATE : 11/2023

E.L. ROBINSON  
 3362 Old Park Rd.  
 Raleigh, N.C. 27609  
 Tel: 984.980.2810  
 efr@elrobinsonengineering.com  
 License: C-22 9