PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.12.05.20491	17	

THERMOPLASTIC AND PAINT QUANTITIES

													4413000000-E	4447000000-E	4457000000-N	4685000000-E		4695000000-E		4709000000-E	4725000000-E						4810000000-E		4905100000-N
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK SONE ADVANCE/GENERAL WARNING SIGNING	PEDESTRIAN CHANNELIZING DEVICES	TEMPORARY TRAFFIC CONTROL	THERMOPLASTIC PAVEMENT MARKING LINES WHITE (4", 90 MILS)	THERMOPLASTIC PAVEMENT MARKING LINES YELLOW (4", 90 MILS)	THERMOPLASTIC PAVEMENT MARKING LINES YELLOW (8", 90 MILS)	THERMOPLASTIC PAVEMENT MARKING LINES WHITE (8", 90 MILS)	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	THERMO LT ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO STR ARROW 90 M	THERMO MERGE ARROW (90 MILS)	THERMO RT ARROW 90 M	THERMO STR & LT ARROW 90 M	4" WHITE PAINT	4" YELLOW PAINT	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKER
								MI	FT			SF	LF	LS	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	LF	LF	EA
2024CPT.12.05.20491	Iredell	1	SR-1446 / COOLEY RD	FROM SR 1445 (KEMP RD.) TO DEAD END	1	2		0.261	18	1.757	2.018	30														6,040	6,040	
TOTAL FOR MAP NO. 1								**0.261**				**30**														**6,040**	**6,040**	
2024CPT.12.05.20491	Iredell	2	SR-1445 / KEMP RD	FROM SR 1446 (COOLEY RD.) TO SR 1115 (MCKENDREE RD.)	1	2		0.721	20	0	0.721	80														16,750	16,750	
TOTAL FOR MAP NO. 2								**0.721**				**80**														**16,750**	**16,750**	
2024CPT.12.05.20491	Iredell	3	SR-2923 / CHATWORTH LN	FROM SR 1179 (CANVASBACK RD.) TO CUL-DE-SAC	1	2		0.069	20	0	0.069	16																
TOTAL FOR MAP NO. 3								**0.069**				**16**																
2024CPT.12.05.20491	Iredell	4	SR-2361 / MCNESS RD	FROM SR 2638 (SALISBURY HWY.) TO END OF MAINTANANCE	1	2		0.076	24	0	0.076	16																
TOTAL FOR MAP NO. 4								**0.076**				**16**																
2024CPT.12.05.20491	Iredell	5	SR-2141 / DUNLAP GATE RD	FROM US 21 TO SR 2158 (OLD MOCKSVILLE RD.)	1	2		1.504	20	0	1.504	168														34,850	34,850	
TOTAL FOR MAP NO. 5								**1.504**				**168**														**34,850**	**34,850**	
2024CPT.12.05.20491	Iredell	6	SR-2366 / PERRY RD./HOOVER RD./CREEKS EDGE LN	FROM US 21 TO CUL-DE-SAC	1	2		1.582	20	0	1.582	177														33,400	33,400	
TOTAL FOR MAP NO. 6								**1.582**				**177**														**33,400**	**33,400**	
2024CPT.12.05.20491	Iredell	7	SR-1916 / LENTZ RD	FROM SR 1890 (TOMLIN MILL RD.) TO SR 1892 (JENNINGS RD.)	1	2		1.956	20	0	1.956	220														45,535	45,535	
TOTAL FOR MAP NO. 7								**1.956**				**220**														**45,535**	**45,535**	
2024CPT.12.05.20491	Iredell	8	SR-1873 / N CHIPLEY FORD RD	FROM SR 1896 (FRIENDSHIP RD.) TO SR 1898 (DOBSON FARM RD)	1	2		2.031	20	0	2.031	228														47,160	47,160	
TOTAL FOR MAP NO. 8								**2.031**				**228**														**47,160**	**47,160**	
2024CPT.12.05.20491	Iredell	9	SR-1898 / N CHIPLEY FORD RD	FROM SR 1873 (NORTH CHIPLEY FORD RD.) TO SR 1903 (SNOW CREEK RD.)	1	2		1.743	20	2.39	4.133	195		1												40,425	40,425	
TOTAL FOR MAP NO. 9								**1.743**				**195**														**40,425**	**40,425**	
2024CPT.12.05.20491	Iredell	10	SR-1328 / EAST MONBO RD	FROM SR 1005 (OLD MOUNTAIN RD.) TO SR 2801 (HIGHLAND VIEW DR.)	2, 4	2		4.91	20	0	4.91	550														111,000	111,000	
TOTAL FOR MAP NO. 10								**4.91**				**550**														**111,000**	**111,000**	
2024CPT.12.05.20491	Iredell	11	SR-1903 / SNOW CREEK RD	FROM NC 115 TO SR 1892 (JENNINGS RD.)	3	2		4.555	20	0	4.555	515														106,000	106,000	
TOTAL FOR MAP NO. 11								**4.555**				**515**														**106,000**	**106,000**	
2024CPT.12.05.20491	Iredell	12	SR-1005 / OLD MOUNTAIN RD	FROM ALEXANDER COUNTY LINE TO BRIDGE #90 OVER I-40	2	2		5.732	20	0	5.732	650			66,600	66,600	150		48									625
TOTAL FOR MAP NO. 12								**5.732**				**650**			**66,600**	**66,600**	**150**		**48**									**625**
2024CPT.12.05.20491	Iredell	13	SR-2321 OI / E BROAD ST	FROM I-3819B PROJECT LIMITS TO SR 2320 (S.GREENBRIAR)	2, 4, 5	2		1.51	20	1.973	3.483	170			18,662	19,250	195	182	150	12	4	4	3					200
TOTAL FOR MAP NO. 13								**1.51**				**170**			**18,662**	**19,250**	**195**	**182**	**150**	**12**	**4**	**4**	**3**					**200**
2024CPT.12.05.20491	Iredell	14	SR-2333 / EASTSIDE DR	FROM I-3819B PROJECT LIMITS TO SR 2735 (SALISBURY RD.)	2, 5, 6, 7	2		1.04	22	0.124	1.164	120			12,125	12,250	154		110	15				9				150
TOTAL FOR MAP NO. 14								**1.04**				**120**			**12,125**	**12,250**	**154**		**110**	**15**				**9**				**150**
2024CPT.12.05.20491	Iredell	15	SR-1245 / MEDICAL PARK RD	FROM US 21 TO SR 1246 (FAIRVIEW RD)	4, 5, 6, 8	2		0.601	35	0	0.601	70			6,350	7,615	150	22	209	22	4			3				100
TOTAL FOR MAP NO. 15								**0.601**				**70**			**6,350**	**7,615**	**150**	**22**	**209**	**22**	**4**			**3**				**100**
2024CPT.12.05.20491	Iredell	16	SR-1421 / WILSON W LEE BLVD	FROM SR 1338 (WALLACE SPRINGS RD.) TO PAVEMENT CHANGE NORTH OF US 70	2, 9	2		0.701	30	0.251	0.952	80	50		900	10,200		160	250		4			2	4			100
TOTAL FOR MAP NO. 16								**0.701**				**80**	**50**		**900**	**10,200**		**160**	**250**		**4**			**2**	**4**			**100**
TOTAL FOR PROJ NO. 2024CPT.12.05.20491								**28.992**				**3,285**	**50**	**1**	**104,637**	**115,915**	**649**	**364**	**767**	**49**	**12**	**4**	**3**	**14**	**4**	**441,160**	**441,160**	**1,175**
															220,552		**1,013**			**86**						**882,320**		
GRAND TOTAL								**28.992**				**3,285**	**50**	**1**	**104,637**	**115,915**	**649**	**364**	**767**	**49**	**12**	**4**	**3**	**14**	**4**	**441,160**	**441,160**	**1,175**
															220,552		**1,013**			**86**						**882,320**		