

PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.08.14.20761	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1575000000-E	1704000000-E	1775500000-E	1838000000-E	1838500000-N	2143000000-E
														SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	1.5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	BLOTTING SAND
											MI	FT												
											SMI	TON	SY	SY	TONS	TONS	TONS	SY	GAL	WK	TON			
2024CPT.08.14.20761	Randolph	1	SR-2459 / SANDY CREEK CHURCH RD	FROM SR 2436 (WALL RD) TO SR 2440 (BROWER MEADOW RD)	1	2	2WU	NO	NO	2.83	23	1	3.83	5.66	795		1,040	3,545	244	276				
TOTAL FOR MAP NO. 1										2.83				5.66	795		1,040	3,545	244	276				
2024CPT.08.14.20761	Randolph	2	SR-2419 / E BUTLER AVE	FROM SR 1006 (N GREENSBORO ST) TO ALAMANCE COUNTY LINE	2	2	2WU	NO	NO	2.16	23	0	2.16	4.32	607		1,820	2,415	164	150	29,274	11,710	1.00	5
TOTAL FOR MAP NO. 2										2.16				4.32	607		1,820	2,415	164	150	29,274	11,710	1.00	5
2024CPT.08.14.20761	Randolph	3	SR-2425 / FLYNT RD	FROM SR 2424 (SILK HOPE RD) TO SR 2464 (PIKE FARM RD)	1	2	2WU	NO	NO	1.672	21	0	1.672	3.00	469		260	1,907	136	250				
TOTAL FOR MAP NO. 3										1.672				3.00	469		260	1,907	136	250				
2024CPT.08.14.20761	Randolph	4	SR-2427 / KINRO RD	FROM SR 1006 (OLD 421 RD) TO NC 49	2	2	2WU	NO	NO	0.498	20	0	0.498	1.00	140		520	612	47	150	5,867	2,347	0.15	1
TOTAL FOR MAP NO. 4										0.498				1.00	140		520	612	47	150	5,867	2,347	0.15	1
2024CPT.08.14.20761	Randolph	5	SR-1002 / FORK CREEK MILL RD	FROM SR 1003 (ERECT RD) TO SR 2907 (LITTLE BEANE STORE RD)	1	2	2WU	NO	NO	2.242	20	6.79	9.032	5.00	635	150	650	2,507	173	200				
TOTAL FOR MAP NO. 5										2.242				5.00	635	150	650	2,507	173	200				
2024CPT.08.14.20761	Randolph	6	SR-1003 / ERECT RD	FROM SR 1002 (FORK CREEK MILL RD) TO NC 42	2	2	2WU	NO	NO	5.13	21	3.56	8.69	10.00	1,441		910	5,875	401	400	63,203	25,290	3.00	10
TOTAL FOR MAP NO. 6										5.13				10.00	1,441		910	5,875	401	400	63,203	25,290	3.00	10
TOTAL FOR PROJ NO. 2024CPT.08.14.20761										14.532				28.98	4,087	150	5,200	16,861	1,165	1,426	98,344	39,347	4.15	16
GRAND TOTAL										14.532				28.98	4,087	150	5,200	16,861	1,165	1,426	98,344	39,347	4.15	16