

PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.09.05.10341		
2024CPT.09.06.20341		16

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGT H	WIDT H	BEGIN MP	END MP	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1523000000-E	1524200000-E	1575000000-E	1577000000-E	1704000000-E	1881000000-E	2830000000-N	2845000000-N	5255000000-N			
														INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	MILLING ASPHALT PAVEMENT, 1 1/2" DEPTH	INCIDENTAL MILLING	ASPHALT SURFACE COURSE, S9.5B	ASPHALT SURFACE COURSE, S9.5C	ASPHALT SURFACE COURSE, S9.5D	ASPHALT BINDER FOR PLANT MIX	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	GENERIC PAVING ITEM (SINUSOIDAL RUMBLE STRIPS)	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOX	PORTABLE LIGHTING			
														MI	FT																
														TONS	SMI	TON	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	LF	EA	EA	LS			
2024CPT.09.05.10341	Forsyth	1	US-421 N	FROM PVT JOINT N OF WILLIAMS RD SR1173 TO YADKIN COUNTY LINE BRG#055	1	2,3	MD	NO	NO	4.13	32	23.5	27.63		8.26	1,594	82,013			7,952		470		10	43,613						
TOTAL FOR MAP NO. 1														4.13		8.26	1,594	82,013			7,952		470		10	43,613					
2024CPT.09.05.10341	Forsyth	2	US-421 S	FROM YADKIN COUNTY LINE BRG#051 TO PVT JOINT N OF WILLIAMS RD SR1173	1	2,3	MD	NO	NO	4.1	32	0	4.1		8.20	1,583	81,071			7,837		463		10	43,296						
TOTAL FOR MAP NO. 2														4.1		8.20	1,583	81,071			7,837		463		10	43,296					
2024CPT.09.05.10341	Forsyth	3	US-421 N	FROM BRG#359 AT US-158 TO US-158 MERGE	2	2,3	MD	NO	NO	0.155	32	8.995	9.15		0.31	60	1,778				245		14	10	1,637			*			
TOTAL FOR MAP NO. 3														0.155		0.31	60	1,778			245		14	10	1,637						
2024CPT.09.05.10341	Forsyth	4	US-421 S	FROM BRG #358 AT US-158 TO US158 MERGE	2	2,3	MD	NO	NO	0.261	32	18.396	18.657		0.52	101	4,900				413		24	10	2,756						
TOTAL FOR MAP NO. 4														0.261		0.52	101	4,900			413		24	10	2,756						
2024CPT.09.05.10341	Forsyth	5	US-158 W/ US-421N	FROM MP12.6 ON US158 ENTRANCE TO BRG#345 RESEARCH PRKWAY	2,3,4,5	2,3	MD	NO	NO	2.617	26-38	12.6	15.217		5.23	1,010	66,843	1,800			6,881		399	10	27,636						
TOTAL FOR MAP NO. 5														2.617		5.23	1,010	66,843	1,800		6,881		399	10	27,636						
2024CPT.09.05.10341	Forsyth	6	US-158 E/ US-421S	FROM BRG#345 RESEARCH PRKWAY TO MP 15.74 ON US158	2,3,4,5	2,3	MD	NO	NO	2.68	26-38	13.06	15.74		5.36	1,034	63,946	1,427			6,616		384	10	28,301						
TOTAL FOR MAP NO. 6														2.68		5.36	1,034	63,946	1,427		6,616		384	10	28,301						
2024CPT.09.05.10341	Forsyth	7	US-158 / STRATFORD RD	FROM APPROX. MP 7.4 N OF BURKE MILL RD TO APPROX 200' N OF BRG#125 US421/SALEM PRKWAY	6	2,6	MU	NO	NO	3.163	42-70	7.4	10.563				110,658	2,029		10,488		638		400		144	124				
TOTAL FOR MAP NO. 7														3.163				110,658	2,029		10,488		638		400		144	124			
2024CPT.09.05.10341	Forsyth	8	RMP-3383 OI	FROM US-158/ US-421 TO LOWERY CT	7	1,2		NO	NO	0.317	24-36	0	0.317		0.63	122	5,200			564		33									
TOTAL FOR MAP NO. 8														0.317		0.63	122	5,200			564		33								
2024CPT.09.05.10341	Forsyth	9	RMP-3384 OI	FROM LOWERY CT TO US-158/ US-421 MERGE	7	1,2		NO	NO	0.207	24-36	0	0.207		0.41	100	3,643			353		21									
TOTAL FOR MAP NO. 9														0.207		0.41	100	3,643			353		21								
TOTAL FOR PROJ NO. 2024CPT.09.05.10341														17.63		28.93	5,604	420,052	5,256		27,194		14,155		1,625	821	460	147,239	144	124	1
2024CPT.09.06.20341	Forsyth	10	SR-2643 / UNION CROSS RD	FROM CLYDE EDGERTON RD TO BRG# 368 AT US-421/ BUS-40	7	2,3	2WU	NO	NO	1.88	25-48	7.33	9.21		3.76	726	41,432	1,648		3,626		228		293		38	54				
TOTAL FOR MAP NO. 10														1.88		3.76	726	41,432	1,648		3,626		228		293		38	54			
2024CPT.09.06.20341	Forsyth	11	SR-2385 / WALKERTOWN-GUTHRIE RD	FROM W MOUNTAIN ST SR2377 TO DARROW RD SR2385	8	2	2WU	NO	NO	2.72	22.5	0	2.72		5.44	1,050	36,914	1,616	3,582			261		578			18				
TOTAL FOR MAP NO. 11														2.72		5.44	1,050	36,914	1,616	3,582		261		578		18					
2024CPT.09.06.20341	Forsyth	12	SR-2624 / WATKINS FORD RD	FROM NC66 TO HIGHPOINT RD SR1003	8	2	2WU	NO	NO	2.6	23	0	2.6		5.20	1,004	36,143	674	3,447			249		513			6				
TOTAL FOR MAP NO. 12														2.6		5.20	1,004	36,143	674	3,447		249		513		6					
TOTAL FOR PROJ NO. 2024CPT.09.06.20341														7.2		14.40	2,780	114,489	3,938	7,029		3,626		738		1,384		38	78		
GRAND TOTAL														24.83		358	43.33	8,384	534,541	9,194	7,029	30,820	14,155	2,363	821	1,844	147,239	182	202	1	

Note: All quantities listed include turn lanes and are estimates; Payment will be based on actual field quantities recieved