PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.07.13.20011, 2024CPT.07.13.20411	14	

THERMOPLASTIC AND PAINT QUANTITIES

													4413000000-E	4457000000-N	4510000000-N	4685000000-E		4688000000-E		4695000000-E		4700000000-E	4709000000-E	4720000000-E					4725000000-E				4905100000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	12" X 90 M YELLOW THERMO	24" X 90 M WHITE THERMO	THERMO MSG ONLY 90 M	THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	THERMO MSG SCHOOL 90 M	THERMO MSG YIELD 90 M	THERMO LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR & RT ARROW 90 M	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKERS CRYSTAL/RED	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKERS YELLOW/YELLOW
								MI	FT			SF	LS	HR	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2024CPT.07.13.20011	Alamance	1	SR-1133 / BRICK CHURCH RD	FROM GUILFORD COUNTY LINE TO NC 62	1	2		0.57	22	0.07	0.64				6,100	5,000																	
TOTAL FOR MAP NO. 1								**0.57**							**6,100**	**5,000**																	
TOTAL FOR PROJ NO. 2024CPT.07.13.20011								**0.57**							**6,100**	**5,000**																	
															11,100																		
2024CPT.07.13.20411	Guilford	2	SR-3040 / WAGONER BEND RD	FROM SR 4762 - OLD BURLINGTON RD TO PVMT JOINT	1	2		0.09	19	0	0.09				920	920																	
TOTAL FOR MAP NO. 2								**0.09**							**920**	**920**																	
2024CPT.07.13.20411	Guilford	3	SR-4762 / OLD BURLINGTON RD	FROM US 70 - BURLINGTON RD TO DEAD END	1, 2	2		0.89	26	0	0.89				9,500	9,500	100				200							2					
TOTAL FOR MAP NO. 3								**0.89**							**9,500**	**9,500**	**100**				**200**							**2**					
2024CPT.07.13.20411	Guilford	4	SR-3143 / MILLSTREAM RD	FROM SR 3000 - MCCONNELL RD TO SR 3056 - ROCK CREEK DAIRY RD	2	2		3.91	24	0	3.91	433			28,775	42,000	410				650	125	8					11	7	7	2		
TOTAL FOR MAP NO. 4								**3.91**				**433**			**28,775**	**42,000**	**410**				**650**	**125**	**8**					**11**	**7**	**7**	**2**		
2024CPT.07.13.20411	Guilford	5	SR-3045 / MT HOPE CHURCH RD	FROM PVMT JOINT TO 2 LANE SECTION	2	4		1.07	24	2.22	3.29			160	15,500	8,800	1,000	100			750	600	4					19	28	3	14	208	78
2024CPT.07.13.20411	Guilford	5	SR-3045 / MT HOPE CHURCH RD	FROM 2 LANE SECTION TO 200' SOUTH OF BRIDGE #209	3	2		0.22	23	3.29	3.51				2,500	2,500	30															76	18
TOTAL FOR MAP NO. 5								**1.29**						**160**	**18,000**	**11,300**	**1,030**	**100**			**750**	**600**	**4**					**19**	**28**	**3**	**14**	**284**	**96**
2024CPT.07.13.20411	Guilford	6	SR-3124 / STEWART MILL RD	FROM SR 3045 - MT HOPE CHURCH RD TO BEGINNING OF CURB & GUTTER	1	2		0.15	22	0	0.15																						
2024CPT.07.13.20411	Guilford	6	SR-3124 / STEWART MILL RD	BEGINNING OF CURB & GUTTER TO JOINT NEAR END OF CURB & GUTTER	2	2		0.17	24	0.15	0.32																						
TOTAL FOR MAP NO. 6								**0.32**																									
2024CPT.07.13.20411	Guilford	7	SR-3066 / WHEELER BRIDGE RD	FROM SR 3068 - ELMDALE RD TO PVMT JOINT	1	2		0.09	20	0	0.09				2,000	1,800																	
TOTAL FOR MAP NO. 7								**0.09**							**2,000**	**1,800**																	
2024CPT.07.13.20411	Guilford	8	SR-3068 / ELMDALE RD	FROM END MAINT TO END MAINT	1	2		0.49	18	0	0.49																						
TOTAL FOR MAP NO. 8								**0.49**																									
2024CPT.07.13.20411	Guilford	9	SR-3069 / INGLE DAIRY RD	FROM SR 3068 - ELMDALE RD TO PVMT JOINT AT EOM	1	2		0.14	25	0	0.14																						
TOTAL FOR MAP NO. 9								**0.14**																									
2024CPT.07.13.20411	Guilford	10	SR-3293 / CARRIAGE WAY	FROM SR 3069 - INGLE DAIRY RD TO CUL DE SAC	1	2		0.10	20	0	0.1																						
TOTAL FOR MAP NO. 10								**0.10**																									
2024CPT.07.13.20411	Guilford	11	SR-3294 / INGLEWOOD RD	FROM SR 3293 - CARRIAGE WAY TO DEAD END	1	2		0.22	20	0	0.22																						
TOTAL FOR MAP NO. 11								**0.22**																									
2024CPT.07.13.20411	Guilford	12	SR-3255 / JEANNIE RD	FROM SR 3093 - OLD JULIAN RD TO CUL DE SAC	1	2		0.38	19	0	0.38																						
TOTAL FOR MAP NO. 12								**0.38**																									
2024CPT.07.13.20411	Guilford	13	SR-3256 / CORBETT RD	FROM SR 3255 - JEANNIE RD TO END MAINT	1	2		0.07	20	0	0.07																						
TOTAL FOR MAP NO. 13								**0.07**																									
2024CPT.07.13.20411	Guilford	14	SR-3188 / LONG MEADOW DR	FROM SR 3056 - ROCK CREEK DAIRY RD TO DEAD END	1	2		0.56	17	0	0.56		1.00																				
TOTAL FOR MAP NO. 14								**0.56**																									
2024CPT.07.13.20411	Guilford	15	SR-3189 / ROCKCLIFFE DR	FROM SR 3188 - LONG MEADOW DR TO SR 3190 - BRIARBROOK RD	1	2		0.34	20	0	0.34																						
TOTAL FOR MAP NO. 15								**0.34**																									
2024CPT.07.13.20411	Guilford	16	SR-3190 / BRIARBROOK RD	FROM SR 3188 - LONG MEADOW DR TO END PVMT	1	2		0.32	16	0	0.32																						
TOTAL FOR MAP NO. 16								**0.32**																									
2024CPT.07.13.20411	Guilford	17	SR-3230 / WINDFIELD RIDGE DR	FROM SR 3108 - SHOE RD TO CUL DE SAC	1	2		0.54	19	0	0.54																						
TOTAL FOR MAP NO. 17								**0.54**																									
2024CPT.07.13.20411	Guilford	18	SR-3246 / THOMAS ARLENDO DR	FROM SR 3108 - SHOE RD TO CUL DE SAC	1	2		0.21	20	0	0.21																						
TOTAL FOR MAP NO. 18								**0.21**																									
2024CPT.07.13.20411	Guilford	19	SR-3241 / HOLLYOAKS CT	FROM SR 3112 - CALM LAKE RD TO CUL DE SAC	1	2		0.14	20	0	0.14																						
TOTAL FOR MAP NO. 19								**0.14**																									
2024CPT.07.13.20411	Guilford	20	SR-3237 / VIOLA DR	FROM SR 3111 - HOLTS STORE RD TO END MAINT	1	2		0.13	20	0	0.13																						
TOTAL FOR MAP NO. 20								**0.13**																									
2024CPT.07.13.20411	Guilford	21	SR-3236 / HARRY CT	FROM SR 3237 - VIOLA DR TO CUL DE SAC	1	2		0.10	20	0	0.1																						
TOTAL FOR MAP NO. 21								**0.10**																									
2024CPT.07.13.20411	Guilford	22	SR-3111 / HOLTS STORE RD	FROM NC 61 TO ALAMANCE COUNTY LINE	1	2		1.46	21	3.21	4.67				16,000	14,500								4	5								
TOTAL FOR MAP NO. 22								**1.46**							**16,000**	**14,500**								**4**	**5**								
2024CPT.07.13.20411	Guilford	23	SR-3116 / NC HIGHWAY 61 S	FROM NC 61 TO NC 62	1	2		0.19	23	0	0.19				1,800	1,800																	
TOTAL FOR MAP NO. 23								**0.19**							**1,800**	**1,800**																	
2024CPT.07.13.20411	Guilford	24	SR-3297 / QUARTERS EDGE DR	FROM SR 3122 - GARRETT STORE RD TO DEAD END	1	2		0.17	20	0	0.17																						
TOTAL FOR MAP NO. 24								**0.17**																									
2024CPT.07.13.20411	Guilford	25	SR-3360 / BOWMAN DAIRY RD	FROM RANDOLPH COUNTY LINE TO SR 3617 - MABLE LN (SKIP NC-62)	1	2		3.57	21	0	3.57	400			37,700	32,700	100																
TOTAL FOR MAP NO. 25								**3.57**				**400**			**37,700**	**32,700**	**100**																
2024CPT.07.13.20411	Guilford	26	SR-3346 / KIMESVILLE RD	FROM SR 1005 - ALAMANCE CHURCH RD TO RANDOLPH COUNTY LINE	1	2		3.87	22	0	3.87	434			41,000	38,000	150																
TOTAL FOR MAP NO. 26								**3.87**				**434**			**41,000**	**38,000**	**150**																
2024CPT.07.13.20411	Guilford	27	SR-3661 / RADER DR	FROM NC 22 TO SR 3662 - RADER CT	1	2		0.49	21	0	0.49																						
TOTAL FOR MAP NO. 27								**0.49**																									
2024CPT.07.13.20411	Guilford	28	SR-3662 / RADER CT	FROM DEAD END TO CUL DE SAC	1	2		0.13	20	0	0.13																						
TOTAL FOR MAP NO. 28								**0.13**																									
2024CPT.07.13.20411	Guilford	29	SR-3330 / SOUTHEAST SCHOOL RD	FROM PVMT JOINT 200' NW OF ROUNDABOUT TO SR 1005 - ALAMANCE CHURCH RD	2	2		3.77	22	0	3.77	423			35,250	43,200	430		550	1,610	1,610	104			5	12	5	12		2			
TOTAL FOR MAP NO. 29								**3.77**				**423**			**35,250**	**43,200**	**430**		**550**	**1,610**	**1,610**	**104**			**5**	**12**	**5**	**12**		**2**			
TOTAL FOR PROJ NO. 2024CPT.07.13.20411								**23.98**				**1,690**		**160**	**190,945**	**195,720**	**2,220**	**100**	**550**	**1,610**	**3,210**	**829**	**12**	**4**	**10**	**12**	**5**	**44**	**35**	**12**	**16**	**284**	**96**
															386,665		**2,320**		**2,160**						**43**				**107**			**380**	
GRAND TOTAL								**24.55**				**1,690**	**1.00**	**160**	**197,045**	**200,720**	**2,220**	**100**	**550**	**1,610**	**3,210**	**829**	**12**	**4**	**10**	**12**	**5**	**44**	**35**	**12**	**16**	**284**	**96**
															397,765		**2,320**		**2,160**						**43**				**107**			**380**	