

| | |
|-------------|-----------|
| PROJECT NO. | SHEET NO. |
| HI-0016 | 3B-2 |

SUMMARY OF QUANTITIES - ROADWAY

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | 000100000-N | 000400000-N | 010600000-E | 124500000-E | 126000000-E | 129700000-E | 129700000-E | 130800000-E | 130800000-E | | | | | | | | | | | |
|---------------------|---------|--------|--------------------|--|--------|-------|-----------|--------------------------------|---------------------------|--------|-------|--------------------|------------------------|-------------------|-------------------------|---------------------------|--------------|-------------|-----------------------|------------------|--|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | MOBILIZATION | CONSTRUCTION SURVEYING | BORROW EXCAVATION | SHOULDER RECONSTRUCTION | AGGREGATE SHOULDER BORROW | 1.5" MILLING | 2" MILLING | 0.75" TO 1.5" MILLING | 1" TO 2" MILLING | | | | | | | | | | | |
| | | | | | | | | | | | | LS | LS | CY | SMI | TON | SY | SY | SY | SY | | | | | | | | | | | |
| | | | | | | | | | | | | MI | FT | | | | | | | | | | | | | | | | | | |
| 49987.3.1 | Robeson | 1 | US 74 WB 2" MILL | FROM 1 MILE EAST OF 41 TO WHITNEY RD | 1 | 2 | 2WD | NO | NO | 2.0 | 24 | | | | | | | 2,104 | | 126,067 | | | | | | | | | | | |
| | | 1 | US 74 WB 1.5" MILL | WHITNEY RD TO EAST OF LUMBER RIVER BRIDGES | 2 | 2 | 2WD | NO | NO | 9.2 | 24 | | | | | | 12,237 | | 52,048 | | | | | | | | | | | | |
| | | 2 | US 74 EB 2" MILL | FROM 1 MILE EAST OF 41 TO EAST OF LUMBER RIVER BRIDGES | 1 | 2 | 2WD | NO | NO | 11.2 | 24 | | | | | | 12,181 | 2,913 | 52,767 | 124,107 | | | | | | | | | | | |
| TOTAL FOR MAP NO. 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| TOTAL FOR MAP NO. 2 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GRAND TOTAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 1 | 1 | 1,570 | 32.83 | 6,555 | 24,418 | 5,017 | 104,815 | 250,174 | | | | | | | | | | | |
| | | | | | | | | | | | | 1 | 1 | 1,570 | 32.83 | 6,555 | 24,420 | 5,020 | 104,815 | 250,175 | | | | | | | | | | | |
| | | | | | | | | | | | | TOTAL FOR DRAINAGE | | 30 | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | PROJECT TOTAL | | 1,600 | | | | | | | | | | | | | | | | | |

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | 133000000-E | 149100000-E | 152300000-E | 157500000-E | 184000000-E | 188000000-E | 188000000-E | 300100000-N | 303000000-E | 304500000-E |
|---------------------|---------|--------|--------------------|--|--------|-------|-----------|--------------------------------|---------------------------|--------|-------|--------------------|---------------------------------------|------------------------------------|------------------------------|---|--|--|-----------------------------------|----------------------|-----------------------------------|
| | | | | | | | | | | | | INCIDENTAL MILLING | ASPHALT CONC BASE COURSE, TYPE B25.0C | ASPHALT CONC SURFACE COURSE, S9.5C | ASPHALT BINDER FOR PLANT MIX | MILLED RUMBLE STRIPS (ASPHALT CONCRETE) | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C (WEDGING COURSE) | ASPHALT CONC SURFACE COURSE, TYPE S9.5C (WEDGING COURSE) | IMPACT ATTENUATOR UNIT, TYPE TL-3 | STEEL BEAM GUARDRAIL | STEEL BEAM GUARDRAIL, SHOP CURVED |
| | | | | | | | | | | | | SY | TONS | TONS | TONS | LF | TONS | TONS | EA | LF | LF |
| | | | | | | | | | | | | MI | FT | | | | | | | | |
| 49987.3.1 | Robeson | 1 | US 74 WB 2" MILL | FROM 1 MILE EAST OF 41 TO WHITNEY RD | 1 | 2 | 2WD | NO | NO | 2.0 | 24 | | | 3,110 | 225 | 15,600 | 330 | 435 | | | |
| | | 1 | US 74 WB 1.5" MILL | WHITNEY RD TO EAST OF LUMBER RIVER BRIDGES | 2 | 2 | 2WD | NO | NO | 9.2 | 24 | | | 13,748 | 811 | 85,090 | | | | | |
| | | 2 | US 74 EB 2" MILL | FROM 1 MILE EAST OF 41 TO EAST OF LUMBER RIVER BRIDGES | 1 | 2 | 2WD | NO | NO | 11.2 | 24 | | | 5,210 | 21,479 | 1,543 | 96,060 | 330 | 435 | | |
| TOTAL FOR MAP NO. 1 | | | | | | | | | | | | | | | | | | | | | |
| TOTAL FOR MAP NO. 2 | | | | | | | | | | | | | | | | | | | | | |
| GRAND TOTAL | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 5,000 | 5,210 | 38,337 | 2,579 | 196,750 | 660 | 870 | 2 | 26,162.5 | 200 |
| | | | | | | | | | | | | 5,000 | 5,210 | 38,340 | 2,580 | 196,750 | 660 | 870 | 2 | 26,162.5 | 200 |

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | 315000000-N | 319500000-N | 321000000-N | 321500000-N | 328700000-N | 331700000-N | 336000000-E | 350300000-E | 350900000-E | 351500000-E |
|---------------------|---------|--------|--------------------|--|--------|-------|-----------|--------------------------------|---------------------------|--------|-------|----------------------------|--------------------------------|---------------------------------|----------------------------------|--------------------------------|-----------------------------------|---------------------------|------------------------------|-----------------------------------|-----------------------------------|
| | | | | | | | | | | | | ADDITIONAL GUARDRAIL POSTS | GUARDRAIL END UNITS, TYPE AT-1 | GUARDRAIL END UNITS, TYPE CAT-1 | GUARDRAIL ANCHOR UNITS, TYPE III | GUARDRAIL END UNITS, TYPE TL-3 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | REMOVE EXISTING GUARDRAIL | WOVEN WIRE FENCE, 47" FABRIC | 4" TIMBER FENCE POSTS, 7'-6" LONG | 5" TIMBER FENCE POSTS, 8'-0" LONG |
| | | | | | | | | | | | | EA | EA | EA | EA | EA | EA | LF | LF | EA | EA |
| | | | | | | | | | | | | MI | FT | | | | | | | | |
| 49987.3.1 | Robeson | 1 | US 74 WB 2" MILL | FROM 1 MILE EAST OF 41 TO WHITNEY RD | 1 | 2 | 2WD | NO | NO | 2.0 | 24 | | | | | | | | | | |
| | | 1 | US 74 WB 1.5" MILL | WHITNEY RD TO EAST OF LUMBER RIVER BRIDGES | 2 | 2 | 2WD | NO | NO | 9.2 | 24 | | | | | | | | | | |
| | | 2 | US 74 EB 2" MILL | FROM 1 MILE EAST OF 41 TO EAST OF LUMBER RIVER BRIDGES | 1 | 2 | 2WD | NO | NO | 11.2 | 24 | | | | | | | | | | |
| TOTAL FOR MAP NO. 1 | | | | | | | | | | | | | | | | | | | | | |
| TOTAL FOR MAP NO. 2 | | | | | | | | | | | | | | | | | | | | | |
| GRAND TOTAL | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 25 | 1 | 12 | 4 | 26 | 30 | 27,870 | 2,220 | 131 | 50 |
| | | | | | | | | | | | | 25 | 1 | 12 | 4 | 26 | 30 | 27,870 | 2,220 | 131 | 50 |