

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

REMOVAL OF EXISTING CONCRETE PAVEMENT

IN SQUARE YARDS

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
L	0+00	1+89	LT	398.39		44.27
L	0+00	1+89	RT	307.94		34.22
L	0+33	2+01	RT	519.61		57.73
L	0+60	9+49	LT	1,932.62		214.74
L	4+01	9+50	RT	821.70		91.30
L	11+39	15+02	MED	2,146.37		238.49
L	13+88	20+73	LT	13,720.96		1,524.55
L	17+69	23+78	RT	5,952.71		661.41
L	23+95	34+50	CL	32,573.31		3,619.26
L	37+50	46+00	CL	24,337.15		2,704.13
L	46+00	48+23	LT/RT	4,408.55		489.84
L	50+88	54+85	LT	9,368.77		1,040.97
L	54+61	68+80	CL	13,610.43		1,512.27
L	62+00	64+21	RT	562.90		62.54
L	68+06	69+01	RT	279.89		31.10
L	71+29	80+47	RT	3,656.38		406.26
L	79+68	81+82	RT	735.14		81.68
L	82+00	85+00	RT	7,175.50		797.28
L	85+00	85+81	RT	171.51		19.06
L	88+06	89+00	LT/RT	557.37		61.93
L	89+00	96+50	RT	20,955.43		2,328.38
L	101+00	101+50	RT	483.84		53.76
L	101+50	107+00	RT	2,888.16		320.91
L	107+00	112+18	RT	2,075.68		230.63
L	112+98	128+35	RT	6,713.85		745.98
L	130+41	135+75	RT	1,617.55		179.73
L	139+49	141+19	RT	5,370.27		596.70
L	143+00	149+50	MED	41,227.38		4,580.82
L	149+50	150+25	MED/LT	4,371.40		485.71
L	172+55	175+40	LT	2,223.82		247.09
L	172+57	178+00	RT	12,799.12		1,422.12
L	176+27	178+00	RT	1,470.61		163.40
L	178+00	179+25	MED	6,574.84		730.54
L	180+11	193+81	MED	15,422.19		1,713.58
L	180+84	194+03	RT	8,064.75		896.08
L	194+58	199+63	MED	3,500.23		388.91
L	195+92	204+12	RT	3,794.15		421.57
					TOTAL	29,198.94

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
L2	204+38	208+43	MED	1,524.60		169.40
L2	208+71	212+75	MED	6,919.95		768.88
L2	215+44	233+50	RT	41,658.81		4,628.76
L2	232+50	240+55	MED	18,232.43		2,025.83
L2	236+52	239+36	RT	1,521.45		169.05
L2	239+67	242+09	RT	4,784.48		531.61
L	242+08	242+43	RT	729.02		81.00
L	242+80	246+61	RT	9,414.91		1,046.10
L	246+80	250+19	RT	7,241.47		804.61
L	251+35	255+13	RT	8,302.78		922.53
L	252+18	256+14	MED	1,924.92		213.88
L	255+38	260+04	RT	11,885.00		1,320.56
L	260+37	280+21	RT	28,912.67		3,212.52
L	272+40	272+71	RT	15.71		1.75
L	278+08	284+56	MED	747.62		83.07
L	281+55	290+18	RT	17,191.10		1,910.12
L	291+08	300+50	RT	10,050.49		1,116.72
L	300+50	300+87	RT	208.23		23.14
					SHEET 2 TOTAL	19,029.51
					SHEET 1 TOTAL	29,198.94
					TOTAL	48,228.46
					SAY	48,230

REMOVAL OF EXISTING ASPHALT PAVEMENT

IN SQUARE YARDS

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
Y1A	10+12	12+00	LT/RT	530.36		58.93
Y1B	10+32	15+02	LT	14,146.43		1,571.83
Y1C	10+94	11+19	RT	51.43		5.71
Y1D	12+15	13+73	RT	3,367.00		374.11
Y1E	11+15	16+39	RT	11,574.44		1,286.05
Y1E	12+77	13+98	LT	867.38		96.38
Y4	10+49	13+43	RT	4,183.15		464.79
Y5	13+25	17+29	RT	8,645.53		960.61
Y5A	12+30	14+77	LT	4,114.13		457.13
Y6	10+45	11+85	RT	2,997.30		333.03
Y25	10+38	12+75	CL	5,316.10		590.68
Y9	11+50	11+75	CL	471.58		52.40
Y10	11+00	11+31	RT	12.25		1.36
Y13	12+20	13+00	LT/RT	729.73		81.08
Y15	13+25	15+75	LT/RT	6,529.90		725.54
Y16	13+00	14+12	LT	1,217.70		135.30
Y16	13+00	15+33	RT	644.49		71.61
Y17	13+00	14+00	LT/RT	2,518.19		279.80
Y17A	11+24	11+50	RT	91.19		10.13
Y23	13+82	16+15	RT	3,456.87		384.10
Y24	15+50	16+00	LT/RT	433.55		48.17
Y24	18+06	23+58	LT/RT	13,016.43		1,446.27
					TOTAL	9,435.02

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
<i>TEMPORARY PAVEMENT:</i>						
L	24+00	34+12	LT	4019.35		446.59
L	16+14	16+82	LT	332.4		36.93
L	66+74	68+07	LT	2638.88		293.21
L	79+68	82+66	LT	2718.12		302.01
L	91+09	92+36	LT	2770.41		307.82
L	106+62	112+14	LT	7137.92		793.10
L	136+94	138+00	RT	850.57		94.51
L	137+12	140+81	LT	1443.43		160.38
L	138+00	139+39	LT	1096.09		121.79
L	141+52	143+00	LT	1162.42		129.16
L	143+00	145+93	LT	2728.49		303.17
L	145+43	149+00	LT	3933.35		437.04
L	177+88	179+01	LT	342.48		38.05
L	185+84	193+81	LT	8263.21		918.13
L	200+19	208+36	LT	8184.88		909.43
L2	236+56	241+56	LT	8424.63		936.07
L	254+62	255+85	LT	2330.35		258.93
L	256+50	268+15	LT	14458.72		1,606.52
L	291+57	298+05	LT	2731.6		303.51
Y13	10+38	13+00	LT	3,776.37		419.60
Y25	10+39	14+05	LT	7,162.64		795.85
					SHEET 1 TOTAL	9,435.02
					SHEET 2 TOTAL	9,611.81
					TOTAL	19,046.83
					SAY	19,050

R:\2024\proj\p_o\N\p-2577A_Rdy_psh03B_ser1es.dgn