

COMPUTED BY: KTB DATE: 1-15-18
 CHECKED BY: JCL DATE: 1-15-18

PROJECT REFERENCE NO. SHEET NO.
 14SP.20441.I X-1A

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

CROSS SECTION SUMMARY
 IN CUBIC YARDS

-L- LOCATION	UNCLASSIFIED EXCAVATION	EMBT
11+00	0	0
11+25	3	1
11+50	5	7
11+75	7	13
12+00	9	15
12+25	26	32
12+50	10	63
12+75	23	38
12+75.12 (BEGIN BRIDGE)	0	0
13+92.86 (END BRIDGE)	0	0
14+00	45	45
14+25	4	3
14+50	9	5
14+75	9	5
15+00	4	7
15+25	3	7
15+50	3	5
15+75	5	3
16+00	8	1
16+25	8	0
16+30	1	0
-Y- LOCATION	UNCLASSIFIED EXCAVATION	EMBT
10+10	0	0
10+25	0	0
10+50	13	1
-DET- LOCATION	UNCLASSIFIED EXCAVATION	EMBT
10+50	0	0
10+75	1	2
11+00	1	5
11+25	0	7
11+50	1	6

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

Approximate quantities only. Unclassified excavation, borrow excavation, clearing and grubbing, fine grading and removal of existing pavement will be paid for at the contract lump sum price for "grading".

7/11/2023, 4:05:16 PM
 \\P01\Hgywood\15_psh03_sum.dgn
 User:smfHzp@rick