



A $1\frac{1}{2}$ DEEP, $\frac{3}{8}$ WIDE CONTRACTION JOINT AT BENT CONTROL LINE SHALL BE SAWED WITHIN 24 HOURS OF POURING THE DECK. THE JOINT SHALL BE FILLED WITH JOINT SEALER MATERIAL. THE JOINT SEALER MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF SECTION 1028-3 OF THE SYANDARD SPECIFICATIONS. OF THE STANDARD SPECIFICATIONS.


METAL STAY-IN-PLACE FORMS SHALL NOT BE WELDED TO THE GIRDER FLANGES IN THE REGION OF THE LINK SLAB.



PLAN AT BENT - LINK SLAB

THE TOP OF THE GIRDER IN THE REGION OF THE LINK SLAB SHALL BE SMOOTH (NOT RAKED) AND FREE OF STIRRUPS, ANCHOR STUDS, DECK FORMWORK ATTACHMENTS, AND OVERHANG FALSEWORK/FORMWORK ATTACHMENTS.





* TO BE SET TO MATCH SLOPE OF BOTTOM OF OVERHANG (17 DRAINS REQUIRED)

TOP OF DRAIN

PLAN OF RECESS

PIPE DETAIL

DRAIN DETAILS

TOP OF FLOOR DRAINS TO BE SET $\frac{3}{8}$ " BELOW SURFACE OF SLAB. 4 - 1/2" SQUARE LUGS TO BE GLUED TO THE P.V.C. PLASTIC PIPE AT EQUAL SPACES AROUND THE PIPE DRAIN APPROXIMATELY 4" FROM THE TOP OF THE PIPE.

SHEET 2 OF 2

THE 6" Ø PVC PLASTIC PIPE AND FITTINGS SHALL BE SCHEDULE 40 AND CONFORM TO ASTM D1785.

> B-4926 PROJECT NO._ LENOIR COUNTY STATION: 35+00.00 -L-

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

SUPERSTRUCTURE TYPICAL SECTION

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Johnson, Mirmiran, & Thompson Inc. 4700 Falls of Neuse Rd, Suite 100, Raleigh, NC, 27609 License No: C-3097

REVISIONS					SHEET NO.
BY:	DATE:	NO.	BY:	DATE:	S2-8
		3			TOTAL SHEETS
		4			39

DATE: 03/2023 DWN. BY: WDC DATE: 03/2023 CHKD. BY: PRG DES. EGR. OF RECORD: PRG DATE: 03/2023

** BASED ON PREDICTED FINAL CAMBER AND THEORETICAL GRADE LINE ELEVATIONS.