

12/06/07

COMPUTED BY: JLC DATE: 01/25/23  
CHECKED BY: BCS DATE: 01/26/23

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO. 1-2513AA/AB  
SHEET NO. 3B-3

I-2513AA

PAVEMENT REMOVAL SUMMARY

Table with 7 columns: SURVEY LINE, STATION, STATION, LOCATION LT/RT/CL, AREA (SF), ASPHALT REMOVAL (SY), CONCRETE REMOVAL (SY). Rows include various stationing and removal amounts, ending with a total of 38,800.00 SF asphalt and 68,000.00 SY concrete.

SUMMARY OF WOVEN WIRE FENCE, 47" FABRIC

Table with 5 columns: STATION TO STATION, LT. OR RT., FABRIC (LF), 4" POSTS (EA), 5" POSTS (EA). Rows include stationing like -Y5RPA- 15+05 TO 18+06, totaling 6,600 LF fabric, 395 4" posts, and 150 5" posts.

SUMMARY OF CONCRETE BARRIER

Table with 7 columns: SURVEY LINE, STATION, STATION, LOCATION LT/RT/CL, SINGLE FACED BARRIER (LF), SINGLE SLOPE BARRIER (LF), CONC. BARRIER TRANSITION (EA). Rows include stationing like -Y- 48+16.00, totaling 2,803.3 SF single faced barrier, 415.0 SF single slope barrier, and 6 transitions.

SUMMARY OF 4" SHOULDER DRAINS

Table with 7 columns: LINE, BEG STATION, END STATION, SHOULDER DRAIN PIPE (LF), SHOULDER DRAINS (LF), OUTLET PIPE (LF), CONC PADS (EA). Rows include stationing like -Y- RT (EB, OUTSIDE) 18+80.00, totaling 11,300 LF shoulder drains, 270 LF outlet pipes, and 5 pads.

I-2513AB

PAVEMENT REMOVAL SUMMARY

Table with 7 columns: SURVEY LINE, STATION, STATION, LOCATION LT/RT/CL, AREA (SF), ASPHALT REMOVAL (SY), CONCRETE REMOVAL (SY). Rows include stationing like -Y5LPB- 21+70.00, totaling 17,007.87 SF asphalt and 17,050.00 SY concrete.

SUMMARY OF WOVEN WIRE FENCE, 47" FABRIC

Table with 5 columns: STATION TO STATION, LT. OR RT., FABRIC (LF), 4" POSTS (EA), 5" POSTS (EA). Rows include stationing like -RPC- 22+70 TO 36+45, totaling 1,700 LF fabric, 98 4" posts, and 45 5" posts.

SUMMARY OF CONCRETE BARRIER

Table with 7 columns: SURVEY LINE, STATION, STATION, LOCATION LT/RT/CL, SINGLE FACED BARRIER (LF), SINGLE SLOPE BARRIER (LF), CONC. BARRIER TRANSITION (EA). Rows include stationing like -Y5RPA- 21+56.84, totaling 1,677.0 SF single faced barrier, 1680 SF single slope barrier, and 0 transitions.

GRAND TOTALS (I-2513AA & I-2513AB)

PAVEMENT REMOVAL SUMMARY

Summary table for Pavement Removal: I-2513AA (38,800.00 SF asphalt, 68,000.00 SY concrete), I-2513AB (17,050.00 SF asphalt, 17,050.00 SY concrete), TOTAL (55,850.00 SF asphalt, 85,050.00 SY concrete).

SUMMARY OF 4" SHOULDER DRAINS

Summary table for 4" Shoulder Drains: I-2513AA (11,300 LF shoulder drains, 270 LF outlet pipes, 5 pads), I-2513AB (11,300 LF shoulder drains, 270 LF outlet pipes, 5 pads), TOTAL (22,600 LF shoulder drains, 540 LF outlet pipes, 10 pads).

SUMMARY OF WOVEN WIRE FENCE, 47" FABRIC

Summary table for Woven Wire Fence: I-2513AA (6,600 LF fabric, 395 4" posts, 150 5" posts), I-2513AB (1,700 LF fabric, 100 4" posts, 45 5" posts), TOTAL (8,300 LF fabric, 495 4" posts, 195 5" posts).

SUMMARY OF CONCRETE BARRIER

Summary table for Concrete Barrier: I-2513AA (2,803.3 SF single faced barrier, 420 SF single slope barrier, 6 transitions), I-2513AB (1,680 SF single faced barrier, 1680 SF single slope barrier, 0 transitions), TOTAL (4,483.3 SF single faced barrier, 2,100 SF single slope barrier, 6 transitions).

12/13/04  
12/13/04  
12/13/04