

PROJECT NO.	SHEET NO.
2024CPT.13.14.20811	20

THERMOPLASTIC AND PAINT QUANTITIES

MAP NO	ROUTE	DESCRIPTION	TYP NO	472500000-E				484600000-E		485000000-E	489000000-E			
				LENGTH	WIDTH	BEGIN MP	END MP	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) LT ARROW	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) RT ARROW	POLYUREA PAVEMENT MARKING LINES (4", 20 MILS) (WHITE) (STANDARD GLASS BEADS)	POLYUREA PAVEMENT MARKING LINES (4", 20 MILS) (YELLOW) (STANDARD GLASS BEADS)	REMOVAL OF PAVEMENT MARKING LINES (4")	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 55 MILS) (WHITE)	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 55 MILS) (YELLOW)
								EA	EA	LF	LF	LF	LF	LF
1	SR 1814 (RIVERSIDE DRIVE)	FROM SR 1901 (OLD CAROLEEN ROAD) TO US 74 BUSINESS	2	0.69	22.00	0.00	0.69	3	2			7,436	7,286	
2	SR 1901 (ARLINGTON ST/OLD CAROLEEN ROAD)	FROM US 74 BUSINESS TO END OF 24' WIDE ROAD	1, 3, 4	2.39	24.00	0.01	2.40	1	1	742	742	1,484	17,306	23,792
3	SR 1905 (COFFEY ROAD)	FROM SR 1906 (MOUNT PLEASANT CHURCH ROAD) TO END OF MAINTENANCE	6	0.34	18.00	0.00	0.34							
4	SR 1906 (MOUNT PLEASANT CHURCH ROAD)	FROM SR 1901 (OLD CAROLEEN ROAD) TO US 221 ALTERNATE	1	1.56	18.00	0.01	1.57					16,474	12,923	
5	SR 1909 (C H HAMRICK ROAD)	FROM SR 1910 (BAXTER CEMETERY ROAD) TO END OF MAINTENANCE	6	0.52	19.00	0.01	0.53							
6	SR 1920 (ELLENBORO HENRIETTA ROAD)	FROM US 74 BUSINESS TO SR 1920 (SOUTH PEA RIDGE ROAD)	1, 3	4.16	24.50	0.01	4.17	1	1	892	892	1,784	39,208	12,995
7	SR 1921 (RACE PATH CHURCH ROAD)	FROM NC 120 HIGHWAY TO PAVEMENT CHANGE AT RAIL ROAD CROSSING	1	3.08	20.00	0.01	3.09			452	452	904	32,525	27,621
8	SR 1954 (ELLENBORO HENRIETTA ROAD)	FROM US 221 ALTERNATE TO SR 1960 (SOUTH PEA RIDGE ROAD)	1	0.61	20.00	0.02	0.63						6,442	6,442
9	SR 1960 (SOUTH PEA RIDGE ROAD)	FROM SR 1920 (NORTH MAIN STREET) TO US 221 ALTERNATE	1	0.84	20.00	0.01	0.85						8,870	8,870
10	SR 1974 (FAIRVIEW ROAD)	FROM SR 1003 (BOILING SPRINGS ROAD) TO END OF MAINTENANCE	6	0.16	17.50	0.01	0.17							
11	SR 1978 (KIRBY ROAD)	FROM CLEVELAND COUNTY LINE TO SR 1993 (OLD US 221 ALTERNATE HIGHWAY)	1	0.84	18.50	0.01	0.85						8,976	8,976
12	SR 1982 (BUGGER HOLLOW ROAD)	FROM SR 1921 (RACE PATH CHURCH ROAD) TO SR 1920 (ELLENBORO HENRIETTA ROAD)	1	1.03	21.50	1.78	2.81						10,877	10,877
13	SR 1984 (J M LOVELACE ROAD)	FROM SR 1982 (WEBB ROAD) TO END OF MAINTENANCE	6	0.77	20.00	0.01	0.78							
14	SR 2013 (DOBBINSVILLE EXTENSION)	FROM SR 1921 (RACE PATH CHURCH ROAD) TO END OF MAINTENANCE	6	0.30	18.00	0.01	0.31							
15	SR 2022 (GREEN ACRES ROAD)	FROM SR 1976 (CHESTERFIELD ROAD) TO US 221 ALTERNATE	6	0.28	18.00	0.01	0.29							
16	SR 2025 (SHORT STREET)	FROM SR 1982 (WEBB ROAD) TO END OF MAINTENANCE	1	0.17	18.00	0.01	0.18							
17	SR 2031 (BRADBURY ROAD)	FROM SR 1936 (SOCO GAP ROAD) TO END OF MAINTENANCE	6	0.29	17.00	0.01	0.30							
18	SR 2035 (WOODSET DRIVE)	FROM SR 1911 (LOW BRIDGE ROAD) TO END OF MAINTENANCE	6	0.12	24.00	0.01	0.13							
19	SR 2036 (KEMIT COURT)	FROM SR 1914 (PUZZLE CREEK ROAD) TO END OF MAINTENANCE	6	0.18	18.50	0.01	0.19							
20	SR 2040 (HARRILL DAIRY ROAD)	FROM US 221 ALTERNATE TO SR 1906 (MOUNT PLEASANT CHURCH ROAD)	6	1.43	20.50	0.01	1.44						15,102	15,102
21	SR 2107 (HINES LOOP ROAD)	FROM SR 2102 (HINES ROAD) TO SR 2102 (HINES ROAD)	6	0.56	18.50	0.01	0.57						5,914	5,914
22	SR 2109 (ISLAND FORD ROAD)	FROM US 221 ALTERNATE TO SR 2111 (HENRY JENKINS ROAD)	1	1.88	19.00	0.03	1.91						19,642	16,631
23	SR 2125 (HARRIS HENRIETTA ROAD)	FROM US 221 ALTERNATE TO SR 2117 (FERRY ROAD)	1, 4	2.31	20.00	0.02	2.33			734	734	1,468	24,288	24,288
24	SR 2270 (TROJAN LANE)	FROM SR 2210 (CHASE HIGH ROAD) TO CUL DE SAC	6	0.41	20.50	0.01	0.42							
25	SR 2303 (BIRDSONG LANE)	FROM US 221 ALTERNATE TO DEAD END	6	0.40	19.00	0.01	0.41							
26	CLIFFSIDE FIRE DEPARTMENT (PARKING LOT)	4600 US 221 ALTERNATE (RUTHERFORD COUNTY)	5											
TOTAL FOR PROJ NO. 2024CPT.13.14.20811				25.32				5	4	2,820	2,820	5,640	213,060	181,717
								9		5640			394,777	
GRAND TOTAL				25.33				5	4	2,820	2,820	5,640	213,060	181,717
								9		5640			394,777	

*NOTE-ALL MAPS, PROJECT NUMBER = 2024CPT.13.14.10811, COUNTY = RUTHERFORD, LANES = 2, LANE TYPE = 2WU, FINAL TESTING REQUIRED = NO, WARM MIX ASPHALT REQUIRED = NO