PROJECT NO.	SHEET NO.
2024CPT.03.12.10821,ETC.	14

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	0234000000-E BORROW EXCAVATION STATE FURNISHED	0264000000-E SHOULDER RECONSTRUCTION STATE FURNISHED BORROW EXCAVATION	1220000000-E INCIDENTAL STONE BASE	1297000000-E 1.5" MILLING	1308000000-E 0" - 1.5" MILLING (GENERIC)	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1520000000-E LEVELING COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C
										MI	FT			CY	SMI	TON	SY	SY	SY	TONS	TON	TON	TON	TON
2024CPT.03.12.10821	Sampson	1	US-13, NEWTON GROVE TRAFFIC CIRCLE, NE-BOUND	FROM MILEPOST 17.72 AROUND ROUNDABOUT TO MILEPOST 17.87 [MP 17.72 - MP 17.87]	1	2	2WD	NO	NO	0.15	33	17.72	17.87					907	625				279	
TOTAL FOR MAP NO. 1										**0.15**								**907**	**625**				**279**	
2024CPT.03.12.10821	Sampson	2	US-13, NEWTON GROVE TRAFFIC CIRCLE, SW-BOUND	FROM MILEPOST 3.99 AROUND ROUNDABOUT TO MILEPOST 4.13 [MP 3.99 - MP 4.13]	1	2	2WD	NO	NO	0.14	33	3.99	4.13					908	625				271	
TOTAL FOR MAP NO. 2										**0.14**								**908**	**625**				**271**	
2024CPT.03.12.10821	Sampson	3	NC-50, HARNETT-DUNN HIGHWAY	FROM I-40 OVERPASS BRIDGE TO NC HWY 55 [MP 16.40 - MP 16.66]	2	2	2WU	NO	NO	0.26	40	16.4	16.66	32	0.52				966				739	10
TOTAL FOR MAP NO. 3										**0.26**				**32**	**0.52**				**966**				**739**	**10**
2024CPT.03.12.10821	Sampson	4	NC-55, HARNETT-DUNN HIGHWAY	FROM NC HWY 50 TO JOHNSTON COUNTY LINE [MP 8.19 - MP 12.47]	2	2	2WU	NO	NO	4.28	26	8.19	12.47	522	8.56	114			2,376				5,967	15
TOTAL FOR MAP NO. 4										**4.28**				**522**	**8.56**	**114**			**2,376**				**5,967**	**15**
TOTAL FOR PROJ NO. 2024CPT.03.12.10821										**4.83**				**554**	**9.08**	**114**		**1,815**	**4,592**				**7,256**	**25**
2024CPT.03.12.20821	Sampson	5	SR-1731 / GOSHEN CHURCH RD	FROM SR 1722 (SUTTONTOWN RD) TO SR 1725 (GIDDENSVILLE RD) [MP 0.06 - MP 5.37]	3	2	2WU	NO	NO	5.31	19	0.06	5.37	648	10.62	46			648		5,344	15		
TOTAL FOR MAP NO. 5										**5.31**				**648**	**10.62**	**46**			**648**		**5,344**	**15**		
2024CPT.03.12.20821	Sampson	6	SR-1002 / MINGO CHURCH RD	FROM US HWY 13 (FAYETTEVILLE HWY) TO SR 1603 (GAINEY RD) [MP 16.48 - MP 19.18]	4	2	2WU	NO	NO	2.7	23	16.48	19.18	329	5.40	66			604	2,498	2,689	10		
TOTAL FOR MAP NO. 6										**2.7**				**329**	**5.40**	**66**			**604**	**2,498**	**2,689**	**10**		
2024CPT.03.12.20821	Sampson	7	SR-1239 / UNDERWOOD RD	FROM NC HWY 24 (ROSEBORO HWY) TO NC HWY 24 (ROSEBORO HWY) [MP 0.00 - MP 1.40]	3	2	2WU	NO	NO	1.4	20	0	1.4	171	2.80	36			111		1,212			
TOTAL FOR MAP NO. 7										**1.4**				**171**	**2.80**	**36**			**111**		**1,212**			
2024CPT.03.12.20821	Sampson	8	SR-1316 / MURPHY RD	FROM SR 1308 (BOONE RD) TO SR 1317 (FREDRICK RD) [MP 0.00 - MP 1.08]	3	2	2WU	NO	NO	1.08	20	0	1.08	132	2.16	28			300		1,119			
TOTAL FOR MAP NO. 8										**1.08**				**132**	**2.16**	**28**			**300**		**1,119**			
2024CPT.03.12.20821	Sampson	9	SR-1146 / MOSELEY AVE	FROM SR 1145 (BONEY MILL RD) TO US HWY 701 (GARLAND HWY) [MP 2.46 - MP 6.55]	3	2	2WU	NO	NO	4.09	20	2.46	6.55	499	8.18	60			530		4,249	30		
TOTAL FOR MAP NO. 9										**4.09**				**499**	**8.18**	**60**			**530**		**4,249**	**30**		
2024CPT.03.12.20821	Sampson	10	SR-1365 / ROSEBORO HWY	FROM CUL-DE-SAC TO CUL-DE-SAC [MP 0.00 - MP 0.79]	3	2	2WU	NO	NO	0.79	26	0	0.79	96	1.58	38			1,172		1,323	20		
TOTAL FOR MAP NO. 10										**0.79**				**96**	**1.58**	**38**			**1,172**		**1,323**	**20**		
2024CPT.03.12.20821	Sampson	11	SR-1292 / DIXIE RD	FROM NC HWY 24 TO OLD ROSEBORO HWY [MP 0.75 - MP 0.80]	3	2	2WU	NO	NO	0.05	26	0.75	0.8	6	0.10	4			144		78			
TOTAL FOR MAP NO. 11										**0.05**				**6**	**0.10**	**4**			**144**		**78**			
2024CPT.03.12.20821	Sampson	12	SR-1309 / BASS LAKE RD	FROM NC HWY 24 TO OLD ROSEBORO HWY [MP 5.08 - MP 5.21]	3	2	2WU	NO	NO	0.13	21	5.08	5.21	16	0.26	4			117		146			
TOTAL FOR MAP NO. 12										**0.13**				**16**	**0.26**	**4**			**117**		**146**			
2024CPT.03.12.20821	Sampson	13	SR-1149 / CHANCEY RD	FROM US HWY 701 TO SR 1145 (BONEY MILL RD) [MP 0.00 - MP 2.49]	3	2	2WU	NO	NO	2.49	21	0	2.49	304	4.98	38			1,245		2,715	10		
TOTAL FOR MAP NO. 13										**2.49**				**304**	**4.98**	**38**			**1,245**		**2,715**	**10**		
2024CPT.03.12.20821	Sampson	14	SR-1145 / BONEY MILL RD	FROM SR 1145 (BONEY MILL RD) TO SR 1147 (W MT GILEAD CHURCH RD) [MP 1.90 - MP 3.48]	5	2	2WU	NO	NO	1.58	23	1.9	3.48	193	3.16	24	868		684	798	1,687	20		
TOTAL FOR MAP NO. 14										**1.58**				**193**	**3.16**	**24**	**868**		**684**	**798**	**1,687**	**20**		
TOTAL FOR PROJ NO. 2024CPT.03.12.20821										**19.62**				**2,394**	**39.24**	**344**	**868**		**5,555**	**3,296**	**20,562**	**105**		
GRAND TOTAL										**24.45**				**2,948**	**48.32**	**458**	**868**	**1,815**	**10,147**	**3,296**	**20,562**	**105**	**7,256**	**25**