


ALL BAR DIMENSION



TEMPORARY RIP RAP-

BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT


TYPES	BILL OF MATERIAL						
B2	END BENT 1						
B1	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
B1 HK° (1 ↓ b°)	B1	8	9	1	46′-6″	1,265	
	B2	8	9	1	47'-9"	1,299	
	B3	12	5	STR	43'-8"	547	
	B4	12	4	STR	29'-9"	238	
3'-71/2"	B5	22	4	STR	3'-2"	47	
	B6	8	4	STR	14'-6"	77	
	Β7	4	4	STR	20'-5"	55	
5 ¹ /2" HK. 3'-2"	H1	10	4	STR	4'-9"	32	
HK.	H2	4	4	STR	2'-8"	7	
	Н3	4	4	STR	1'-11"	5	
1'-3"							
	S1	82	5	2	11'-4"	969	
	S2	82	5	3	4'-1"	349	
	S3	44	4	5	7'-7"	223	
	U1	34	4	4	6'-2"	140	
	V1	88	4	STR	6'-3"	367	
2'-0"Ø	V2	8	6	STR	9'-11"	119	
	٧3	4	6	STR	9'-2"	55	
	REINFORCING STEEL					794 LBS.	
ONS ARE OUT TO OUT	CLASS A CONCRETE 48.5 C.Y.						

- TEMPORARY SLOPE DRAIN

MSE WALL


TEMPORARY RIP RAP





Kimley»Horn

421 Fayetteville Street, Suite 600 Raleigh, NC 27601-1772 Phone (919) 677-2000 NC LICENSE # F-0102



RALEIGH SUBSTRUCTURE

END BENT SECTION AND DETAILS

REVISIONS					SHEET NO.		
NO.	BY:	DATE:	NO.	BY:	DATE:	S-26	
1			3			TOTAL SHEETS	
2			4			33	