

REFERENCE: BR-0139

PROJECT: 67139

SEE SHEET 3 FOR PLAN SHEET LAYOUT AT TIME OF INVESTIGATION

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT

ROADWAY SUBSURFACE INVESTIGATION

COUNTY BRUNSWICK PROJECT DESCRIPTION REPLACE CULVERT #003 OVER SAND HILL CREEK AND THREE OTHER CULVERTS ON NC 133 (RIVER RD)

INVENTORY

CONTENTS

Table with columns: LINE, STATION, PLAN. Rows: -L- 12+50 TO 40+20 4-5, -YI- 10+00 TO 11+90 5

CROSS SECTIONS

Table with columns: LINE, STATION, SHEETS. Rows: -L- 13+50 TO 39+00 6-28, CULVERT 33+27 29

SAMPLE RESULTS

30

Table with columns: STATE, STATE PROJECT REFERENCE NO., SHEET NO., TOTAL SHEETS. Values: N.C., BR-0139, 1, 1

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

- NOTES: 1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT. 2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

- S.N. ZIMARINO
T.W. MILLER
A. KINTNER
R.E. SMITH
C.M. WALKER
J.M. EDMONDSON
D. PINTER

INVESTIGATED BY T.C. BOTTOMS
DRAWN BY T.C. BOTTOMS
CHECKED BY D.N. ARGENBRIGHT
SUBMITTED BY D.N. ARGENBRIGHT
DATE OCTOBER 2022



DocuSigned by: Tyler C. Bottoms 02/02/2023
48A2D3BD08CF4A6 SIGNATURE DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS


Table with 4 main columns: SOIL DESCRIPTION, GRADATION, ROCK DESCRIPTION, and TERMS AND DEFINITIONS. Includes sub-sections like SOIL LEGEND AND AASHTO CLASSIFICATION, CONSISTENCY OR DENSENESS, TEXTURE OR GRAIN SIZE, SOIL MOISTURE - CORRELATION OF TERMS, PLASTICITY, COLOR, MISCELLANEOUS SYMBOLS, RECOMMENDATION SYMBOLS, ABBREVIATIONS, EQUIPMENT USED ON SUBJECT PROJECT, and FRACTURE SPACING/BEDDING/INDURATION.

09/08/23

TIP PROJECT: BR-0139

CONTRACT:

See Sheet 1B For Standard Symbology Sheet



APPROVED 25% PLANS



STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# BRUNSWICK COUNTY

**LOCATION: REPLACE CULVERT #003 OVER SAND HILL CREEK AND THREE OTHER CULVERTS ON NC 133 (RIVER RD)**

**TYPE OF WORK: GRADING, DRAINAGE, PAVING, CULVERT AND STRUCTURE**

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BR-0139	3	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
67139.1		PE	
67139.2		UTIL & RW	
67139.3		CONSTRUCTION	



THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES.  
CLEARING LIMITS ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III (MODIFIED).

**INCOMPLETE PLANS**  
DO NOT USE FOR R/W ACQUISITION  
DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED

<p><b>GRAPHIC SCALES</b></p> <p>50 25 0 50 100 PLANS</p> <p>50 25 0 50 100 PROFILE (HORIZONTAL)</p> <p>10 5 0 10 20 PROFILE (VERTICAL)</p>	<p><b>DESIGN DATA</b></p> <p>ADT 2024 = 7,300 ADT 2044 = 13,200 K = 10 % D = 55 % T = 8 % * V = 60 MPH * TTST=2% DUAL=6% FUNC CLASS = MINOR ARTERIAL REGIONAL TIER</p>	<p><b>PROJECT LENGTH</b></p> <p>LENGTH OF ROADWAY T.I.P. PROJECT BR-0139 = 0.452 MI</p> <p>LENGTH OF STRUCTURES T.I.P. PROJECT BR-0139 = 0.073 MI</p> <p>TOTAL LENGTH OF T.I.P. PROJECT BR-0139 = 0.525 MI</p>	<p>Prepared In the Office of:</p> <p><b>HNTB</b> HNTB NORTH CAROLINA, P.C. 343 E. Six Forks Road, Suite 200 Raleigh, North Carolina 27609 NC License No: C-1554</p> <p>2018 STANDARD SPECIFICATIONS</p> <p><b>RIGHT OF WAY DATE:</b> JANUARY 13, 2023</p> <p><b>LETTING DATE:</b> APRIL 16, 2024</p>	<p><b>HYDRAULICS ENGINEER</b></p> <p>SIGNATURE: _____ P.E.</p> <p><b>ROADWAY DESIGN ENGINEER</b></p> <p>SIGNATURE: _____ P.E.</p>	
--	--	--	--	---	--

26-SEP-2022 13:09  
\\BR0139\_rdy\_tsh.dgn  
\$\$\$\$\$USERNAME\$\$\$\$\$



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

September 27, 2022

State Project: 67139.1.1 (BR-0139)  
F.A. Project: N/A  
County: Brunswick  
Description: Replace Culvert #003 over Sand Hill Creek and three other culverts on NC 133 (River Road)

Subject: Geotechnical Inventory Report

**Project Description**

This project begins approximately 0.3 miles north of the intersection of NC 133 and Funston Road in Brunswick County and extends south along NC 133 for approximately 0.5 miles. Proposed construction consists of widening and raising the grade of NC 133 as well as culvert replacements. This geotechnical investigation was confined to the areas of proposed construction.

Fieldwork was conducted in November of 2017, January of 2019 and August of 2022. SPT, power auger and hand auger borings were completed at various offsets along the project corridor. Representative soil samples were collected for visual classification in the field and for laboratory analysis by the Materials and Tests Unit.

The following alignments were investigated. Subsurface profiles and selected cross sections of these alignments are included in this report.

<u>Line</u>	<u>Station(±)</u>
-L-	12+50 to 40+20
-Y1-	10+00 to 11+90

**Areas of Special Geotechnical Interest**

- 1) The entire project was found to exhibit seasonal high ground water.
- 2) The following sections contain cohesive soils which have the potential to cause embankment/subgrade and or slope stability problems during construction:

<u>Line</u>	<u>Station(±)</u>
-L-	16+25 to 16+75
-L-	17+75 to 18+75
-L-	27+25 to 30+25
-L-	31+25 to 31+75

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
GEOTECHNICAL ENGINEERING UNIT –  
EASTERN REGIONAL OFFICE  
1570 MAIL SERVICE CENTER  
RALEIGH, NC 27699-1570

Telephone: (984) 920-8900  
Customer Service: 1-877-368-4968  
Website: www.ncdot.gov

Location:  
3301 JONES SAUSAGE RD, SUITE 100  
GARNER, NC 27529

<u>Line</u>	<u>Station(±)</u>
-L-	33+25 to 33+75
-L-	34+25 to 34+75

- 3) The following sections contain organic soils which have the potential to cause embankment/subgrade and or slope stability problems during construction:

<u>Line</u>	<u>Station(±)</u>
-L-	18+75 to 22+90
-L-	32+84 to 33+58
-L-	34+20 to 35+35

**Physiography and Geology**

This project corridor is located within the Coastal Plain Physiographic Province. Topography along the project is nearly flat to gently sloping. Natural ground elevations ranged from 8± to 22± feet above sea level.

Surficial soils in this area are generally classified as alluvial sediments and are underlain by formational soils belonging to the Waccamaw Formation.

**Ground Water**

Ground water data was collected in November of 2017, January of 2019 and August of 2022. Ground water elevations ranged from 6± to 22± feet above sea level.

**Soils**

Soils encountered within this project area have been divided into three categories: Roadway Embankment, alluvial and formational

Roadway embankment soils were found along the existing NC 133 corridor and Funston Road. Where encountered it was composed of 1± to 10± feet of loose to medium dense sand (A-2-4, A-3).

Soils identified as alluvial are composed of 1± to 15± feet of very loose to medium dense sand (A-2-6, A-2-4, A-3), 2± to 4± feet of soft sandy clay (A-6, A-7-6), 5± feet of loose moderately organic sand, 7± feet of very soft moderately organic silt, and 5 to 13± feet of soft muck. Moisture samples taken within units returned a natural moisture content ranging from 23% to 203%. Organic percentages ranged from 4% to 60%.

Formational soils belonging to the Waccamaw formation were encountered beneath the alluvial soils. Where encountered, these soils consisted of 10± of very loose sand, 3± of hard silt (A-4) and soft limestone.

**Culvert**


A culvert is proposed at -L- Sta. 33+27 at Dark Bay Branch. A cross section showing anticipated soil conditions at this site is included in this report. Beneath 4 to 6 feet of embankment is approximately 7 feet of very soft muck and moderately organic silt. Soft sandy clay and loose sands underlie the organic material. Soft limestone was encountered at elevation -16 feet at Sta. 33+20, 10' RT. The variability between the SPT borings at 33+20, 10' RT and 33+37, 8' LT suggest there is a sinkhole present. The limits of the sinkhole have not been defined.

**Shelby Tubes**


Shelby tubes were collected at the following locations and submitted to the lab for testing:

<u>Sample Number</u>	<u>Location</u>	<u>Depth</u>	<u>Test Type</u>
ST-1	33+37, 9' LT	7.0'-9.0'	Consolidation
ST-2	33+37, 9' LT	13.5'-15.5'	Consolidation

PROJECT REFERENCE NO. <b>BR-0139</b>	SHEET NO. <b>4</b>
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
<b>INCOMPLETE PLANS</b> DO NOT USE FOR R/W ACQUISITION	
<b>DOCUMENT NOT CONSIDERED FINAL</b> UNLESS ALL SIGNATURES COMPLETED	



8/17/99



MATCHLINE -L- STA 26 + 50.00 SEE SHEET 5



**CAMA WETLANDS**

-L-  
 PI Sta 27+63.86  
 $\Delta = 4' 19' 23.0" (LT)$   
 $D = 0' 50' 33.3"$   
 $L = 513.07'$   
 $T = 256.66'$   
 $R = 6,800.00'$   
 $SE = 3\%$   
 $RO = 72'$


FOR -L- PROFILE, SEE SHEET 6

27-SEP-2022 07:59  
 A:\BR0139\Drawings\plan4.dgn  
 3333333333333333


8/17/99

**HNTB** HNTB NORTH CAROLINA, P.C.  
349 E. SIX FORKS ROAD, SUITE 200  
RALEIGH, NORTH CAROLINA 27609  
NC LICENSE NO: C-1554

PROJECT REFERENCE NO. <b>BR-0139</b>	SHEET NO. <b>5</b>
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
<b>INCOMPLETE PLANS</b> DO NOT USE FOR R/W ACQUISITION	
<b>DOCUMENT NOT CONSIDERED FINAL</b> UNLESS ALL SIGNATURES COMPLETED	



MATCHLINE -L- STA 26 + 50.00 SEE SHEET 4




BM3  
ELEVATION = 17.17  
N 128118 E 2312257  
BL STATION 35+25.00 202 RIGHT  
RR SPK IN BASE OF 14" PINE

-L-	-L-	-YI-
PI Sta 27+63.86	PI Sta 40+92.71	PI Sta 10+63.06
$\Delta = 4' 19' 23.0''$ (LT)	$\Delta = 4' 41' 34.4''$ (RT)	$\Delta = 17' 47' 43.2''$ (RT)
D = 0' 50' 33.5"	D = 0' 50' 29.1"	D = 28' 38' 52.4"
L = 513.07'	L = 557.73'	L = 621.2'
T = 256.66'	T = 279.02'	T = 31.31'
R = 6,800.00'	R = 6,809.35'	R = 200.00'
SE = 3%	SE = 3%	SE = SEE PLANS
RO = 72'	RO = 72'	RO = SEE PLANS

FOR -L- PROFILE, SEE SHEETS 6 & 7  
FOR -YI- PROFILE, SEE SHEET 7


27-SEP-2022 08:00  
A:\BR0139\cadd\plan\sheet5.dgn  
8/17/99


6/23/16




26-SEP-2022 13:10 S:\EFG\greenhill\Investigation\TP\BR0139\_GEO\_ROW\CADD\_GEO\TECH\XSC\BR0139\_rdu\_xpl.dgn \$\$\$USERNAME\$\$\$










75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



— L —


75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

6/23/16



PROJ. REFERENCE NO. BR-0139 SHEET NO. 11

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75




27-SEP-2022 08:36  
S:\PROJECTS\BR0139\_GEO\RDWY\CAOD.GEOTECH\sc\BR0139\_rdy\_xpl.L.dgn  
\$\$\$\$SERNAME\$\$\$\$


75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75


ⓑ LOOSE TO MEDIUM DENSE TAN AND GRAY SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)




10 5 0 -5 -10 -15 -20 -25 -30 -35



75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



6/23/16  
26-SEP-2022 13:16  
\\BR0139\proj\dwg\p1.dgn  
\$\$\$\$\$USER\$NAME\$\$\$\$\$



**VANE SHEAR TESTS**

STATION	OFFSET	DEPTH	S (KPa)	SR (psf)
21+75	22' LT	0.5'	MAX	MAX
21+75	22' LT	1.0'	88	1837.44
21+75	22' LT	1.5'	28	584.64
21+75	22' LT	2.0'	39	814.32
21+75	22' LT	2.5'	49	1023.12
21+75	22' LT	3.0'	68	1419.84
21+75	22' LT	3.5'	115	2401.20
21+75	22' LT	4.0'	97	2025.36
21+75	22' LT	4.5'	MAX	MAX
21+75	22' LT	5.0'	52	1085.76
21+75	22' LT	5.5'	40	835.20
21+75	22' LT	6.0'	28	584.64
21+75	22' LT	6.5'	0	0.0
21+75	22' LT	7.0'	9	187.92
21+75	22' LT	7.5'	8	167.04
21+75	22' LT	8.0'	0	0
21+75	22' LT	8.5'	0	0
21+75	22' LT	9.0'	0	0
21+75	22' LT	9.5'	0	0
21+75	22' LT	10.0'	0	0
21+75	22' LT	10.5'	MAX	MAX
21+75	22' LT	11.0'	68	1419.84
21+75	22' LT	11.5'	78	1628.64
21+75	22' LT	12.0'	MAX	MAX

SURFACE WATER 1/19

SURFACE WATER 1/19

VERY LOOSE TO MEDIUM DENSE BROWN AND GRAY SAND, SATURATED (ALLUVIAL)

VERY LOOSE TO MEDIUM DENSE BROWN AND GRAY SAND, SATURATED (ALLUVIAL)


SOFT GRAY SANDY CLAY, WET (ALLUVIAL)


SOFT GRAY LIMESTONE (WACCAMAW FORMATION)

21 + 50.00


-L-










6/23/16



PROJ. REFERENCE NO.	SHEET NO.
BR-0139	17



26-SEP-2022 13:48  
\\BR0139\at\dwg\p1\dgn  
\$\$\$\$\$USERNAME\$\$\$\$\$



(B) LOOSE TAN SAND, MOIST (ROADWAY EMBANKMENT)

LOOSE GRAY SAND, MOIST TO SATURATED (ALLUVIAL)

27+00.00

(B) LOOSE TAN SAND, MOIST (ROADWAY EMBANKMENT)

LOOSE GRAY SAND, MOIST TO SATURATED (ALLUVIAL)

26+50.00


26+69


FIAD

LOOSE GRAY SAND, MOIST TO SATURATED (ALLUVIAL)

26+00.00

-L-






(B) LOOSE TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)  
 (C) LOOSE GRAY AND TAN SAND, MOIST TO SATURATED (ALLUVIAL)

SOFT GRAY SANDY CLAY, MOIST TO WET (ALLUVIAL)


(B) LOOSE TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)  
 (C) LOOSE GRAY AND TAN SAND, MOIST TO SATURATED (ALLUVIAL)

SOFT GRAY SANDY CLAY, MOIST TO WET (ALLUVIAL)


6/23/16



26-SEP-2022 14:23  
\\BR0139\at\dwg\16.dgn  
\$\$\$\$\$USER\$NAME\$\$\$\$\$



75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



- (A) SOFT GRAY SANDY CLAY, MOIST TO WET (ALLUVIAL)
- (B) LOOSE TAN SAND, MOIST (ROADWAY EMBANKMENT)

LOOSE GRAY AND TAN SAND, MOIST TO SATURATED (ALLUVIAL)

LOOSE TAN SAND, MOIST (ROADWAY EMBANKMENT)

LOOSE GRAY AND TAN SAND, MOIST TO SATURATED (ALLUVIAL)

PAVEMENT


09/22

31+50.00

31+70

32+00.00






**VANE SHEAR TESTS**


STATION	OFFSET	DEPTH	S (KPa)	SR (psf)
33+20	40' RT	0.5	2	41.76
33+20	40' RT	1.0	8	167.04
33+20	40' RT	1.5	25	522.00
33+20	40' RT	2.0	61	1273.68
33+20	40' RT	2.5	19	396.72
33+20	40' RT	3.0	12	250.56
33+20	40' RT	3.5	14	292.32
33+20	40' RT	4.0	15	313.20
33+20	40' RT	4.5	18	375.84
33+20	40' RT	5.0	26	542.88
33+20	40' RT	5.5	83	1733.04
33+20	40' RT	6.0	26	542.88
33+20	40' RT	6.5	41	856.08
33+20	40' RT	7.0	53	1106.64
33+20	40' RT	7.5	39	814.32
33+20	40' RT	8.0	42	876.96
33+20	40' RT	8.5	51	1064.88
33+20	40' RT	9.0	41	856.08
33+20	40' RT	9.5	64	1336.32
33+20	40' RT	10.0	61	1273.68
33+20	40' RT	10.5	MAX	MAX

6/23/16




27-SEP-2022 08:01  
 S:\PROJECTS\BR0139\GEO\RDWY\CAOD.GEOTECH\sc\BR0139\_rdy\_xpl.dgn  
 \$\$\$USERNAME\$\$\$


75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



- (A) SOFT GRAY SANDY CLAY, MOIST TO WET (ALLUVIAL)
- (B) VERY LOOSE TO LOOSE BROWN AND TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)
- (D) VERY LOOSE BROWN MUCK, MOIST TO SATURATED (ALLUVIAL)



75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75





LOOSE GRAY SAND, MOIST TO SATURATED (ALLUVIAL)


LOOSE GRAY SAND, MOIST TO SATURATED (ALLUVIAL)

LOOSE GRAY SAND, MOIST TO SATURATED (ALLUVIAL)


(B) VERY LOOSE TO LOOSE BROWN AND TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)

(D) VERY LOOSE BROWN MUCK, MOIST TO SATURATED (ALLUVIAL)






75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75



PROPOSED CULVERT CROSS SECTION AT -L- STA. 33+27

- (A) SOFT GRAY SANDY CLAY, WET (ALLUVIAL)
- (B) VERY LOOSE TO LOOSE BROWN AND TAN SAND, MOIST TO SATURATED (ROADWAY EMBANKMENT)
- (C) VERY LOOSE TO MEDIUM DENSE BROWN AND GRAY SAND AND CLAYEY SAND, SATURATED (ALLUVIAL)
- (D) VERY SOFT BROWN MUCK AND MODERATELY ORGANIC SILT, WET (ALLUVIAL)



27-SEP-2022 07:56  
 C:\FRONTEND\TIP\BR0139\_GEO\_RDWY\CAOD\_GEO\TECH\sc\BR0139\_r.dwg\_xsc.L.dgn  
 \$\$\$\$USERNAME\$\$\$\$

### SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS- 1	10' RT	33+20	6.0- 7.5	A- 1- b( 0)	0	NP	68.3	14.9	8.7	8.1	93	43	16	-	59.8
SS- 4	8' RT	20+00	10.5- 12.0	A- 4( 0)	0	NP	46.1	13.3	24.4	16.2	97	62	41	-	55.0
SS- 5	8' RT	20+00	13.0- 14.5	A- 2- 4( 0)	0	NP	58.2	21.8	11.9	8.1	95	51	20	-	60.4
SS- 6	8' RT	20+00	15.5- 17.0	A- 2- 4( 0)	0	NP	40.0	35.6	16.4	8.1	100	73	26	124.7	-
SS- 7	8' RT	20+00	18.0- 19.5	A- 3( 0)	0	NP	40.8	51.7	3.4	4.0	100	77	9	-	-
SS- 8	8' RT	20+00	33.0- 34.5	A- 1- b( 0)	0	NP	48.5	29.7	5.7	16.2	49	32	12	-	-
SS- 9	8' RT	21+65	10.5- 12.0	A- 2- 4( 0)	0	NP	51.3	28.7	11.9	8.1	94	57	20	-	39.6
SS- 10	9' LT	21+75	10.5- 12.0	A- 1- b( 0)	0	NP	49.7	33.9	8.3	8.1	80	50	15	-	48.5
SS- 11	8' LT	33+37	6.0- 8.5	A- 4( 0)	0	NP	30.7	33.9	23.2	12.1	99	79	37	203.4	16.0
SS- 12	7' LT	19+95	23.0- 24.5	A- 2- 4( 0)	0	NP	37.4	48.7	1.8	12.1	100	90	17	-	-
SS- 13	7' LT	19+95	28.0- 29.5	A- 2- 4( 0)	29	7	39.8	35.4	4.6	20.2	88	68	24	-	-
S- 2	17' RT	29+70	3.0- 11.5	A- 7- 6( 49)	72	47	0.8	10.7	17.8	70.7	100	100	92	-	-
S- 11	30' RT	34+50	1.0- 2.0	A- 6( 10)	38	22	8.5	33.0	18.2	40.3	100	98	61	22.7	-
S- 12	30' LT	34+50	1.5- 4.0	A- 2- 4( 0)	-	NP	23.0	45.3	23.7	8.1	97	87	34	111.2	14.1
S- 13	32' RT	18+00	0.0- 2.0	A- 7- 6( 20)	46	23	5.2	15.5	32.9	46.3	100	98	82	33.3	-
S- 20	8' RT	19+05	3.5- 8.5	A- 2- 4( 0)	0	NP	42.0	47.5	6.5	4.0	99	74	14	72.8	4.4
S- 21	8' RT	19+05	8.5- 13.0	A- 2- 4( 0)	0	NP	50.5	21.4	20.0	8.1	99	61	30	182.9	27.1
S- 22	40' LT	29+69	3.0- 6.0	A- 7- 6( 40)	62	42	3.8	11.5	24.3	60.4	100	99	88	27.0	-
S- 23	33' RT	27+69	3.5- 6.0	A- 7- 6( 31)	56	36	5.2	17.9	24.5	52.4	100	98	82	43.4	-
ST- 1	9' LT	33+37	7.0- 9.0	-	-	-	-	-	-	-	-	-	-	-	-
ST- 2	9' LT	33+37	13.5- 15.5	-	-	-	-	-	-	-	-	-	-	-	-