

S:\19\2024\PL15\010.00_U-5757_NC8_WinstonRd.wden.Lexington\Traffic\Signing\CADD\Signing_Layout_Plans\U-5757_SIGN1.dgn
8/19/2024 11:01:00 AM J.Bauman

CONTRACT: --

TIP PROJECT: U-5757

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
DAVIDSON COUNTY

LOCATION: NC 8 (WINSTON ROAD) FROM US 29 /US 70 TO
SR 1846 (ARRINGTON DRIVE) IN LEXINGTON

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -
PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C.,
DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE
CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|--|
| 903.10 | GROUND MOUNTED SIGN SUPPORTS |
| 904.10 | ORIENTATION OF GROUND MOUNTED SIGNS |
| 904.20 | SECONDARY SIGN MOUNTING |
| 904.30 | SUPPLEMENTAL SIGN MOUNTING |
| 904.50 | MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS |
| 1264.01 | OBJECT MARKERS - TYPES |
| 1264.02 | OBJECT MARKERS - INSTALLATION |

SUMMARY OF QUANTITIES

| ITEM NO. | | ITEM DESCRIPTION | QUANTITY | UNIT |
|------------|-----------|---|----------|------|
| DESC. NO. | SECT. NO. | | | |
| 4072000000 | 903 | SUPPORTS, 3 LB STEEL U-CHANNEL | 750 | LF |
| 4102000000 | 904 | SIGN ERECTION, TYPE E | 27 | EA |
| 4108000000 | 904 | SIGN ERECTION, TYPE F | 4 | EA |
| 4116100000 | 904 | SIGN ERECTION, RELOCATE TYPE E (GROUND MOUNTED) | 1 | EA |
| 4155000000 | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 37 | EA |

PLAN PREPARED BY:
TRANSYSTEMS

Steve Miller, PE PROJECT MANAGER
John Bauman, PE DESIGN ENGINEER

PROJECT NOTES

- DISPOSAL OF SIGN SYSTEM, U-CHANNEL
- RELOCATE SIGN ON NEW SUPPORTS

GENERAL NOTES

- SIGNS FURNISHED BY STATE
- CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE GRADE C REFLECTIVE SHEETING.
- SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

INDEX

| SHEET NO. | DESCRIPTION |
|-----------|--------------------------|
| SIGN-1 | SIGNING PLAN TITLE SHEET |
| SIGN-2 | TYPE E SIGNS |
| SIGN-3 | TYPE F SIGNS |
| SIGN-4-6 | EXISTING SIGNS |
| SIGN-7-9 | PROPOSED SIGNS |

TRANSYSTEMS

1 Glenwood Avenue
Raleigh, NC 27603
Tel: 919.789.9977
Fax: 919.789.9591
License: F-0453

| | |
|---|-----------|
| TIP NO. | SHEET NO. |
| U-5757 | SIGN-1 |
| APPROVED: <div>DocuSigned by: Steve Miller 9FB08C15CEE8466...</div> | |
| DATE: _____ | |
| SEAL <div>Seal of the State of North Carolina Professional Engineer Seal 037026 Steven D. Miller</div> | |
| DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED | |