

ADA SUMMARY OF QUANTITIES - EBENEZER CHURCH RD FROM SR 1647 TO SR 1664

Municipality:	Raleigh
Project Number:	2025CPT.05.02.20921.1
County:	Wake

Sheet No.
19

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove and Replace Curb & Gutter	2535000000-E (LF) 8" X 12" Concrete Curb	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove and Replace Sidewalk	2738000000-E (SY) Remove Sidewalk	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2612300000-N (EA) Retrofit Existing Concrete Curb Ramp	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2759000000-N (EA) Remove Curb Ramps	Improvement Type
9108	1	SR-1649 (Ebenezer Church Rd)	Bridgeton Park Dr										1		Type 1C - 848.06
9109	1	SR-1649 (Ebenezer Church Rd)	Bridgeton Park Dr		20									1	Remove Ramp
9110	1	SR-1649 (Ebenezer Church Rd)	Bridgeton Park Dr		10								1		Type 3 Modified - 848D0609
9111	1	SR-1649 (Ebenezer Church Rd)	Bridgeton Park Dr		25									1	Remove Ramp
9112	2	SR-1649 (Ebenezer Church Rd)	Burwell Rollins Cir										1		Type 3 Modified - 848D0609
9113	2	SR-1649 (Ebenezer Church Rd)	Burwell Rollins Cir										1		Type 3 Modified - 848D0609
9114	3	SR-1649 (Ebenezer Church Rd)	Touchstone Forest Rd										1		Standard - 848.06
9115	3	SR-1649 (Ebenezer Church Rd)	Touchstone Forest Rd		15			9						1	Remove Ramp
25995	4	SR-1649 (Ebenezer Church Rd)	Harbourgate Dr		18									1	Remove Ramp
25996	4	SR-1649 (Ebenezer Church Rd)	Harbourgate Dr		15					6				1	Remove Ramp
25997	4	SR-1649 (Ebenezer Church Rd)	Harbourgate Dr										1		Type 3 Modified - 848D0609
25998	4	SR-1649 (Ebenezer Church Rd)	Harbourgate Dr		18			12						1	Remove Ramp
25999	5	SR-1649 (Ebenezer Church Rd)	Neiman Cv		18									1	Remove Ramp
26000	5	SR-1649 (Ebenezer Church Rd)	Neiman Cv										1		Standard - 848.06
26001	6	SR-1649 (Ebenezer Church Rd)	Clyden Cv		18									1	Remove Ramp
26002	6	SR-1649 (Ebenezer Church Rd)	Clyden Cv									1			Retrofit Warnings
26003	7	SR-1649 (Ebenezer Church Rd)	Poyner Rd									1			Retrofit Warnings
26004	7	SR-1649 (Ebenezer Church Rd)	Poyner Rd		18									1	Remove Ramp
Sub-Total for Ebenezer Church Rd From SR 1647 To SR 1664				0	175	0	0	21	0	6	0	2	7	9	

Note: ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page.