

ADA SUMMARY OF QUANTITIES - GLOBE RD FROM I-540 TO DEAD END

Municipality:	Raleigh Cary
Project Number:	2025CPT.05.02.20921.1
County:	Wake

Sheet No.
20

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove and Replace Curb & Gutter	2535000000-E (LF) 8" X 12" Concrete Curb	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove and Replace Sidewalk	2738000000-E (SY) Remove Sidewalk	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2612300000-N (EA) Retrofit Existing Concrete Curb Ramp	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2759000000-N (EA) Remove Curb Ramps	Improvement Type
12917	1	SR-1644 (Globe Rd)	Pinhall Company (111 First Flight Ln) Globe Rd Back Entrance										1		Type 1 Modified - 848.06
12918	1	SR-1644 (Globe Rd)	Pinhall Company (111 First Flight Ln) Globe Rd Back Entrance						6				1		Type 1 Modified - 848.06
12919	2	SR-1644 (Globe Rd)	DHL (400 Kitty Hawk Dr)										1		Type 1 Modified - 848.06
12920	2	SR-1644 (Globe Rd)	DHL (400 Kitty Hawk Dr)								1		1		Type 1 Modified - 848.06
12924	3	SR-1644 (Globe Rd)	Globe Center Dr										1		Type 1D - 848.06
12925	3	SR-1644 (Globe Rd)	Globe Center Dr		18			9						1	Remove Ramp
12926	3	SR-1644 (Globe Rd)	Globe Center Dr		20									1	Remove Ramp
12927	3	SR-1644 (Globe Rd)	Globe Center Dr						6				1		Type 1C - 848.06
12928	4	SR-1644 (Globe Rd)	Eaton Delivery Entrance (9400 Globe Center Dr)						6	10			1		Type 2A Modified - 848.06
12929	4	SR-1644 (Globe Rd)	Eaton Delivery Entrance (9400 Globe Center Dr)						6	6			1		Type 1C - 848.06
12930	4	SR-1644 (Globe Rd)	Waste Management (10405 Globe Rd) Entrance										1		Type 2A Modified - 848.06
Sub-Total for Globe Rd From I-540 To Dead End				0	38	0	0	9	24	16	1	0	9	2	

Note: ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page.