PROJECT NO.	SHEET NO.	TOTAL NO.
2025CPT.05.02.10921.1, etc.	22	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	0156000000-E REMOVAL OF EXISTING ASPHALT PAVEMENT	0163000000-E REMOVAL OF EXISTING CONCRETE PAVEMENT	1112000000-E GEOTEXTILE FOR SUBGRADE STABILIZATION	1099500000-E SHALLOW UNDERCUT	1099700000-E CLASS IV SUBGRADE STABILIZATION	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1308000000-E 0" TO 1" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX
							MI	FT	SY	SY	SY	CY	TON	TONS	SMI	TON	SY	SY	SY	SY	TONS	TONS	TON
2025CPT.05.02.10921.1	Wake	1	NC-54 E / HILLSBOROUGH ST	FROM PAVEMENT JOINT TO U-4437 WEST LIMITS	4	2	0.416	38						20	0.83	77	9,272			1,635		920	61
TOTAL FOR PROJ NO. 2025CPT.05.02.10921.1							**0.416**							**20**	**0.83**	**77**	**9,272**			**1,635**		**920**	**61**
2025CPT.05.02.20921.1	Wake	2	SR-5878 / N SALEM ST / OLD APEX RD	FROM W CHATHAM ST TO SR 1614	4	2	1.7	22-64	6	272	272	91	188	42	1.69	156	43,023			2,480	136	3,953	279
	Wake	3	SR-1011 / S SALEM ST/ OLD US 1 HWY	FROM NC 55 TO CHATHAM COUNTY	4	2	8.697	22-66	20	572	572	191	395	408	16.30	1,506	129,409			10,169	286	12,146	810
	Wake	4	SR-1644 / GLOBE RD	FROM BRG #761 TO END MAINT	3	2	0.72	22-60						22	0.87	80		1,350				1,085	74
	Wake	5	SR-1649 / EBENEZER CHURCH RD	FROM SR 1647 TO SR 1664	3	2	4.045	25-56						188	7.55	698		1,260		1,540		5,606	368
	Wake	6	SR-1766 / MELODY LN	FROM SR 1650 TO SR 1652	3	2	0.224	20						12	0.45	41		40		167		244	19
	Wake	7	SR-3046 / HOMESTEAD DR	FROM SR 1652 TO END MAINT	3	2	0.54	22										2,265		407		661	45
	Wake	8	SR-3107 / STONECREST CT	FROM SR 3106 TO CUL-DE-SAC	2	2	0.06	18						3								71	5
	Wake	9	SR-3106 / STONERIDGE DR	FROM SR 1649 TO DEAD END	2	2	0.48	20						24						180		437	31
	Wake	10	SR-3038 / RICHLAND DR	FROM SR 1649 TO END MAINT	2	2	0.27	18						14						125		207	21
	Wake	11	SR-1342 / POWELL DR	FROM NC 54 TO RR TRACKS	4	2	0.06	24						3	0.12	12	545			300		74	6
TOTAL FOR PROJ NO. 2025CPT.05.02.20921.1							**16.796**		**26**	**844**	**844**	**282**	**583**	**716**	**26.98**	**2,493**	**172,977**	**4,915**		**15,368**	**422**	**24,484**	**1,658**
2025CPT.05.02.20922.1	Wake	12	SR-3047 / SETTLERS CIR	FROM SR 3046 TO CUL-DE-SAC	1	2	0.06	22											282	277		61	5
	Wake	13	SR-3056 / HERITAGE CT	FROM SR 3046 TO CUL-DE-SAC	1	2	0.07	22											329	282		69	5
	Wake	14	SR-1203 / GREENLEA DR	FROM SR 1101 TO SR 1204	1	2	0.079	20						4						111		54	4
	Wake	15	SR-1204 / PINEDALE RD	FROM SR 1203 TO CUL-DE-SAC	1	2	0.179	18						9								145	10
	Wake	16	SR-3133 / CARE FREE CV	FROM SR 1204 TO CUL-DE-SAC	1	2	0.053	18						3								50	4
TOTAL FOR PROJ NO. 2025CPT.05.02.20922.1							**0.441**							**16**					**611**	**670**		**379**	**28**
GRAND TOTAL							**17.653**		**26**	**844**	**844**	**282**	**583**	**752**	**27.81**	**2,570**	**182,249**	**4,915**	**611**	**17,673**	**422**	**25,783**	**1,747**