



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TRANSPORTATION MANAGEMENT PLAN
GATES AND PASQUOTANK COUNTY



VICINITY MAP

INDEX OF SHEETS

SHEET NO.	TITLE
TMP-1	TITLE SHEET, AND INDEX OF SHEETS
TMP-1A THRU TMP-1C	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND, TEMPORARY PAVEMENT MARKINGS, MANAGEMENT STRATEGIES, GENERAL NOTES, AND LOCAL NOTES
TMP-1D	TEMPORARY SHORING NOTES & DETAILS
TMP-1E	PHASING NOTES
TMP-2A	TEMPORARY SHORING NOTES
TMP-3A & 3B	PHASE I DETAILS
TMP-4A & 4B	PHASE II DETAILS
TMP-5A & 5B	PHASE III DETAILS
TMP-6A & 6B	PHASE IV DETAILS

SHEET NO.
TMP 1


R-5808

TIP PROJECT:

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

APPROVED: _____
DATE: 9/6/2024

SEAL



PLANS PREPARED BY:


Brandon Gregg

Vince Riccio, P.E.

NCDOT CONTACTS:

Ryan Shook
PROJECT ENGINEER

PROJECT DESIGN ENGINEER



K:\VAB_RDM\17093000 - R-5808 (US 158)\Traffic\TrafficControl\TCPSheets\R5808_TMP_1shdgn 7/16/2024

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANAUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.01	WORK ZONE ADVANCED WARNING SIGNS
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.04	TEMPORARY SHOULDER CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1130.01	DRUMS
1145.01	BARRICADES
1150.01	FLAGGING DEVICES
1160.01	TEMPORARY CRASH CUSHION
1170.01	PORTABLE CONCRETE BARRIER
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - (PERMANENT AND TEMPORARY)

GENERAL

-  DIRECTION OF TRAFFIC FLOW
-  DIRECTION OF PEDESTRIAN TRAFFIC FLOW
-  EXIST. PVMT.
-  NORTH ARROW
-  PROPOSED PVMT.
-  WORK AREA
-  TEMPORARY PAVEMENT

TRAFFIC CONTROL DEVICES

-  BARRICADE (TYPE III)
-  DRUM
-  TEMPORARY CRASH CUSHION
-  ANCHORED PORTABLE CONCRETE BARRIER

TEMPORARY SIGNING

-  STATIONARY SIGN

PAVEMENT MARKINGS

-  EXISTING LINES
-  TEMPORARY LINES

TEMPORARY RAISED PAVEMENT MARKERS

-  YELLOW/YELLOW

LEGEND

TEMPORARY PAVEMENT MARKING


- PAVEMENT MARKING LINES:
- P1 - PAINT (4" WHITE, 2X) EDGELINE
- P13 - PAINT (4" YELLOW, 2X) DOUBLE CENTER LINE
- P61 - PAINT (24" WHITE, 2X) STOP BAR

- TEMPORARY RAISED PAVEMENT MARKERS:
- MH - YELLOW & YELLOW


Kimley»Horn

APPROVED: _____ DATE: _____

SEAL



9/6/2024



ROADWAY STANDARD
DRAWINGS & LEGEND

TRANSPORTATION
MANAGEMENT
STRATEGIES

PROPOSED IMPROVEMENTS ALONG US 158 WILL BE CONSTRUCTED WHILE MAINTAINING TRAFFIC ON TEMPORARY ON-SITE DETOUR, AND USING TEMPORARY LANE AND SHOULDER CLOSURES.

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS, OR RESULT IN DUPLICATE, OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATIONS MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING OR REMOVAL OF DEVICES, AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

TIME RESTRICTIONS

A) DO NOT CLOSE OR NARROW TRAVEL LANES AS FOLLOWS:

ROAD NAME	DAY AND TIME RESTRICTIONS
US 158	MONDAY - FRIDAY, FROM THIRTY (30) MINUTES BEFORE SUNSET TO THIRTY (30) MINUTES AFTER SUNRISE THE FOLLOWING DAY AND SATURDAY, FROM THIRTY (30) MINUTES BEFORE SUNSET TO THIRTY (30) MINUTES AFTER SUNRISE THE FOLLOWING MONDAY

B) DO NOT CLOSE OR NARROW TRAVEL LANES DURING HOLIDAYS AND SPECIAL EVENTS AS FOLLOWS:

ROAD NAME	DAY AND TIME RESTRICTIONS
US 158	
HOLIDAY	
	1. FOR ANY UNEXPECTED OCCURRENCE THAT CREATES UNUSUALLY HIGH TRAFFIC VOLUMES, AS DIRECTED BY THE ENGINEER.
	2. FOR NEW YEAR'S, BETWEEN THE HOURS OF 6:00 A.M. DECEMBER 31 st TO 7:00 P.M. JANUARY 2 ND . IF NEW YEAR'S DAY IS ON A FRIDAY, SATURDAY, SUNDAY, OR MONDAY THEN UNTIL 7:00 P.M. THE FOLLOWING TUESDAY.
	3. FOR EASTER, BETWEEN THE HOURS OF 6:00 A.M. THURSDAY AND 7:00 P.M. MONDAY.
	4. FOR MEMORIAL DAY, BETWEEN THE HOURS OF 6:00 A.M. FRIDAY TO 7:00 P.M. TUESDAY.
	5. FOR INDEPENDENCE DAY, BETWEEN THE HOURS OF 6:00 A.M. THE DAY BEFORE INDEPENDENCE DAY AND 7:00 P.M. THE DAY AFTER INDEPENDENCE DAY.
	IF INDEPENDENCE DAY IS ON A FRIDAY, SATURDAY, SUNDAY OR MONDAY THEN BETWEEN THE HOURS OF 6:00 A.M. THE THURSDAY BEFORE INDEPENDENCE DAY AND 7:00 P.M. THE TUESDAY AFTER INDEPENDENCE DAY.
	6. FOR LABOR DAY, BETWEEN THE HOURS OF 6:00 A.M. FRIDAY AND 7:00 P.M. TUESDAY.
	7. FOR THANKSGIVING DAY, BETWEEN THE HOURS OF 6:00 A.M. TUESDAY TO 7:00 P.M. MONDAY.
	8. FOR CHRISTMAS, BETWEEN THE HOURS OF 6:00 A.M. THE FRIDAY BEFORE THE WEEK OF CHRISTMAS DAY AND 7:00 P.M. THE FOLLOWING TUESDAY AFTER THE WEEK OF CHRISTMAS.

C) DO NOT CLOSE ROADS AS FOLLOWS:

ROAD NAME	DAY AND TIME RESTRICTIONS
US 158	ANYTIME

D) DO NOT CONDUCT ANY HAULING OPERATIONS AGAINST THE FLOW OF TRAFFIC OF AN OPEN TRAVELWAY UNLESS THE HAULING OPERATION IS PROTECTED BY BARRIER OR GUARDRAIL OR AS DIRECTED BY THE ENGINEER.

LANE AND SHOULDER CLOSURE REQUIREMENTS

E) REMOVE LANE CLOSURE DEVICES FROM THE LANE WHEN WORK IS NOT BEING PERFORMED BEHIND THE LANE CLOSURE OR WHEN A LANE CLOSURE IS NO LONGER NEEDED OR AS DIRECTED BY THE ENGINEER.

F) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 15 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.

G) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO AN UNDIVIDED FACILITY AND WITHIN 5 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO A DIVIDED FACILITY AND WITHIN 10 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

H) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN A LANE OF TRAVEL OF AN UNDIVIDED OR DIVIDED FACILITY, CLOSE THE LANE ACCORDING TO THE TRAFFIC CONTROL PLANS, ROADWAY STANDARD DRAWINGS, OR AS DIRECTED BY THE ENGINEER. CONDUCT THE WORK SO THAT ALL PERSONNEL AND/OR EQUIPMENT REMAIN WITHIN THE CLOSED TRAVEL LANE.

I) DO NOT WORK SIMULTANEOUSLY WITHIN 15 FT ON BOTH SIDES OF AN OPEN TRAVELWAY UNLESS PROTECTED WITH GUARDRAIL OR BARRIER.

PAVEMENT EDGE DROP OFF REQUIREMENTS

J) BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPENED TRAVEL LANE THAT HAS AN EDGE OF PAVEMENT DROP-OFF AS FOLLOWS:

BACKFILL DROP-OFFS THAT EXCEED 2 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS OF 45 MPH OR GREATER.

BACKFILL DROP-OFFS THAT EXCEED 3 INCHES ON ROADWAYS WITH POSTED SPEED LIMITS LESS THAN 45 MPH.

BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

K) DO NOT EXCEED A DIFFERENCE OF 2 INCHES IN ELEVATION BETWEEN OPEN LANES OF TRAFFIC FOR NOMINAL LIFTS OF 1.5 INCHES. INSTALL ADVANCE WARNING "UNEVEN LANES" SIGNS (W8-11) 500 FT IN ADVANCE AND A MINIMUM OF EVERY HALF MILE THROUGHOUT THE UNEVEN AREA.

TRAFFIC PATTERN ALTERATIONS

L) NOTIFY THE ENGINEER THIRTY (30) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

Kimley»Horn

APPROVED: _____ DATE: _____

SEAL



9/6/2024



TRANSPORTATION
OPERATIONS
PLAN

GENERAL NOTES (CONT.)

LOCAL NOTES

SIGNING

- M) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- N) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC BARRIER

- O) INSTALL TEMPORARY BARRIER ACCORDING TO THE TRANSPORTATION MANAGEMENT PLANS A MAXIMUM OF TWO (2) WEEKS PRIOR TO BEGINNING WORK IN ANY LOCATION. ONCE TEMPORARY BARRIER IS INSTALLED AT ANY LOCATION PROCEED IN A CONTINUOUS MANNER TO COMPLETE THE PROPOSED WORK IN THAT LOCATION UNLESS OTHERWISE STATED IN THE TRANSPORTATION MANAGEMENT PLANS OR AS DIRECTED BY THE ENGINEER.

DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE.

ONCE TEMPORARY BARRIER IS INSTALLED AT ANY LOCATION AND NO WORK IS PERFORMED BEHIND THE TEMPORARY BARRIER FOR A PERIOD LONGER THAN TWO (2) MONTHS, REMOVE / RESET TEMPORARY BARRIER AT NO COST TO THE DEPARTMENT UNLESS OTHERWISE STATED IN THE TRANSPORTATION MANAGEMENT PLANS, TEMPORARY BARRIER IS PROTECTING A HAZARD, OR AS DIRECTED BY THE ENGINEER.

INSTALL TEMPORARY BARRIER WITH THE TRAFFIC FLOW BEGINNING WITH THE UPSTREAM SIDE OF TRAFFIC. REMOVE TEMPORARY BARRIER AGAINST THE TRAFFIC FLOW BEGINNING WITH THE DOWNSTREAM SIDE OF TRAFFIC.

INSTALL AND SPACE DRUMS NO GREATER THAN TWICE THE POSTED SPEED LIMIT (MPH) TO CLOSE OR KEEP THE SECTION OF THE ROADWAY CLOSED UNTIL THE TEMPORARY BARRIER CAN BE PLACED OR AFTER THE TEMPORARY BARRIER IS REMOVED.

- P) PROTECT THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER AT ALL TIMES DURING THE INSTALLATION AND REMOVAL OF THE BARRIER BY EITHER A TRUCK MOUNTED ATTENUATOR (MAXIMUM 72 HOURS) OR A TEMPORARY CRASH CUSHION.

PROTECT THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER FROM ONCOMING TRAFFIC AT ALL TIMES BY A TEMPORARY CRASH CUSHION UNLESS THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER IS OFFSET FROM ONCOMING TRAFFIC AS FOLLOWS OR AS SHOWN IN THE PLANS: (SEE ALSO 1101.05)

POSTED SPEED LIMIT	MINIMUM OFFSET
40 OR LESS	15 FT
45 - 50	20 FT
55	25 FT
60 MPH or HIGHER	0 FT

TRAFFIC CONTROL DEVICES

- Q) WHEN LANE CLOSURES ARE NOT IN EFFECT SPACE CHANNELIZING DEVICES IN WORK AREAS NO GREATER IN FEET THAN TWICE THE POSTED SPEED LIMIT (MPH) EXCEPT, 10 FT ON-CENTER IN RADII, AND 3 FT OFF THE EDGE OF AN OPEN TRAVELWAY. REFER TO STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES SECTIONS 1130 (DRUMS), 1135 (CONES) AND 1180 (SKINNY DRUMS) FOR ADDITIONAL REQUIREMENTS.
- R) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.
- S) PLACE ADDITIONAL SETS OF THREE CHANNELIZING DEVICES (DRUMS) PERPENDICULAR TO THE EDGE OF TRAVELWAY ON 500 FT CENTERS WHEN UNOPENED LANES ARE CLOSED TO TRAFFIC.

PAVEMENT MARKINGS AND MARKERS

- T) INSTALL TEMPORARY PAVEMENT MARKINGS AND TEMPORARY PAVEMENT MARKERS ON INTERIM LAYERS OF PAVEMENT AS FOLLOWS:

ROAD NAME	MARKING	MARKER
US 158	PAINT	TEMPORARY RAISED

- U) PLACE ONE APPLICATION OF PAINT FOR TEMPORARY TRAFFIC PATTERNS. PLACE A SECOND APPLICATION OF PAINT SIX (6) MONTHS AFTER THE INITIAL APPLICATION AND EVERY SIX MONTHS AS DIRECTED BY THE ENGINEER.
- V) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- W) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS BY THE END OF EACH DAY'S OPERATION.

MISCELLANEOUS

- MM) IN THE EVENT A TIE-IN CANNOT BE MADE IN ONE DAY'S TIME, BRING THE TIE-IN AREA TO AN APPROPRIATE ROADWAY ELEVATION AS DETERMINED BY THE ENGINEER. PLACE BLACK ON ORANGE "LOOSE GRAVEL" SIGNS (W8-7) AND BLACK ON ORANGE "PAVEMENT ENDS" SIGNS (W8-3) 500 FT AND 1000 FT RESPECTIVELY IN ADVANCE OF THE UNEVEN AREAS. USE DRUMS TO DELINEATE TEH EDGE OF ROADWAY ALONG UNPAVED AREAS.

K:\VAB_RDM\17093000 - R-5808 (US 158)\Traffic\TrafficControl\CP\Steel\RS808_TMP_1shdgn

7/16/2024

Kimley»Horn

APPROVED: _____ DATE: _____

SEAL

DESIGNED BY
SAVANA RICCO
SEAL
6E65472643ED43E1
ENGINEER
VINCENT E. RICCO

9/6/2024

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL



TRANSPORTATION
OPERATIONS
PLAN



- 1- REFER TO THE TRAFFIC CONTROL PLANS FOR TEMPORARY SHORING LOCATIONS AND NOTES.
- 2- REFER TO THE "TEMPORARY SHORING" STANDARD PROVISION FOR INFORMATION ABOUT TEMPORARY SHORING AND PORTABLE CONCRETE BARRIER (PCB).
- 3- PCB IS REQUIRED IF TEMPORARY SHORING/WALL IS LOCATED WITHIN THE CLEAR ZONE IN ACCORDANCE WITH THE AASHTO ROADSIDE DESIGN GUIDE. DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE.
(CONTACT NCDOT PAVEMENT MANAGEMENT FOR APPLICABLE PAVEMENT DESIGN).
- 4- BASED ON THE CLEAR DISTANCE, OFFSET, DESIGN SPEED AND PAVEMENT TYPE, CHOOSE AN UNANCHORED OR ANCHORED PCB FROM THE TABLE SHOWN IN FIGURE B. CLEAR DISTANCE IS DEFINED AS SHOWN IN FIGURE A AND OFFSET IS DEFINED AS SHOWN IN FIGURE B.
- 5- AT THE CONTRACTOR'S OPTION OR IF THE MINIMUM REQUIRED CLEAR DISTANCE IS NOT AVAILABLE, SET PCB NEXT TO AND UP AGAINST THE TRAFFIC SIDE OF THE TEMPORARY SHORING/WALLS EXCEPT FOR BARRIER ABOVE TEMPORARY WALLS. PCB WITH THE MINIMUM REQUIRED CLEAR DISTANCE IS REQUIRED ABOVE TEMPORARY WALLS.
- 6- USE NCDOT PORTABLE CONCRETE BARRIER (PCB) IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1170.01 AND SECTION 1170 OF THE STANDARD SPECIFICATIONS.
- 7- SET PCB WITH A MINIMUM HORIZONTAL DISTANCE OF 2 FT BETWEEN THE FRONT FACE OF THE BARRIER AND THE EDGE OF THE NEAREST TRAFFIC LANE AS SHOWN IN FIGURE A UNLESS OTHERWISE SHOWN IN THE PLANS OR APPROVED BY THE ENGINEER.
- 8- FOR PCB ABOVE AND BEHIND TEMPORARY WALLS, PROVIDE A MINIMUM DISTANCE OF 3 FT BETWEEN THE EDGE OF PAVEMENT AND THE WALL FACE AS SHOWN IN FIGURE A. IF THIS MINIMUM REQUIRED DISTANCE IS NOT AVAILABLE, CONTACT THE ENGINEER.
- 9- TABLE SHOWN IN FIGURE B IS BASED ON NCDOT RESEARCH PROJECT NO. 2005-010 WITH VEHICLE TYPE USED FOR NCHRP 350 CRASH TESTS.

*** See Figure Below**




FIGURE B
Kimley»»Horn

APPROVED: _____	DATE: _____	 TEMPORARY SHORING NOTES & DETAILS
 Seal 9/6/2024		

PROJ. REFERENCE NO.	SHEET NO.
R-5808	TMP-1E

PHASING

GENERAL

PHASES 1-4 ARE INTENDED TO CONSTRUCT THE BOX CULVERT UNDER US 158 UTILIZING RSD 1101.03 FOR TEMPORARY ROAD CLOSURE WITH ONSITE DETOUR.

PHASE 1

WHILE MAINTAINING TRAFFIC IN THE EXISTING PATTERN SHIFTED PER PLAN AND USING RSD 1101.04 FOR SHOULDER CLOSURES AS NECESSARY, PERFORM THE FOLLOWING:

- STEP 1: INSTALL WORK ZONE ADVANCED WARNING SIGNS IN ACCORDANCE WITH RSD 1101.01.
STEP 2: INSTALL TEMPORARY STRIPING AND REMOVE CONFLICTING MARKINGS, INSTALL TEMPORARY CONCRETE BARRIER AND CRASH CUSHION IN FRONT OF SHORING AND EXCAVATION AREA TO PROTECT EXISTING TRAFFIC.
STEP 3: INSTALL TEMPORARY SHORING NO. 1, 2 AND 3 IN ACCORDANCE WITH TMP 3A-3B TO SUPPORT TEMPORARY ROAD AS WELL AS DIVERTING STREAM FLOW.
STEP 4: CONSTRUCT TEMPORARY ROAD AND PORTION OF 14' X 7' PERMANENT BOX CULVERT EXTENSION SHOWN ON TMP 3B.
STEP 5: INSTALL TEMPORARY PIPES THRU SHORING TO MAINTAIN FLOW.

PHASE 2

WHILE MAINTAINING TRAFFIC IN THE EXISTING PATTERN SHIFTED PER PLAN AND USING RSD 1101.04 FOR SHOULDER CLOSURES AS NECESSARY, PERFORM THE FOLLOWING:

- STEP 1: INSTALL TEMPORARY SHORING NO. 4 AND 5 IN ACCORDANCE WITH TMP 4A-4B TO SUPPORT TEMPORARY ROAD AS WELL AS DIVERTING STREAM FLOW.
STEP 2: CONSTRUCT TEMPORARY ROAD AND PORTION OF 14' X 7' PERMANENT BOX CULVERT EXTENSION SHOWN ON TMP 4B.
STEP 3: INSTALL TEMPORARY PIPES THROUGH SHORING TO MAINTAIN FLOW.
USING RSD 1101.02, SHEET 1 OF 19, PREFORM THE FOLLOWING:
STEP 4: INSTALL TEMPORARY CONCRETE BARRIER AND CRASH CUSHIONS ALONG BOTH EDGES OF TEMPORARY ROAD.
STEP 5: REMOVE TEMPORARY CONCRETE BARRIER AND CRASH CUSHIONS INSTALLED IN PHASE 1
STEP 6: INSTALL TEMPORARY PAVEMENT MARKINGS AND REMOVE CONFLICTING MARKINGS.
STEP 7: SHIFT TRAFFIC ONTO TEMPORARY ROADWAY.

PHASE 3

WITH TRAFFIC SHIFTED ONTO TEMPORARY DETOUR ROADWAY BEHIND TEMPORARY PCB AND AWAY FROM TRAFFIC, PERFORM THE FOLLOWING IN ACCORDANCE WITH RSD 1101.03:

- STEP 1: INSTALL TEMPORARY SHORING NO. 6, 7, 9 AND 11 IN ACCORDANCE WITH TMP 5B TO FURTHER DIVERT THE STREAM.
STEP 2: CONSTRUCT REMAINDER OF 14' X 7' PERMANENT BOX CULVERT REPLACEMENT/EXTENSION AS SHOWN ON TMP 5B.
STEP 3: REMOVE SHORING NO. 6, 9 AND 11 AS NECESSARY TO RESTORE STREAM FLOW.

PHASE 4

STAGE 1:

WITH TRAFFIC SHIFTED ONTO TEMPORARY DETOUR ROADWAY BEHIND TEMPORARY PCB AND AWAY FROM TRAFFIC, PERFORM THE FOLLOWING IN ACCORDANCE WITH RSD 1101.03, :

- STEP 1: INSTALL TEMPORARY SHORING NO. 8, 10 AND 12 IN ACCORDANCE WITH TMP 6B TO FURTHER DIVERT THE STREAM.
STEP 2: CONSTRUCT REMAINDER OF (1) 14' X 7' PERMANENT BOX CULVERT REPLACEMENT/EXTENSIONS AS SHOWN ON TMP 6B.
STEP 3: REMOVING SHORING AS NECESSARY TO RESTORE STREAM FLOW.
STEP 4: REMOVE ALL TEMPORARY SHORING AND RESTORE CONDITIONS BACK TO EXISTING EXCEPT WHERE ROADWAY CAN BE INTEGRATED INTO PERMANENT CONDITION.

STAGE 2: (NOT SHOWN)

USING RSD 1101.02, SHEET 1 OF 19, PERFORM THE FOLLOWING:

- STEP 1: REMOVE TEMPORARY PCB ALONG BOTH SIDES OF EXISTING US-158
STEP 2: INSTALL TEMPORARY PAVEMENT MARKING TO MATCH EXISTING CONDITION
STEP 3: SHIFT TRAFFIC BACK ON US-158 IN THE EXISTING 2L2W PATTERN

PHASE 5 (NOT SHOWN)

WHILE MAINTAINING TRAFFIC IN THE EXISTING PATTERN AND USING RSD 1101.02 AND 1150.01 FOR LANE CLOSURES AND FLAGGING PROCEDURES AS NECESSARY, PERFORM THE FOLLOWING FROM -L- STA 45+75 +/- TO -L- STA 234+37 +/-:

- STEP 1: USING FLAGGERS, COMPLETE UNDERCUT EXCAVATION PER GEOTECHNICAL RECOMMENDATION AND RESTORE GROUND.
STEP 2: INSTALL SETTLEMENT GUAGES IN ACCORDANCE WITH SHEET 2G-1 PRIOR TO PLACING BORROW.
STEP 3: CONSTRUCT PROPOSED WIDENING TO THE SOUTH OF -L- INCLUDING SURCHARGE IN ACCORDANCE WITH SHEET 2G-1.
STEP 4: AT THE COMPLETION OF THE WAITING PERIOD OR AS DIRECTED BY THE GEOTECH ENGINEER, REMOVE SURCHARGE AND CONSTRUCT PROPOSED PAVEMENT.
STEP 5: CONTRACTOR SHALL RESTORE LANES TO MATCH EXISTING LANE WIDTHS AT THE END OF EACH WORK DAY.

PHASE 6 (NOT SHOWN)

SHIFT TRAFFIC TO PROPOSED EASTBOUND LANES USING RSD 1101.02 AND 1150.01 FOR LANE CLOSURES AND FLAGGING PROCEDURES AS NECESSARY, PERFORM THE FOLLOWING FROM -L- STA 45+75 +/- TO -L- STA 234+37 +/-:

- STEP 1: USING FLAGGERS, CONSTRUCT PROPOSED SHOULDERS TO THE NORTH OF -L- (TRAFFIC SHIFTED ON THE NEWLY CONSTRUCTED WIDENING)
STEP 2: CONTRACTOR SHALL RESTORE LANES TO MATCH EXISTING LANE WIDTHS AT THE END OF EACH WORK DAY.

PHASE 7 (NOT SHOWN)

USING RSD 1101.02, SHEET 1 OF 19, PERFORM THE FOLLOWING:

- STEP 1: REMOVE TEMPORARY PAVEMENTS, CONSTRUCTED IN PHASE 1 AND PHASE 2
STEP 2: PLACE FINAL SURFACE COURSE AND FINAL PAVEMENT MARKINGS ON US-158 FROM -L- STA 17+59 +/- TO -L- STA 234+37 +/-
STEP 3: REMOVE ALL TEMPORARY TC DEVICES

K:\VAB_RDM\17093000 - R-5808 (US 158)\Traffic\TrafficControl\CP\Steel\R5808_TMP_1shdgn

7/16/2024

Kimley»Horn

APPROVED: _____ DATE: _____		PHASING NOTES
SEAL  9/6/2024		

K:\VAB_RDM\17093000 - R-5808 (US 158)\Traffic\TrafficControl\CP\Steels\R5808_TMP_PSH_Q2adgn

7/16/2024



155 N. Market Street
Washington, NC 27880
Telephone (252) 623-2083
Fax (252) 623-2082
www.catlinusa.com

June 12, 2024

MEMORANDUM TO: Vincent Risco, P.E.
Project Engineer
Kimley - Horn

FROM: Lee Stone, PG
Senior Engineering Geologist
CATLIN Engineers and Scientists

STATE PROJECT: 46972.1.1 (R-5808)
F.A. NUMBER: NHP - 0158(076)
COUNTY: Gates

DESCRIPTION: US 158 from the Intersection of SR 1002 (Acorn Hill Rd.) and US 158 to the Pasquotank County Line

SUBJECT: Revised Geotechnical Recommendations for Temporary Shoring

CATLIN Engineers and Scientists (CATLIN) have revised the previous Geotechnical Recommendations to eliminate the temporary shoring for undercut excavations. This recommendation report supersedes the Geotechnical Recommendations for Temporary Shoring Dated November 13, 2023.

Shoring Location No.	Begin Station and Offset (±)	End Station and Offset (±)	Estimated Average Height	Estimated Maximum Height	Shoring Location Type
TM-1	21+51, 47' RT	24+61, 47' RT	3.6	8.0	Roadway
TM-2	24+34, 7' RT	24+61, 7' RT	3.6	4.0	Structure
TM-3	24+61, 7' RT	24+61, 47' RT	9.0	10.0	Structure
TM-4	24+61, 7' RT	24+87, 7' RT	3.6	4.0	Structure
TM-5	24+61, 47' RT	27+79, 37' RT	4.5	8.0	Structure
TM-6	24+59, 46' LT	25+07, 46' LT	6.5	8.0	Structure
TM-7	24+59, 24' LT	24+59, 46' LT	9.0	10.0	Structure
TM-8	24+26, 46' LT	24+61, 46' LT	6.5	8.0	Roadway
TM-9	24+61, 11.5' RT	24+87, 11' RT	3.6	4.0	Structure
TM-10	24+34, 12' RT	24+61, 12' RT	3.6	4.0	Structure
TM-11	25+07, 46' LT	25+07, 23' LT	8.0	10.0	Structure
TM-12	24+27, 23' LT	24+26, 46' LT	8.0	10.0	Structure

R-5808 Temporary Shoring

Page 2 of 8

Shoring Location No. TM-1

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 21+51±, 47' RT TO 24+61±, 47' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 21+51±, 47' RT TO 24+61±, 47' RT.

Shoring Location No. TM-2

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+34±, 7' RT TO 24+61±, 7' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+34±, 7' RT TO 24+47±, 7' RT.

DO NOT USE CANTILEVER, BRACED OR ANCHORED SHORING FOR TEMPORARY SHORING FROM STATION -L- 24+47±, 7' RT TO 24+61±, 7' RT.

AT THE CONTRACTOR'S OPTION, USE A STANDARD TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+47±, 7' RT TO 24+61±, 7' RT. SEE GEOTECHNICAL STANDARD DETAIL NO. 1801.02 FOR STANDARD TEMPORARY WALLS.

R-5808 Temporary Shoring

Page 3 of 8

Shoring Location No. TM-3

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+61±, 7' RT TO 24+61±, 47' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+61±, 7' RT TO 24+61±, 47' RT.

Shoring Location No. TM-4

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+61±, 7' RT TO 24+87±, 7' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+72±, 7' RT TO 24+87±, 7' RT.

DO NOT USE CANTILEVER, BRACED OR ANCHORED SHORING FOR TEMPORARY SHORING FROM STATION -L- 24+61±, 7' RT TO 24+72±, 7' RT.

AT THE CONTRACTOR'S OPTION, USE A STANDARD TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+61±, 7' RT TO 24+72±, 7' RT. SEE GEOTECHNICAL STANDARD DETAIL NO. 1801.02 FOR STANDARD TEMPORARY WALLS.

R-5808 Temporary Shoring

Page 4 of 8

Shoring Location No. TM-5

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+61±, 47' RT TO 27+79±, 37' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+61±, 47' RT TO 27+79±, 37' RT.

Shoring Location No. TM-6

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+59±, 46' LT TO 25+07±, 46' LT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+59±, 46' LT TO 25+07±, 46' LT.

R-5808 Temporary Shoring

Page 5 of 8

Shoring Location No. TM-7

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+59±, 24' LT TO 24+61±, 46' LT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+59±, 24' LT TO 24+61±, 46' LT.

Shoring Location No. TM-8

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+26±, 46' LT TO 24+61±, 46' LT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+26±, 46' LT TO 24+61±, 46' LT.

R-5808 Temporary Shoring

Page 6 of 8

Shoring Location No. TM-9

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+61±, 11.5' RT TO 24+87±, 11' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+61±, 11.5' RT TO 24+87±, 11'.

Shoring Location No. TM-10

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+34±, 12' RT TO 24+61±, 12' RT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+34±, 12' RT TO 24+61±, 12' RT.

R-5808 Temporary Shoring

Page 7 of 8

Shoring Location No. TM-11

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 25+07±, 46' LT TO 24+07±, 23' LT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 25+07±, 46' LT TO 24+07±, 23' LT.

Shoring Location No. TM-12

FOR TEMPORARY SHORING AND POSITIVE PROTECTION FOR TEMPORARY SHORING, SEE PLANS AND TEMPORARY SHORING PROVISION.

BEFORE BEGINNING TEMPORARY SHORING DESIGN OR CONSTRUCTION, SURVEY EXISTING GROUND ELEVATIONS IN THE VICINITY OF SHORING LOCATIONS TO DETERMINE ACTUAL SHORING HEIGHTS.

DESIGN TEMPORARY SHORING FROM STATION -L- 24+27±, 23' LT TO 24+26±, 46' LT, FOR THE FOLLOWING ASSUMED SOIL PARAMETERS AND GROUNDWATER ELEVATION:

UNIT WEIGHT (γ) = 120 PCF
FRICTION ANGLE (ϕ) = 0 DEGREES (EL≥14 FT±)
= 32 DEGREES (EL<14 FT±)
COHESION (c) = 750 PSF (EL≥14 FT±)
= 0 PSF (EL<14 FT±)
GROUNDWATER ELEVATION = 23 FT±

DO NOT USE A TEMPORARY WALL FOR TEMPORARY SHORING FROM STATION -L- 24+27±, 23' LT TO 24+26±, 46' LT.

Prepared By:



J. Lee Stone, PG
Senior Engineering Geologist



Yanhui Liu, PE, PhD.
Senior Geotechnical Engineer

Attachments: Standard Temporary Shoring provision (4 pages)
Standard Detail No. 1801.02 - Standard Temporary Wall (3 sheets)

Kimley»Horn

APPROVED: _____ DATE: _____


SEAL



TEMPORARY
SHORING
NOTES


THE TEMPORARY SHORING NOTES SHOWN ON THIS SHEET WERE PROVIDED THROUGH SEALED DOCUMENTS FROM THE GEOTECHNICAL ENGINEER OF RECORD.

PROJ. REFERENCE NO.	SHEET NO.
R-5808	TMP-3A




GRAPHIC SCALE


NC GRID
83/NA 2011
NAD 83/NA 2011



A-A
-L- STA. 21+50



C-C
-L- STA. 24+00



APPROVED: _____ DATE: _____

SEAL

Downloaded by:
VINCENT E. RICCO
655726 A543ED34...

9/6/2024






Kimley»Horn

TRAFFIC CONTROL
PHASE I

K:\VAB_RDM\N7093000 - R-5808 (US 158)\TrafficControl\TCL\Sheets\R5808_TMP_PSH_03a.dgn

8/13/2024



Kimley»»Horn

TRAFFIC CONTROL PHASE I

APPROVED: _____ DATE: _____


DECLARED BY: _____

SEAL


APR 27 2024
PROFESSIONAL SEAL
VINCENT E. RICCO
655734
A543 ED 34...

ENGINEER
VINCENT E. RICCO

9/6/2024




PROJ. REFERENCE NO.	SHEET NO.
R-5808	TMP-4A



GRAPHIC SCALE

NC GRID
NAD 83/NA 2011




END
ROAD
WORK
48" X 24"

ROAD
WORK
AHEAD
48" X 48"



SHOULDER
WORK
48" X 48"

BEGIN TIP PROJECT R-5808
-L- POT Sta. 17+59.05



BEGIN TEMPORARY ANCHORED PCB
-L- STA. 21+97
CRASH CUSHION

MATCHLINE -L- STA. 24+00 (SEE TMP-3B)




APPROVED: _____ DATE: _____

SEAL







Downloaded by:
VINCENT E. RICCO
655726A543ED34...

7/16/2024



Kimley»Horn

**TRAFFIC CONTROL
PHASE II**






Kimley»Horn

APPROVED: _____ DATE: _____
SEAL
Downloaded by:
PROFESSIONAL SEAL
655726
ENGINEER
VINCENT E. RICCO
9/6/2024



TRAFFIC CONTROL
PHASE II




Kimley»»Horn

TRAFFIC CONTROL PHASE III





APPROVED: _____ DATE: _____

Seal of the Court of Professional Jurisdiction
JUDICIAL PROFESSIONAL BOARD
INCE RICO
SEAL
855726 A543 ED34...
ENGINEER
VINCENT E. RICCO
9/6/2024





NC GRID
NAD 83/NA 2011



Kimley»Horn

APPROVED: _____ DATE: _____

SEAL

DESIGNED BY:
Vincent E. Riccio

PROFESSIONAL ENGINEER
No. 655726

EXPIRATION DATE: 12/31/24


9/6/2024





TRAFFIC CONTROL
PHASE III

K:\VAB_RDM\NIT093000 - R-5808 (US 15B)\TrafficControl\CP\Sheets\R5808_TMP_PSH_05b.dgn

8/13/2024



110
NC GRID
NAD 83/NA 2011



MATCHLINE -L- STA. 24+00 (SEE TMP 5B)

Kimley»Horn



TRAFFIC CONTROL
PHASE IV

APPROVED: _____ DATE: _____

SEAL

Downloaded by: Vincent E. Riccio
655726 A543ED34...

9/6/2024




10
FULL STA. 10+00.00

END
ROAD
WORK

ROAD
WORK
AHEAD

45
M.P.H.
W1-4R
48' X 48'
W3-1
24' X 24'



-L- US RTE 158

SR 1002 FOLLY RD

SR 1002 ACORN HILL RD

BEGIN TIP PROJECT R-5808
-L- POT Sta. 17+59.05

TEMPORARY DOUBLE YELLOW CENTERLINE WITH
YELLOW/YELLOW PAVEMENT MARKERS ALONG
CENTERLINE @ 20' SPACING



BEGIN TEMPORARY ANCHORED PCB
-L- STA. 22+31.85
CRASH CUSHION

BEGIN TEMPORARY ANCHORED PCB
-L- STA. 18+21.54
CRASH CUSHION




TEMPORARY WHITE EDGE LINE

PHASE I C-C
TEMPORARY SHORING

PROJ. REFERENCE NO.	SHEET NO.
R-5808	TMP-6B



MATCHLINE -L- STA 24+00 (SEE SHEET TMP-5A)



Kimley»Horn

APPROVED: _____ DATE: _____

SEAL

DESIGNED BY: Vincent E. Riccio


SEAL

655726

ENGINEER

VINCENT E. RICCIO

9/6/2024



TRAFFIC CONTROL
PHASE IV

K:\VAB_RDM\NIT093000 - R-5808 (US 158)\Traffic\TrafficControl\CP\Sheets\RS5808_TMP_PSH_06b.dgn

8/13/2024