

LOCATION SKETCH

INFORMATION INDICATED ON THE LOCATION SKETCH SHALL BE CONSIDERED GENERAL INFORMATION ONLY, CONTRACTOR SHALL CONFIRM, THROUGH OTHER SOURCES, SPECIFIC INFORMATION REGARDING BRIDGES, ROADWAY, UTILITIES, THE SURROUNDING AREA, AND ANY OTHER ASPECTS THAT MAY BE NECESSARY TO PERFORM AND COMPLETE THE PROJECT.

	BRIDGE CO	ORDINATES
I	LATITUDE	LONGITUDE
	34°-19'-20.38''	78°-27'-18.10''

GENERAL NOTES

SEE CONTRACT DOCUMENTS FOR LANE WIDTHS, SEQUENCING AND OTHER TRAFFIC CONTROL MEASURES FOR STAGING OF OVERLAY SURFACE PREPARATION AND POLYMER CONCRETE (PC) PLACEMENT. THE BRIDGE SURFACE AND/OR TRAFFIC.

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT DUE TO THE NATURE OF PRESERVATION PROJECTS, THE EXTENT OF WORK CANNOT ALWAYS BE ACCURATELY DETERMINED PRIOR TO COMMENCEMENT OF WORK. REPAIR LOCATIONS AND ESTIMATES OF QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER SHALL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIR.

EXISTING DIMENSIONS AND BRIDGE CONDITION ARE FROM THE BEST INFORMATION AVAILABLE. THE CONTRACTOR SHALL FIELD VERIFY THE INFORMATION SHOWN ON THE PLANS AND NOTIFY THE ENGINEER IF ACTUAL DIMENSIONS AND CONDITIONS DIFFER.

THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN WHAT IS SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO FOLLOW ALL STATE AND FEDERAL SAFETY REQUIREMENTS.

WORK ON THE BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL BELOW, EXCEPT WHERE THE CONTRACTOR'S PLAN USED PLATFORMS, NETS, SCREEN OR OTHER PROTECTIVE DEVICES TO CATCH THE MATERIAL. THE CONTRACTOR SHALL SUBMIT PLANS FOR CONSTRUCTION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS AND THE PROJECT SPECIAL PROVISIONS. ANY DAMAGE TO EXISTING REINFORCING STEEL DURING CONTRACTOR'S OPERATIONS SHALL BE REPAIRED AS DIRECTED BY THE ENGINEER AND PERFORMED AT NO ADDITIONAL COST TO THE DEPARTMENT.

FOR CONTROL OF TRAFFIC AND LIMITS OF PHASING OF CONSTRUCTION, SEE CONTRACT DOCUMENTS.

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL SUBMIT FOR REVIEW AND APPROVAL A COMPLETE SEQUENCE OF TASKS FOR EACH OPERATION AFFECTING

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

ALL PAVEMENT MARKING WILL BE IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

EXISTING JOINTS AND DECK DRAINS SHALL BE SEALED PRIOR TO BEGINNING SURFACE PREPARATIONS OF THE BRIDGE DECK. THE CONTRACTOR SHALL TAKE CARE THAT ANY CONSTRUCTION DEBRIS THAT COLLECTS IN THE DRAINS IS CONTAINED. DRAINS IN SHOULDERS OF ADJACENT TRAVEL LANES SHALL BE KEPT FREE AND CLEAR OF DEBRIS.

LONGITUDINAL CONSTRUCTION JOINTS OF OVERLAYS SHALL BE LOCATED ALONG THE CENTERLINE OR EDGE OF TRAVEL LANES.

FOR CLASS IB SURFACE PREPARATION, SEE BRIDGE DECK ASPHALT OVERLAY SPECIAL PROVISION.

FOR ASPHALT PLUG JOINTS FOR PRESERVATION, SEE SPECIAL PROVISIONS.

FOR PILE ENCAPSULATION, SEE SPECIAL PROVISIONS.

FOR BRIDGE DECK WATERPROOFING MEMBRANE-SPRAY APPLIED, SEE SPECIAL PROVISIONS.

> **HI-0018** PROJECT NO. _ **COLUMBUS** COUNTY

BRIDGE NO._

230388


SHEET 2 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

GENERAL DRAWING

FOR BRIDGE ON US 74 - US 76 BYP EBL OVER FRIAR SWAMP






- 4" ∅ PVC DRAIN

SEE CONTRACT DOCUMENTS FOR LANE WIDTHS, SEQUENCING AND OTHER TRAFFIC CONTROL MEASURES FOR STAGING OF OVERLAY SURFACE PREPARATION AND ASPHALT OVERLAY.

FOR BRIDGE DECK WATERPROOFING MEMBRANE-SPRAY APPLIED, SEE SPECIAL PROVISIONS.



PAY LIMITS FOR OVERLAY BID ITEMS

PROJECT NO. HI-0018 COLUMBUS _ COUNTY

230388 BRIDGE NO.___


> STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

TYPICAL SECTION AND **SURFACE PREPARATION** DETATIC

.D _{No}	OCUMENT NOT CONSIDERED
1	FINAL UNLESS ALL SIGNATURES COMPLETED
2	SIGNATURES COMPLETED

	L)E	IATL	.5	
	REVI	SIO	NS		SHEET NO
BY:	DATE:	NO.	BY:	DATE:	S10-03
		3			TOTAL SHEETS
		4			79

R.L.PUTEK J.A.YANNACCONE _ DATE : 08/2024 _ DATE : 08/2024 DRAWN BY : CHECKED BY :



PLAN

NOTES

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE REPAIR QUANTITY TABLE.

FOR CLASS IB SURFACE PREPARATION, SEE BRIDGE DECK ASPHALT OVERLAY SPECIAL PROVISION.

FOR ASPHALT OVERLAY, SEE ROADWAY PLANS.

AS-BUILT QUANTITY REPAIR TABLE

DECK SURFACE REPAIR & APPROACH SLAB REPAIR

		ESTIMATE	ACTUAL
	APPROACH SLAB @ END BENT 1	40.0 SQ. YDS.	
CLASS IB	SPAN A	144.3 SQ. YDS.	
SURFACE	SPAN B	140.0 SQ. YDS.	
PREPARATION			
	APPROACH SLAB @ END BENT 1	6.0 SQ. YDS.	
BRIDGE DECK	SPAN A	144.3 SQ. YDS.	
WATERPROOFING MEMBRANE-SPRAY	SPAN B	140.0 SQ. YDS.	
APPLIED			

CLASS IB SURFACE PREPARATION

HI-0018 PROJECT NO._

COLUMBUS

COUNTY 230388 BRIDGE NO._

SHEET 1 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

DECK REPAIRS

SPAN A W/APPROACH SLAB & SPAN B




DOCUMENT	NOT	CON	STDFRFD
FINAL			
SIGNATUR			
STGNATO	\L3	COM	LLILU

						_	
			REVI	10I2	NS		SHEET NO.
	NO.	BY:	DATE:	NO.	BY:	DATE:	S10-04
S ALL MPLETED	1			3			TOTAL SHEETS
1411 22128	2			4			79

R.L.PUTEK J.A.YANNACCONE _ DATE : 08/2024 _ DATE : 08/2024 DRAWN BY : CHECKED BY :

FOR SECTION A-A AND B-B. SEE "ASPHALT PLUG JOINT DETAILS" SHEET.

FOR BRIDGE DECK WATERPROOFING MEMBRANE-SPRAY APPLIED, SEE SPECIAL PROVISIONS.



AS-BUILT QUANTITY REPAIR TABLE

DECK SURFACE REPAIR & APPROACH SLAB REPAIR

		ESTIMATE	ACTUAL
CLASS IB			
SURFACE	SPAN C	140.0 SQ. YDS.	
PREPARATION	SPAN D	144.3 SQ. YDS.	
	APPROACH SLAB @ END BENT 2	40.0 SQ. YDS.	
BRIDGE DECK			
WATERPROOFING MEMBRANE-SPRAY	SPAN C	140.0 SQ. YDS.	
APPLIED	SPAN D	144.3 SQ. YDS.	
	APPROACH SLAB @ END BENT 2	6.0 SQ. YDS.	

CLASS IB SURFACE PREPARATION

NOTES

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE

FOR SECTION A-A AND B-B. SEE "ASPHALT PLUG JOINT DETAILS" SHEET.

FOR CLASS IB SURFACE PREPARATION, SEE BRIDGE DECK ASPHALT OVERLAY SPECIAL PROVISION.

FOR BRIDGE DECK WATERPROOFING MEMBRANE-SPRAY APPLIED, SEE SPECIAL PROVISIONS.

HI-0018 PROJECT NO._

COLUMBUS

COUNTY 230388 BRIDGE NO._

SHEET 2 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

DECK REPAIRS

SPAN C & SPAN D W/APPROACH SLAB




SEAL 032492


							_
			REVI	SIO	VS		SHEET 1
SIDERED	NO.	BY:	DATE:	NO.	BY:	DATE:	S10-0
ALL LETED	1			3			TOTAL SHEETS
			1	10		1	II

R.L.PUTEK J.A.YANNACCONE _ DATE : 08/2024 _ DATE : 08/2024 DRAWN BY : CHECKED BY :

NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF REPAIR QUANTITY TABLE.

FOR ASPHALT OVERLAY, SEE ROADWAY PLANS.





PLAN

APPLY MARINE EPOXY

ADHESIVE TO SEAMS

DETAIL C

(TOP OF JACKET)

FACE OF -

PILE

EXIST. CONC.

AS-BUILT SUMMARY OF QUANTITIES

		CONC	CRETE	PILE	ENCA	PSULA	TION	LOCA	TION	TABL	E	
	FIBERO	GLASS	REINFO	RCED I	PLASTIC	(FRP)	JACKET	LENGT	HS (LI	N.FT.)	ESTIMATE	ACTUAL
LOCATION	P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	LIN. FT.	LIN. FT.
BENT 1	5.5	4.8	4.1	3.4	2.7	5.5	4.8	4.1	3.4	2.7	41.0	
BENT 2	5.9	5.6	5.3	5.0	4.7	5.9	5.6	5.3	5.0	4.7	53.0	
BENT 3	3.1	3.1	3.1	3.1	3.1	3.1	3.1	3.1	3.1	3.1	31.0	
TOTAL											125.0	

PILE ENCAPSULATION EXTENDS FROM 1'-0" BELOW BOTTOM OF BENT CAP TO 1'-0" BELOW MUD LINE.


QUANTITIES ARE BASED ON BEST AVAILABLE INFORMATION. CONTRACTOR SHALL VERIFY MUD LINE ELEVATION PRIOR TO INSTALLATION OF JACKETS.

NOTE:

THE FLOATING TURBIDITY CURTAIN QUANTITY SHOWN ON THE TOTAL BILL OF MATERIAL IS BASED ON A 1.5' WATER DEPTH AND THE LENGTH NECESSARY TO FULLY ENCOMPASS ONE INTERIOR BENT.

FOR FLOATING TURBIDITY CURTAIN, SEE SPECIAL PROVISIONS.

CONTRACTOR SHALL MAKE ALL REASONABLE EFFORTS TO LIMIT CONTAMINATION OF THE WATER DURING EXCAVATION FOR THE PILE ENCAPSULATION, PUMPING OF EPOXY GROUT AND ALL OTHER WORK TO INSTALL THE PILE **ENCAPSULATION.**



DETAIL D

HEX NUT

1" PVC PLUG

- FRP JACKET

- 1" PVC PLUG SUPPLIED BY

CONTRACTOR USED TO SEAL

PORT AFTER GROUT INJECTION

- POLYMER

HEX NUT

REPAIR SEQUENCE

- INSTALL FLOATING TURBIDITY CURTAIN TO ENCOMPASS ENTIRE INTERIOR BENT. ALLOW ENOUGH SPACE FOR PILE ENCAPSULATION WORK.
- AFTER SURFACE PREPARATION, PLACE JACKET IN PROPER LOCATION AROUND PILE AND SEAL LONGITUDINAL SEAMS (SEE DETAIL A). INSTALL TEMPORARY BRACING.
- CONFIRM SPACING BETWEEN JACKET AND PILE. INSTALL BOTTOM SEAL (SEE DETAIL D). ALLOW BOTTOM SEAL TO CURE APPROX. 4 HOURS.
- ATTACH GROUT HOSE TO LOWERMOST INJECTION PORT AND PUMP EPOXY GROUT FOR 30-SEC. CHECK FOR LEAKS ALONG SEAM AND BOTTOM SEAL. (OPTIONALLY ALLOW THIS GROUT TO CURE AND PROCEED WITH GROUT INJECTION FROM 2ND PORT.)
- PLUG UPPER INJECTION PORTS AND PUMP GROUT INTO LOWER PORT UNTIL GROUT REACHES TOP OF JACKET. ONLY USE UPPER PORTS IF INJECTION BECOME DIFFICULT.
- REPEAT STEPS 2 THRU 5 FOR EACH PILE WITHIN ONE BENT.
- WHEN PILE ENCAPSULATION WORK AT THE BENT IS COMPLETE, REMOVE FLOATING TURBIDITY CURTAIN AND REINSTALL THE CURTAIN FOR THE PILE ENCAPSULATION WORK AT THE NEXT INTERIOR BENT.


HI-0018 PROJECT NO. **COLUMBUS**

COUNTY 230388 BRIDGE NO.

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

SUBSTRUCTURE REPAIR

CONCRETE PILE ENCAPSULATION



INJECTION PORT -

MOLDED POLYMER

INJECTION PORT

INSIDE THREAD -

BODY

1" N.P.T.

ADHÉRED IN FIELD

USING HOT MELT GLUE

FIXED ½" POLYMER

STAND-OFF

FRP JACKET

DETAIL E

One Glenwood Avenue OCUMENT NOT CONSIDEREI FINAL UNLESS ALL Raleigh, NC 27603 SIGNATURES COMPLETED 919-420-7660 NC Lic. No. F-0270

SESSION A

SEAL 032492

YANNA!

Signed by ONEER

SHEET NO REVISIONS S10-07 DATE: BY: DATE: BY: TOTAL SHEETS 79

DATE : 08/2024 R.L,PUTEK DRAWN BY : _ DATE . 08/2024 J.A.YANNACCONE CHECKED BY:

ADJUSTABLE STAND-OFF DETAIL

FRP JACKET

VARIES

FACE OF

PILE

STAND-OFF

EXIST. CONC

THREADED POLYMER

(VARIABLE LENGTH)

+

DETAIL A

(SEAM DETAIL)

THREADED

ADHERE POLYMER

IN FIELD USING HOT

MELT GLUE

STAND-OFF TO JACKET

POLYMER BOSS