Docusign Envelope ID: 3EA26309-CF25-4CE5-9520-17F74298C2DE

TIP NO.	SHEET NO.
U-5536	SIGN-2

APPROVED: DocuSigned by: Adam M. Conrad — 0DDC0FFA0FD94AD...

DATE: 12/19/2024

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 043767 ENGINEER ADAM M. CONRAD

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

CDM Smith
CDM Smith Inc.
5400 Glenwood Avenue
Suite 400
Raleigh, NC 27612-3228
NC COA No. F-1255

401

QUANTITY REQUIRED 16



R1–2
36″ X 36″ X 36″

ONE "U POST" PER SIGN

402

QUANTITY REQUIRED 30

R1–6
12″ X 36″

ONE "U POST" PER 2 SIGNS

403

QUANTITY REQUIRED 16

R6–1
36″ X 12″

TWO "U POSTS" PER SIGN
MOUNTED ABOVE SIGN 406
IN 1 INSTALLATION

404

QUANTITY REQUIRED 14



W2–6
30″ X 30″

ONE "U POST" PER SIGN

405

QUANTITY REQUIRED 10

R2–1
24″ X 30″

ONE "U POST" PER SIGN

406

QUANTITY REQUIRED 19

R1–1
30″ X 30″

ONE "U POST" PER SIGN

407

QUANTITY REQUIRED 14

W13–1P
18″ X 18″

MOUNTED UNDER SIGN #404
IN 14 INSTALLATIONS

408

QUANTITY REQUIRED 52

YELLOW/GREEN REFLECTIVE SHEETING

W11–2
36″ X 36″

ONE "U POST" PER SIGN

409

QUANTITY REQUIRED 52

YELLOW/GREEN REFLECTIVE SHEETING

W16–7PL
24″ X 12″

MOUNTED UNDER SIGN #408
IN 52 INSTALLATIONS

410

QUANTITY REQUIRED 2

R2–1
24″ X 30″

ONE "U POST" PER SIGN

412

QUANTITY REQUIRED 3



W14–1
30′′ X 30′′

ONE "U POST" PER SIGN

413

QUANTITY REQUIRED 12

R3–17
24″ X 18″

ONE "U POST" PER SIGN

414

QUANTITY REQUIRED 6

R3–17A
24″ X 8″

MOUNTED UNDER SIGN #413
IN 6 INSTALLATIONS

415

QUANTITY REQUIRED 6

R3–17B
24″ X 8″

MOUNTED UNDER SIGN #413
IN 6 INSTALLATIONS

416

QUANTITY REQUIRED 4

R7–8–NC
12″ X 26″

ONE "U POST" PER SIGN

417

QUANTITY REQUIRED 1



M6–1
21′′ X 15′′

MOUNTED UNDER "BEGIN" RELOCATED SIGN
IN 1 INSTALLATION
STA. 12+14 –Y8–

418

QUANTITY REQUIRED 1

M6–6L
21′′ X 15′′

MOUNTED UNDER "BIKE ROUTE" RELOCATED
SIGN IN 1 INSTALLATION
STA. 13+75 –Y8–

419

QUANTITY REQUIRED 1



W2–2
48′′ X 48′′

ONE "U POST" PER SIGN

TYPE "E" SIGNS

10/29/2024
pw:\\cdmsmith-az02-pw.bentley.com:pw_pll\Documents\117240\231192\10 Transportation\04 Client Folder Structure\U5536\Traffic\Signing\CADD\U5536_TMP_SGN_02.dgn
User:CONRADAM