

Docusign Envelope ID: B8A1838B-5CF1-423C-BE8C-1D6E4E369D53

METAL	POLE	No.	1	and	
			•	ana	-

MAST ARM LOADING SCHEDULE							
loading symbol	DESCRIPTION	AREA	SIZE	WEIGHT			
0000	RIGID MOUNTED SIGNAL HEAD 12″-4 SECTION-WITH BACKPLATE	11.5 S.F.	25.5″W X 66.0″L	74 LBS			
	RIGID MOUNTED SIGNAL HEAD 12″-3 SECTION-WITH BACKPLATE	9.3 S.F.	25.5″W X 52.5″L	60 LBS			
Street Name	STREET NAME SIGN RIGID MOUNTED	16.0 S.F.	24.0″W X 96.0″L	36 LBS			
2	SIGN RIGID MOUNTED	7.5 S.F.	30.0″W X 36.0″L	14 LBS			

PROJECT REFERENCE NO.

R-5930B

SHEET NO.

Sig. 2.3

NOTES

DESIGN REFERENCE MATERIAL

1. Design the traffic signal structure and foundation in accordance with: • The 6th Edition 2013 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions. • The 2018 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions. • The 2018 NCDOT Roadway Standard Drawings. • The traffic signal project plans and special provisions. • The NCDOT "Metal Pole Standards" located at the following NCDOT website: https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx 2. Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation. 3. Design all signal supports using force ratios that do not exceed 0.9. 4. A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design 5. Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts. 6. The mast arm attachment height (H1) shown is based on the following design assumptions: a. Nominal vertical rise in mast arm is 5 feet as measured from the centerline of the arm base to the centerline of the free end of the arm. b. Signal heads are rigidly mounted and vertically centered on the mast arm. c. The roadway clearance height for design is as shown in the elevation views. d. The top of the pole base plate is 0.75 feet above the ground elevation. e. Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway. f. Provide horizontal distance from the proposed centerline of the foundation to the edge of travelway. Refer to the Elevation Data Chart for elevation difference between the proposed foundation ground level and the edge of travelway. This information is necessary to ensure that the roadway clearance is maintained at the edge of the travelway and to aid in the camber design of the arm. 7. The pole manufacturer will determine the total height (H2) of each pole using the greater of • Mast arm attachment height (H1) plus 2 feet, or • H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot. 8. If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000. 9. The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway. 10. The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed. Allmetalpoles and arms should be agate gray in color as specified in the LANS PREPARED IN THE OFFICE OF: project special provisions. Kimley **»Horn** NC License #F-0102 421 Fayetteville Street, Suite 600 Raleigh, NC 27601 (919) 677-2000 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED NCDOT Wind Zone 5 (110 mph) Prepared for the Offices of: SEAL SR 2700 (Chatham Park Way) CARN at US 64 EB Ramps SEAL 044434 Pittsboro Division 8 Chatham County PLAN DATE: April 2024 REVIEWED BY: KP Baumann 50 N.Greenfield Pkwy,Garner,NC 27529 PREPARED BY: SP Pennington REVIEWED BY: REVISIONS SCALE INIT. DATE Ken Barrow 0 N/A 12/12/2024 -5DC709A86BCB447... SIGNATURE DATE N / A SIG. INVENTORY NO. 08-05/9