

+

TOTAL BILL OF MATERIAL																	
BRIDGE NO.	INCIDENTAL MILLING	ASPHALT CONCRETE SURFACE COURSE TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	GROOVING BRIDGE FLOORS	CONCRETE BARRIER RAIL	EPOXY COATED REINFORCING STEEL	CLASS II SURFACE PREPARATION	CLASS III SURFACE PREPARATION	LATEX MODIFIED CONCRETE OVERLAY	LATEX MODIFIED CONCRETE OVERLAY -VERY EARLY STRENGTH	PLACING & FINISHING OF LATEX MODIFIED CONCRETE OVERLAY	PLACING & FINISHING OF LATEX MODIFIED CONCRETE OVERLAY -VERY EARLY STRENGTH	CONCRETE REPAIRS	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	FIELD MEASURING	CLEANING AND REPAINTING OF BRIDGE #
	SQ. YDS	TONS	TONS	SQ. FT.	LIN. FT.	LBS.	SQ. YDS.	SQ. YDS.	CU. YDS.	CU. YDS.	SQ. YDS.	SQ. YDS.	CU. FT.	CU. FT.	LIN. FT.	LUMP SUM	LUMP SUM
040019	163	14	1	4,732	12.0	1,521	0.2	21.8	50.5	-	569.7	-	16.8	31.0	1.5	-	-
040032	334	28	2	9,762	21.4	1,104	39.2	-	103.4	-	1,154.7	-	36.6	68.6	5.0	-	-
040478	544	75	5	6,404	-	-	-	-	-	54.0	-	785.2	23.5	170.3	6.0	LUMP SUM	LUMP SUM
040507	220	28	2	5,180	-	-	-	-	-	38.9	-	634.0	0.5	90.3	-	LUMP SUM	LUMP SUM
TOTAL	1,261	145	10	26,078	33.4	2,625	39.4	21.8	153.9	92.9	1,724.4	1,419.2	77.4	360.2	12.5	LUMP SUM	LUMP SUM


TOTAL BILL OF MATERIAL																			
BRIDGE NO.	PAINTING CONTAINMENT FOR BRIDGE #__	POLLUTION CONTROL	VOLUMETRIC MIXER	POURABLE SILICONE JOINT SEALANT	VERY HIGH PERFORMANCE CONCRETE	ELASTOMERIC CONCRETE FOR PRESERVATION	REPAIRS TO PRESTRESSED CONCRETE GIRDERS FOR BRIDGE #040019	REPAIRS TO PRESTRESSED CONCRETE GIRDERS FOR BRIDGE #040032	BEAM REPAIR CUT-OUT	BRIDGE JOINT DEMOLITION	EPOXY COATING CONCRETE GIRDER ENDS	FRP STRENGTHENING SYSTEM	EPOXY COATING	HYDRO-DEMOLITION OF BRIDGE DECK	SCARIFYING BRIDGE DECK	CLEANING AND PAINTING EXISTING BEARINGS WITH HIGH RATIO CALCIUM SULFONATE	ELASTOMERIC BEARING, MODIFIED	TYPE I BRIDGE JACKING BRIDGE NO. __	TYPE II BRIDGE JACKING BRIDGE NO. __
	LUMP SUM	LUMP SUM	LUMP SUM	LIN. FT.	CU. FT.	CU. FT.	CU. FT.	CU. FT.	LBS.	SQ. FT.	SQ. FT.	SQ. FT.	SQ. FT.	SQ. YDS.	SQ. YDS.	EA.	EA.	EA.	EA.
040019	-	-	LUMP SUM	109.5	-	26.1	21.3	-	-	103.8	346	-	100	569.7	569.7	-	-	3	2
040032	-	-	LUMP SUM	210.0	169.4	51.0	-	162.3	-	209.6	-	1,956	196	1,154.7	1,154.7	-	-	-	6
040478	LUMP SUM	LUMP SUM	LUMP SUM	150.0	-	35.0	-	-	7,155	139.0	-	-	340	785.2	785.2	8	40	40	-
040507	LUMP SUM	LUMP SUM	LUMP SUM	81.0	-	18.6	-	-	3,195	74.4	-	-	183	634.0	634.0	8	24	24	-
TOTAL	LUMP SUM	LUMP SUM	LUMP SUM	550.5	169.4	130.7	21.3	162.3	10,350	526.8	346	1,956	819	3,143.6	3,143.6	16	64	67	8

NOTE:

AT THE TIME OF PREPARATION OF THESE PLANS, IT WAS NOT ANTICIPATED THAT THE ITEM(S) LISTED BELOW WOULD BE REQUIRED. HOWEVER, IT MAY BE DETERMINED IN THE FIELD THAT THE FOLLOWING ITEM(S) LISTED, OR OTHER WORK WILL BE NECESSARY TO PROPERLY COMPLETE THE INTENDED BRIDGE PRESERVATION/REHABILITATION WORK. THE CONTRACTOR SHALL BE PREPARED TO PERFORM SUCH WORK IN A TIMELY MANNER, AS DETERMINED IN THE FIELD. SUCH WORK SHALL BE CONSIDERED EXTRA WORK AND SHALL BE ADDRESSED AS PER ARTICLE 104-7 OF THE STANDARD SPECIFICATIONS. PROJECT SPECIAL PROVISIONS THAT OUTLINE REQUIREMENTS FOR THESE POTENTIAL ADDITIONAL WORK ITEMS HAVE BEEN PROVIDED IN THE PROJECT DOCUMENTS, BUT NO QUANTITIES HAVE BEEN LISTED. ACTUAL PAY ITEMS, QUANTITIES, AND COSTS WILL BE ESTABLISHED, AS REQUIRED, IF EXTRA WORK IS ENCOUNTERED.

UNANTICIPATED ITEMS:
SPlicing OF PRESTRESSING STRAND

PROJECT NO. 15BPR.133
ASHE COUNTY
BRIDGE NO. 040019, 040032
040478, 040507



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH									
TOTAL BILL OF MATERIAL									
REVISIONS									SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:				S-1
1			3						TOTAL SHEETS
2			4						87

DRAWN BY :	J.HARRIS	DATE :	03/2022
CHECKED BY :	J. YANNACCONE	DATE :	03/2022



One Glenwood Avenue
Suite 900
Raleigh, NC 27603
919-420-7660
NC Lic.No.F-0270

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED