

- 1

INSTALL COAX CABLE
- 2

INSTALL ETHERNET CABLE
- 3

EXISTING ETHERNET (OR COAX) CABLE
- 4

INSTALL SMFO CABLE
- 5

EXISTING SMFO CABLE
- 6

INSTALL FIBER OPTIC DROP CABLE
- 7

INSTALL TRACER WIRE
- 8

TRENCH
- 9

INSTALL PVC CONDUIT
- 10

INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11

INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12

INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL
- 13

INSTALL OUTER-DUCT POLYETHYLENE CONDUIT
- 14

INSTALL POLYETHYLENE CONDUIT
- 15

DIRECTIONAL DRILL CONDUIT
- 16

BORE AND JACK CONDUIT
- 17

INSTALL CABLE(S) IN EXISTING CONDUIT
- 18

INSTALL CABLE(S) IN NEW CONDUIT
- 19

INSTALL CABLE(S) IN EXISTING RISER
- 20

INSTALL CABLE(S) IN NEW RISER
- 21

INSTALL CABLE(S) IN EXISTING CONDUIT STUB-OUTS
- 22

INSTALL NEW CONDUIT INTO EXISTING CABINET BASE
(USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 23

INSTALL NEW RISER INTO EXISTING CABINET BASE
(USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 24

INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET
- 25

INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET
- 26

INSTALL NEW ETHERNET EDGE SWITCH
- 27

INSTALL NEW FIBER OPTIC TRANSCEIVER
- 28

INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS
AND FUSION SPLICE CABLE IN CABINET
- 29

INSTALL UNDERGROUND SPLICE ENCLOSURE
- 30

INSTALL AERIAL SPLICE ENCLOSURE
- 31

MODIFY EXISTING INTERCONNECT CENTER /SPLICE ENCLOSURE
- 32

INSTALL POLE MOUNTED SPLICE CABINET
- 33

INSTALL BASE MOUNTED SPLICE CABINET

- 34

INSTALL CABINET FOUNDATION
- 35

INSTALL CCTV CAMERA POLE MOUNTED CABINET
- 36

INSTALL CCTV CAMERA ASSEMBLY
- 37

INSTALL CCTV CAMERA WOOD POLE
- 38

INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39

INSTALL JUNCTION BOX
- 40A

INSTALL OVERSIZED JUNCTION BOX
- 40B

INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 24" x 24")
- 41

REMOVE EXISTING JUNCTION BOX
- 42

INSTALL WOOD POLE
- 43

REMOVE EXISTING WOOD POLE
- 44

INSTALL AERIAL GUY ASSEMBLY
- 45

INSTALL STANDARD GUY ASSEMBLY
- 46

INSTALL SIDEWALK GUY ASSEMBLY
- 47

INSTALL MESSENGER CABLE
- 48A

REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE
- 48B

REMOVE EXISTING COMMUNICATIONS CABLE
- 49

BACK PULL EXISTING COMMUNICATIONS CABLE
- 50

INSTALL CELL MODEM AND ANTENNA
- 51

INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE
100 FEET OF CABLE
- 52A

INSTALL DELINEATOR MARKER
- 52B

INSTALL JUNCTION BOX MARKER
- 53A

STORE 20 FEET OF COMMUNICATIONS CABLE
- 53B

STORE 50 FEET OF EACH COMMUNICATIONS CABLE
- 54

LASH CABLE(S) TO EXISTING COMMUNICATIONS CABLE
- 55

LASH CABLE(S) TO EXISTING MESSENGER CABLE
- 56

LASH CABLE(S) TO NEW MESSENGER CABLE
- 57

MODIFY EXISTING ELECTRICAL SERVICE
- 58

INSTALL NEW ELECTRICAL SERVICE
- 59

INSTALL NEW EQUIPMENT CABINET DISCONNECT
- 60

BOND TRACER WIRE TO EQUIPMENT
GROUND BUS
DO NOT BOND TRACER WIRE TO
EQUIPMENT GROUND BUS
- 61

BOND RISER AND MESSENGER CABLE
TO POLE GROUND
- 62

BOND RISER TO POLE GROUND
- 63

BOND MESSENGER CABLE TO POLE GROUND
- 64

INSTALL HEAT SHRINK TUBING RETROFIT KIT
- 65

INSTALL MOLDABLE DUCT SEAL
- 66

SLACK SPAN
- 67