## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

# SIGNING PLAN HAYWOOD COUNTY

LOCATION: BRIDGE NO. 236 OVER SR 1513 ON I-40

### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE	
901.10	TYPE `A' SIGNS	

SIGN STRINGERS AND SUPPORT SPACING

SIGN MOUNTING DETAILS - FOR TYPE A AND TYPE B SIGNS

GROUND MOUNTED SIGN SUPPORTS ORIENTATION OF GROUND MOUNTED SIGNS

### SUMMARY OF QUANTITIES ITEM NO. ITEM DESCRIPTION QUANTITY UNIT SECT. DESC. NO. 4025000000-E CONTRACTOR FURNISHED, TYPE A SIGN S.F. C.Y. 4048000000-E REINFORCED CONCRETE SIGN FOUNDATION 4060000000-E SUPPORTS, BREAKAWAY STEEL BEAM 833 LB. EA. 4110000000-N SIGN ERECTION, TYPE A (GROUND MOUNTED)

### **GENERAL NOTES**

- SIGNS SHALL BE FURNISHED BY THE CONTRACTOR.
- IF REMOVAL OR RELOCATIONS OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- DO NOT BEGIN FABRICATION FOR TYPE A & B SIGNS MOUNTED ON STEEL SUPPORTS UNTIL 'S' DIMENSIONS HAVE BEEN FIELD VERIFIED.
- SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.
- SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION, SIGNING, OR PAVEMENT MARKING. SEE TRAFFIC MANAGEMENT PLANS.

DESCRIPTION

TITLE, GENERAL NOTES, SCHEDULE, AND SUMMARY OF QUANTITIES SHEET SIGN-01

TYPE 'A' AND 'B' GROUND MOUNTED SIGNS SIGN-02 SIGN-03

SIGN-04-06 SIGNING PLAN SHEETS

**INDEX** 

SHEET NO.

SIGN DESIGNS

PLAN PREPARED BY: DRMP, INC

BRITTANY GROOME, PE, PTOE, RSP1 PROJECT MANAGER TRAFFIC DESIGN ENGINEER DARREN WHITE



Brittany N Groom

<sub>DATE:</sub> 3/6/2025

