

PROJECT NO.	SHEET NO.
2025CPT.03.10.10821, ETC.	15

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE					0106000000-E	1220000000-E	1245000000-E	1297000000-E	1330000000-E	1491000000-E	1519000000-E	1520000000-E	1523000000-E	1524000000-E	1575000000-E	1705500000-E	1881000000-E	
								LENGTH	WIDTH	BEGIN MP	END MP	BORROW EXCAVATION	INCIDENTAL STONE BASE	SHOULDER RECONSTRUC TION	1.5" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	SURFACE COURSE, S9.5C	LEVELING COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT (MILL)	SINUSOIDAL MILLED RUMBLE STRIP (14") SHOULDER	SINUSOIDAL MILLED RUMBLE STRIP (18") CENTERLINE
																								LF	LF
2025CPT.03.10.10821	Sampson	1	NC-41 / TOMAHAWK HWY	FROM THE BLADEN COUNTY LINE TO SR 1155 (WARD RD) [MP 0.00 - MP 10.41]	1, 2	2	2WU	10.41	26	0	10.41	655	200	20.63	3,845	3,321	5,009			14,487	700	1,124	45	108,950	54,475
TOTAL FOR MAP NO. 1								10.41				655	200	20.63	3,845	3,321	5,009			14,487	700	1,124	45	108,950	54,475
2025CPT.03.10.10821	Sampson	2	NC-55 / HARNETT-DUNN HIGHWAY	FROM THE JOHNSTON COUNTY LINE TO THE HARNETT COUNTY LINE [MP 14.78 - MP 20.14]	3	2	2WU	5.36	25	14.78	20.14	1,272	138	10.44	1,322	1,075				6,851		423	391	55,108	27,554
TOTAL FOR MAP NO. 2								5.36				1,272	138	10.44	1,322	1,075				6,851		423	391	55,108	27,554
TOTAL FOR PROJ NO. 2025CPT.03.10.10821								15.77				1,927	338	31.07	5,167	4,396	5,009			21,338	700	1,547	436	164,058	82,029
2025CPT.03.10.20821	Sampson	3	SR-1007 / WILDCAT RD	FROM NC HWY 41 (TOMAHAWK HWY) TO SR 1105 (DR KERR RD) [MP 0.00 - MP 6.00]	4, 5	2	2WU	6	22	0	6	733	118	11.72	4,589	2,353	3,849	6,851	200			459	23		
TOTAL FOR MAP NO. 3								6				733	118	11.72	4,589	2,353	3,849	6,851	200			459	23		
TOTAL FOR PROJ NO. 2025CPT.03.10.20821								6				733	118	11.72	4,589	2,353	3,849	6,851	200			459	23		
GRAND TOTAL								21.77				2,660	456	42.79	9,756	6,749	8,858	6,851	200	21,338	700	2,006	459	164,058	82,029