

PROJECT NO.	SHEET NO.
2025CPT.03.10.10821, ETC.	17

THERMOPLASTIC AND PAINT QUANTITIES

												4413000000-E	4457000000-N	4688000000-E		4700000000-E	4709000000-E	4725000000-E				4895000000-N		4900000000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	6" X 90 M WHITE THERMO	6" X90 M YELLOW THERMO	12" X 90 M WHITE THERMO	THERMOPLASTIC PAVEMENT MARKING LINES (24" X 90 MILS)	THERMO STR ARROW (90 MIL)	THERMO RT ARROW (90 MIL)	THERMO LT ARROW (90 MIL)	THERMO STR & RT ARROW (90 MIL)	POLYCARBONATE H SHAPED MARKER (Y/Y)	POLYCARBONATE H SHAPED MARKER (C/R)	YELLOW & YELLOW MARKERS	
								MI	FT			SF	LS	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	
2025CPT.03.10.10821	Sampson	1	NC-41 / TOMAHAWK HWY	FROM THE BLADEN COUNTY LINE TO SR 1155 (WARD RD) [MP 0.00 - MP 10.41]	1, 2	2	2WU	10.41	26	0	10.41	1,168	*	108,980	79,683	60		3	3	6	2	707	27		
TOTAL FOR MAP NO. 1							10.41				1,168	108,980		79,683	60		3	3	6	2	707	27			
2025CPT.03.10.10821	Sampson	2	NC-55 / HARNETT-DUNN HIGHWAY	FROM THE JOHNSTON COUNTY LINE TO THE HARNETT COUNTY LINE [MP 14.78 - MP 20.14]	3	2	2WU	5.36	25	14.78	20.14	608		55,108	27,097		80					344			
TOTAL FOR MAP NO. 2							5.36					608		55,108	27,097		80					344			
TOTAL FOR PROJ NO. 2025CPT.03.10.10821							15.77					1,776	1.00	164,088	106,780	60	80	3	3	6	2	1,051	27		
														270,868				14				1,078			
2025CPT.03.10.20821	Sampson	3	SR-1007 / WILDCAT RD	FROM NC HWY 41 (TOMAHAWK HWY) TO SR 1105 (DR KERR RD) [MP 0.00 - MP 6.00]	4, 5	2	2WU	6	22	0	6	672	*	61,974	33,914									387	
TOTAL FOR MAP NO. 3							6				672	61,974		33,914										387	
TOTAL FOR PROJ NO. 2025CPT.03.10.20821							6				672	61,974		33,914										387	
													1.000	95,888											
GRAND TOTAL								21.77				2,448	1	226,062	140,694	60	80	3	3	6	2	1,051	27	387	
														366,756				14				1,078			