Docusign Envelope ID: 5A2F53F8-4B01-4185-9EBF-131A833EB70B

TIP NO.	SHEET NO.
R-5863	SIGN-2

APPROVED: DocuSigned by: F3F9B6A833CD405...

DATE: 7/22/2025 | 11:21:06 AM PDT

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

(401) QUANTITY REQ. 4

R2-1
24'' X 30''

ONE 'U' POST PER SIGN

(402) QUANTITY REQ. 1



W3-3
30'' X 30''

ONE 'U' POST PER SIGN

(403) QUANTITY REQ. 12

R1-1
30'' X 30''

ONE 'U' POST PER SIGN

(404) QUANTITY REQ. 1

R4-4
30" x 24"

ONE 'U' POST PER SIGN

(405) QUANTITY REQ. 1

W3-5
36'' X 36''

ONE 'U' POST PER SIGN

(406) QUANTITY REQ. 1



W3-5
36'' X 36''

ONE 'U' POST PER SIGN

(407) QUANTITY REQ. 2

R2-1
24'' X 30''

ONE 'U' POST PER SIGN

(408) QUANTITY REQ. 1

R7-1
12'' X 18''

MOUNT BEHIND SIGN 403
IN 1 INSTALLATIONS

(409) QUANTITY REQ. 1



W2-6
30'' X 30''

ONE 'U' POST PER SIGN

(410) QUANTITY REQ. 12

W11-2
24'' X 24''

ONE 'U' POST PER SIGN

(411) QUANTITY REQ. 4

R4-7
18'' X 24''

ONE 'U' POST PER SIGN

INSTALL R4-7 SIGN OF A MINIMUM OF 10 FT FROM THE NOSE OF THE ISLAND.

(412) QUANTITY REQ. 5

R1-2
36'' X 36'' X 36"

ONE 'U' POST PER SIGN

(413) QUANTITY REQ. 1

R2-1
24'' X 30''

ONE 'U' POST PER SIGN

(414) QUANTITY REQ. 1

R2-1
24'' X 30''

ONE 'U' POST PER SIGN

(415) QUANTITY REQ. 3

R1-3P
18'' X 6''

MOUNT BELOW SIGN 403
IN 3 INSTALLATIONS

(416) QUANTITY REQ. 6

R6-1
36'' X 12''



MOUNT BELOW SIGN 403
IN 2 INSTALLATIONS

(416) QUANTITY REQ. 12

W16-7p
24'' X 12''

MOUNT BELOW SIGN 410
IN 12 INSTALLATIONS

Johnson, Mirmiran, & Thompson Inc.
1318 Patton Ave Suite F,
Asheville, NC, 28806
License No: C-3097

TYPE "E" SIGNS

2/27/2025 11:56:47 AM
...\Signing\R-5863 SIGN_2.dgn
User:BT-adde