Docusign Envelope ID: 7738856D-558C-4856-AAB9-D288CA0062B6

TIP NO.	SHEET NO.
R-5600	SIGN-2

APPROVED: Michael T. Rzepka

DATE: 10/14/2025

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 15876 ENGINEER MICHAEL T. RZEPKA

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

HDR Engineering, Inc. of the Carolinas
555 Fayetteville St, Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

401 QUANTITY REQ'D 2

18 X 12
W16-1P

MOUNT BELOW SIGN 401
IN 2 INSTALLATIONS

406 QUANTITY REQ'D 3

36 X 36
R3-7

ONE "U" POST PER SIGN

411 QUANTITY REQ'D 20

42 X 30
R5-1a

ONE "U" POST PER SIGN

416 QUANTITY REQ'D 21

24 X 30
R4-7

ONE "U" POST PER SIGN

421 QUANTITY REQ'D 1

36 X 36
R3-4

ONE "U" POST

426 QUANTITY REQ'D 9

30 X 36
R2-1

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 2

30 X 30
W11-1

ONE "U" POST PER SIGN

407 QUANTITY REQ'D 1



36 X 36
W10-3

ONE "U" POST

412 QUANTITY REQ'D 1

36 X 36
W3-5

ONE "U" POST

417 QUANTITY REQ'D 22

18 X 18
OM1-3

MOUNT BELOW SIGN 416
IN 21 INSTALLATIONS

MOUNT BELOW SIGN 440
IN 1 INSTALLATION

422 QUANTITY REQ'D 2



30 X 30
W3-3

ONE "U" POST PER SIGN

427 QUANTITY REQ'D 3

36 X 36
W14-2

ONE "U" POST PER SIGN

431 QUANTITY REQ'D 1

36 X 36
W1-2R

ONE "U" POST

403 QUANTITY REQ'D 1



36 X 36
W10-3

ONE "U" POST

408 QUANTITY REQ'D 2

30 X 36
R2-1

ONE "U" POST PER SIGN

413 QUANTITY REQ'D 22

48 X 18
R6-1 (L)

TWO "U" POSTS PER SIGN

418 **QUANTITY REQ'D 3**

36 X 36
R1-5(L)

ONE "U" POST PER SIGN

423 QUANTITY REQ'D 1

18 X 18
W13-1P

MOUNT BELOW SIGN 422
IN 1 INSTALLATION

428 QUANTITY REQ'D 3

12 X 18
M1-8

ONE "U" POST PER SIGN

432 QUANTITY REQ'D 2

18 X 18
W13-1P

MOUNT BELOW SIGN 434
IN 1 INSTALLATION

MOUNT BELOW SIGN 431
IN 1 INSTALLATION

404 QUANTITY REQ'D 20

36 X 36
R1-1

ONE "U" POST PER SIGN

409 QUANTITY REQ'D 3

24 X 18
R3-17

ONE "U" POST PER SIGN

414 QUANTITY REQ'D 27

48 X 18
R6-1 (R)

MOUNT ABOVE SIGN 404
IN 11 INSTALLATIONS

TWO "U" POSTS PER SIGN

419 QUANTITY REQ'D **3**

36 X 36
R1-5(R)

ONE "U" POST PER SIGN

424 QUANTITY REQ'D 1



36 X 36
W4-3(R)

ONE "U" POST

429 QUANTITY REQ'D 1

12 X 9
M6-1P

MOUNT BELOW SIGN 428
IN 1 INSTALLATION

433 QUANTITY REQ'D 4

36 X 30
R4-4

ONE "U" POST PER SIGN

405 QUANTITY REQ'D 1

36 X 36
S4-5

YELLOW/GREEN REFLECTIVE SHEETING

ONE "U" POST PER SIGN

410 QUANTITY REQ'D 3

24 X 9
R3-17a

MOUNT BELOW SIGN 409
IN 2 INSTALLATIONS

MOUNT BELOW SIGN 435
IN 1 INSTALLATION

415 QUANTITY REQ'D 2

48 X 48 X 48
R1-2

TWO "U" POST PER SIGN

420 QUANTITY REQ'D 20

36 X 36
R5-1

ONE "U" POST PER SIGN

425 QUANTITY REQ'D 1

24 X 9
R3-17b

MOUNT BELOW SIGN 409
IN 1 INSTALLATION

430 QUANTITY REQ'D 3



36 X 36
W12-1

ONE "U" POST PER SIGN

434 QUANTITY REQ'D 1

36 X 36
W1-2L

ONE "U" POST

TYPE "E" SIGNS