Sig 7.2 I-5898

MAXTIME OVERLAP PROGRAMMING DETAIL FOR DEFAULT PHASING

Front Panel

Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface

Home >Controller >Overlap Configuration >Overlaps

Overlap Plan 1

Overlap	1	3	
Туре	FYA 4 - Section	FYA 4- Section	
Included Phases	2	2	
Modifier Phases	1	-	
Modifier Overlaps	<u>.</u>	-	
Trail Green	0	0	
Trail Yellow	0.0	0.0	
Trail Red	0.0	0.0	

MAXTIME STARTUP AND SOFTWARE FLASH PROGRAMMING DETAIL

Front Panel

Main Menu >Controller >Unit

Web Interface

Home >Controller >Unit

Modify parameters as shown below and save changes.

Start Up Parameters

Unit Flash Parameters

All Red Flash Exit Time

StartUp Clearance Hold

SPECIAL DETECTOR NOTE

Install a video detection system for vehicle detection.
Perform installation according to manufacturer's directions and
NCDOT engineer approved mounting locations to accomplish the
detection schemes shown on the Signal Design Plans.

OUTPUT CHANNEL CONFIGURATION

Front Panel

Main Menu >Controller >More>Channels>Channels Config

Web Interface

Home >Controller >Advanced IO>Channels>Channel Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channe		
1	Phase Vehicle	1		Х	Х	1		
2	Phase Vehicle	2		Х		2		
3	Phase Vehicle	3		Х	Х	3		
4	Phase Vehicle	4		Х		4		
5	Phase Vehicle	5		Х		5		
6	Phase Vehicle	6		Х	Х	6		
7	Phase Vehicle	7		Х		7		
8	Phase Vehicle	8		Х	Х	8		
9	Overlap	1		Х	Х	9		
10	Overlap	2		Х	Х	10		
11	Overlap	3		Х		11		
12	Overlap	4		Х		12		
13	Phase Ped	2				13		
14	Phase Ped	4				14		
15	Phase Ped	6				15		
16	Phase Ped	8				16		
17	Overlap	5		Χ	Х	17		
18	Overlap	6		Χ		18		

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: Ø7-1475 T1 DESIGNED: June 2025 SEALED: 6/30/2025 REVISED: N/A

<u> Signal Upgrade - Temp Design 1 (TMP Phase II)</u>

ELECTRICAL AND PROGRAMMING Prepared for the Offices of:

US 311/NC 135 US 220 Southbound Ramps

Rockingham County PLAN DATE: June 2025 REVIEWED BY: prepared by: Golam Moinuddin reviewed by: REVISIONS

034454 Golam Moinuddin

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared in the Offices of:

Johnson, Mirmiran, & Thompson Inc. 4700 Falls of Neuse Rd, Suite 100,

INIT. DATE