PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.12.02.10181,	8	
2026CPT.12.02.20181		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	1297000000-E 3" MILLING	1297000000-E 6" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E ASPHALT CONC BASE COURSE, TYPE B25.0C	1519000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1523000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2830000000-N ADJUSTMENT OF MANHOLES	2845000000-N ADJUSTMENT OF METER BOXES OR VALVE BOXES	2846000000-N ADJUSMENT OF OVERSIZED MANHOLES	5255000000-N PORTABLE LIGHTING	7324000000-N JUNCTION BOX (STANDARD SIZE)	7444000000-E INDUCTIVE LOOP	7456100000-E LEAD-IN CABLE (14-2)
								MI	FT			TON	SMI	TON	SY	SY	SY	SY	TON	TON	TON	TONS	TONS	EA	EA	EA	LS	EA	LF	LF
2026CPT.12.02.10181	Catawba	1	US-321 BUS	FROM LINCOLN CO TO SR 1855 (E MAIDEN RD)	1, 2	2	2WU	1.100	24-40	0.000	1.100	25	1.45	150	8,578			355			1,683	102	60	10	8			1.00	30	310
2026CPT.12.02.10181	Catawba	2	US-321 BUS	FROM SR 1855 (E MAIDEN RD) TO SR 2007 (W MAIDEN RD)	4, 8	2	2WU	1.100	28-38	1.100	2.200				12,160	10,205					1,972	120	80	34	10		*			
2026CPT.12.02.10181	Catawba	3	US-321 BUS	FROM SR 2007 (W MAIDEN RD) TO NC 10	1, 2	2	2WU	6.100	23	2.200	8.300	100	10.97	1,097	16,025			1,025			7,899	476	200	20	32					
TOTAL FOR PROJ NO. 2026CPT.12.02.10181								**8.300**				**125**	**12.42**	**1,247**	**36,763**	**10,205**		**1,380**			**11,554**	**698**	**340**	**64**	**50**		**1.00**	**1.00**	**30**	**310**
															46,968															
2026CPT.12.02.20181	Catawba	4	SR-1007/1692 1ST ST W	FROM SR 1476 (FAIRGROVE CH RD) TO NC 16 BUS	2. 6, 7	2	2WU	3.040	24-60	0.000	3.040				90,900						8,022	478	100	32	32				2,750	100
2026CPT.12.02.20181	Catawba	5	SR-2231 OI / 2ND AV SE	FROM SR 1692 (1ST AVE SW) TO NC 127	2, 5	2	2WU	1.970	30	0.000	1.970				30,005		4,667		1,117		3,207	240		90	54	8			48	50
2026CPT.12.02.20181	Catawba	6	SR-3004 / TURTLE DOVE RD	FROM SR 1453 (SPRINGS RD) TO DEAD END	3	2	2WU	0.600	20	0.000	0.600									408		29	60							
2026CPT.12.02.20181	Catawba	7	SR-2251 / PUETT PARK DR	FROM SR 1544 (ADAMS ST) TO DEAD END	3	2	2WU	0.250	18	0.000	0.250									192		16	80							
2026CPT.12.02.20181	Catawba	8	SR-2250 / BARBARA DR	FROM SR 1544 (ADAMS ST) TO SR 2251 (PUETT PARK DR)	3	2	2WU	0.110	18	0.000	0.110									84		6	20							
2026CPT.12.02.20181	Catawba	9	SR-2252 / TERRY ST	FROM SR 2250 (BARBARA DR) TO CUL-DE-SAC	3	2	2WU	0.200	18	0.000	0.200									161		11	20							
2026CPT.12.02.20181	Catawba	10	SR-1641 / CORAL WAY	FROM SR 1544 (ADAMS ST) TO DEAD END	3	2	2WU	0.150	20	0.000	0.150									128		10	40							
TOTAL FOR PROJ NO. 2026CPT.12.02.20181								**6.320**							**120,905**		**4,667**		**1,117**	**973**	**11,229**	**790**	**320**	**122**	**86**	**8**			**2,798**	**150**
															125,572															
GRAND TOTAL								**14.620**				**125**	**12.42**	**1,247**	**157,668**	**10,205**	**4,667**	**1,380**	**1,117**	**973**	**22,783**	**1,488**	**660**	**186**	**136**	**8**	**1.00**	**1.00**	**2,828**	**460**
															172,540															