

5/28/99

5-N04-2025-1309
p17/ncgrrnccdot-pw-01/Documents/Division_09/HI-0005/Roadway/Design/Hi-0005-D09-SUM
USER NAME: 88888

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES
SLAB REPAIR SUMMARY

SOUTHBOUND									NORTHBOUND								
TMP LOCATION NO.	MILE MARKER/ RAMP	LANE	X (LONGITUDE)	Y (LATITUDE)	WIDTH (FT)	LENGTH (FT)	AREA (SF)		TMP LOCATION NO.	MILE MARKER/ RAMP	LANE	X (LONGITUDE)	Y (LATITUDE)	WIDTH (FT)	LENGTH (FT)	AREA (SF)	
1	92.34	3	-80.24760363	35.87360194	12	6	72		3	92.50	1,2	-80.24487825	35.87377604	24	60	1440	
2	92.39	1,2	-80.24675506	35.87377631	24	20	480		8	94.46	2	-80.23249472	35.89488853	12	6	72	
4	92.60	1,2	-80.24335608	35.87447087	12	6	72		9	94.64	1,2	-80.23303546	35.89748089	24	20	480	
5	92.66	2	-80.24217053	35.87471776	12	6	72		11	95.35	2	-80.23454233	35.9077358	12	6	72	
6	93.62	1,2	-80.23064098	35.88290429	24	20	480		12	95.52	2	-80.23440571	35.91020921	12	20	240	
7	93.73	1,2	-80.23079827	35.88451913	24	20	480		13	96.23	2	-80.23250663	35.92035335	12	6	72	
10	94.84	2	-80.23410674	35.900362	12	6	72		14	96.62	1,2	-80.2314086	35.92591943	12	6	72	
17	96.65	2	-80.23184594	35.92621494	12	6	72		15	96.64	1,2	-80.23135077	35.92630926	24	40	960	
18	96.64	2	-80.23181046	35.92642907	12	12	144		16	96.76	1,2	-80.23118979	35.92799969	24	20	480	
22	EXIT 97 ON RAMP	1	-80.23571484	35.93816183	16	12	192		19	EXIT 97 OFF RAMP	1	-80.2337977	35.93864754	16	30	480	
23	97.68	1,2	-80.23509041	35.9408928	24	40	960		20	97.80	3	-80.23505119	35.9426563	12	6	72	
26	98.19	1,2	-80.23593317	35.94825066	24	40	960		21	97.88	3, OS	-80.23527223	35.94369522	12	20	240	
30	99.36	1,2	-80.23025688	35.96437655	24	100	2400		24	98.01	2	-80.23553761	35.94558639	12	80	960	
32	EXIT 100 ON RAMP	1	-80.23107346	35.97062552	16	20	320		25	98.35	OS	-80.23506667	35.95059409	12	12	144	
33	99.99	2	-80.23085786	35.97352847	12	40	480		27	98.55	1,2	-80.23415066	35.95331759	24	160	3840	
44	100.15	2	-80.23149285	35.9753341	12	6	72		28	98.64	1,2	-80.23347984	35.95482665	24	160	3840	
45	100.43	1,2	-80.23318828	35.97948097	24	20	480		29	98.69	2	-80.23329125	35.95527122	12	20	240	
46	100.65	2	-80.23463524	35.98259322	12	20	240		31	EXIT 100 ON RAMP	1	-80.22911798	35.96832856	16	20	320	
47	100.69	OS	-80.23490686	35.9831703	10	40	400		34	100.47	2	-80.23222131	35.98053068	12	6	72	
48	100.88	OS	-80.23612335	35.98583668	10	40	400		35	100.62	2	-80.23298955	35.98246081	12	6	72	
49	100.89	2, OS	-80.2362789	35.98609056	22	40	880		36	100.87	2	-80.23483071	35.98578256	12	6	72	
50	100.94	1,2	-80.236579	35.98677368	24	6	144		37	100.94	1,2	-80.23529354	35.98679738	24	20	480	
51	100.98	IS,1,2,OS	-80.23675396	35.9872114	38	100	3800		38	101.08	2	-80.2363203	35.98860938	12	6	72	
52	101.09	1	-80.23732489	35.9884931	12	20	240		39	101.36	2	-80.23775041	35.99254338	12	20	240	
52	101.10	1,2	-80.23738482	35.98861954	24	6	144		40	101.44	2	-80.23786297	35.99365619	24	20	480	
53	101.28	IS,1	-80.23824672	35.99116974	16	40	640		41	101.49	1,2	-80.23785465	35.99437732	24	6	144	
53	101.29	2	-80.2383059	35.9912792	12	6	72		42	101.56	2	-80.23776126	35.99555751	12	20	240	
54	101.36	1,2	-80.23850741	35.9923714	24	6	144		43	101.80	OS	-80.23733985	35.99877424	12	20	240	
55	101.45	1,2	-80.23866559	35.99385691	24	6	144		60	102.00	2	-80.23698776	36.00169883	12	60	720	
56	101.65	1,2	-80.23832269	35.99663136	24	40	960		61	102.02	2	-80.2369457	36.00194421	12	10	120	
57	101.67	2	-80.2382698	35.9969855	12	20	240		62	102.48	OS	-80.23603185	36.0085952	10	80	800	
57	101.68	1	-80.23822202	35.99706034	12	10	120		63	102.52	OS	-80.23591441	36.00920637	10	60	600	
58	101.70	2	-80.23818976	35.99735519	12	30	360		64	102.72	2	-80.23555087	36.01200536	12	10	120	
59	101.85	OS	-80.23775377	35.99958524	10	40	400		65	EXIT 103 OFF RAMP	1	-80.23520065	36.01264901	12	20	240	
67	101.96	OS	-80.23747365	36.00123767	10	140	1400		66	EXIT 103 OFF RAMP	1	-80.23459274	36.01447424	16	10	160	
68	102.02	OS	-80.23731411	36.00195378	12	6	72							TOTAL AREA=		18896	SF
69	102.04	OS	-80.23725883	36.00225596	10	80	800							TOTAL AREA=		2099.6	SY
70	102.13	OS	-80.23704186	36.00359817	10	300	3000							TOTAL AREA NB & SB=		4649.3	SY
71	102.32	2	-80.23661444	36.00633527	12	40	480								SAY=	4650	SY
72	102.88	OS	-80.23558954	36.01428687	10	6	60										
					TOTAL AREA=		22948	SF	CLASS IV SUBGRADE STABILIZATION CONTINGENCY FOR USE AT DISCRETION OF ENGINEER FOR SLAB REPAIRS:								
					TOTAL AREA=		2549.8	SY		SHALLOW UNDERCUT	CLASS IV SUB. STABIL.			GEOTEXTILE FOR SUB. STABIL.			
										780 CY	1570 TONS			2330 SY			