Docusign Envelope ID: B7758B81-8F28-4039-9827-A0AA3044BDC2

PROJECT REFERENCE NO.	SHEET NO.
U-6105	SIGN-2A

APPROVED: _____

DATE: _____

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 0326 Signed by: Jason D. Lewis Date: 8/12/2025 ENGINEERING JASON D. LEWIS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

(401) QUANTITY REQ'D _4_



R1-2
36" X 36" X 36"

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D _2_

R2-1
24" X 30"

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D _4_

R4-7
24" X 30"

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D _4_

R6-1
36" X 12"

ONE "U" POST PER SIGN

(405) QUANTITY REQ'D _6_

W2-6
30" X 30"

ONE "U" POST PER SIGN

(406) QUANTITY REQ'D _4_

W3-2
30" X 30"

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D _2_

W11-2
36" X 36"

SHEETING COLOR:
FLUORESCENT YELLOW-GREEN

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D _2_



W16-7PL
21" X 15"

SHEETING COLOR:
FLUORESCENT YELLOW-GREEN

MOUNTED BELOW SIGN 407
IN 2 INSTALLATIONS

(409) QUANTITY REQ'D _2_

R2-1
24" X 30"

ONE "U" POST PER SIGN

Kimley»Horn

TYPE "E" SIGNS

8/26/2025 K:\CHL_PRJ\011036528 - U-6105 (Bailey Rd Ext)\Traffic\Signing\CADD\Signing Layout Plans\U-6105_rdy_sgn_2Adgn