

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.09.09.10851	15	
2026CPT.09.10.20851		

THERMOPLASTIC AND PAINT QUANTITIES

												4413000000-E	4457000000-N	4685000000-E		4688000000-E		4700000000-E	4709000000-E	4720000000-E	4725000000-E		4810000000-E		4895000000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/GE NERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	12" X 90 M WHITE THERMO	THERMOPLAS TIC PAVEMENT MARKING LINES (24", 90 MILS)	THERMO RXR 90 M	THERMO LT ARROW 90 M	THERMO STR & RT ARROW 90 M	4" WHITE PAINT	4" YELLOW PAINT	POLYCARBONATE H-SHAPED MARKERS	
								MI	FT						SF	LS	LF	LF	LF	LF	LF	LF	EA	EA	EA	LF
2026CPT.09.09.10851	Stokes	1	NC-268	FROM SURRY COUNTY LINE TO NC66	1	2	2WU	7.96	21-23	0	7.96	900	*			84,892	84,892						84,892	84,892	610	
TOTAL FOR MAP NO. 1							7.96				900					84,892	84,892						84,892	84,892	610	
2026CPT.09.09.10851	Stokes	2	NC-268	FROM NC66 TO PROJ# BR-0102 LIMITS AT NC89	2	2	2WU	3.846	21-23	8.004	11.85	433				40,888	40,888								300	
TOTAL FOR MAP NO. 2							3.846				433					40,888	40,888								300	
TOTAL FOR PROJ NO. 2026CPT.09.09.10851							11.806				1,333					125,780	125,780						84,892	84,892	910	
																251,560							169,784			
2026CPT.09.10.20851	Stokes	3	SR-1236 / N OLD 52 RD	FROM SURRY COUNTY LINE TO START OF CURB NORTH OF MOORE RD/ MOUNTAI VIEW RD SR1122	4,5	2,4	2WU	9.96	22.5-49	0	9.96	1,110					105,708	109,600	30	213	10	15	6			
TOTAL FOR MAP NO. 3							9.96				1,110					105,708	109,600	30	213	10	15	6				
2026CPT.09.10.20851	Stokes	4	SR-1195 / OSBORNE JOYCE RD	FROM NC268 TO BROWN MOUNTAIN RD SR1210	3	2	2WU	2.44	20.5	0	2.44	275			25,648	25,648										
TOTAL FOR MAP NO. 4							2.44				275				25,648	25,648										
2026CPT.09.10.20851	Stokes	5	SR-1179 / GRASSY KNOB RD	FROM NC268 TO SURRY COUNTY LINE	3	2	2WU	0.74	21	0	0.74	15			7,534	7,534										
TOTAL FOR MAP NO. 5							0.74				15				7,534	7,534										
TOTAL FOR PROJ NO. 2026CPT.09.10.20851							13.14				1,400				33,182	33,182	105,708	109,600	30	213	10	15	6			
														66,364		215,308						21				
GRAND TOTAL							24.946				2,733				33,182	33,182	231,488	235,380	30	213	10	15	6	84,892	84,892	910
												1.00	66,364		466,868						21		169,784			

Note: All quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received