

SUMMARY OF QUANTITIES

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.05.12.10911.1 2026CPT.05.12.20911.1 2026CPT.05.12.20912.1	10	

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEG N	END MP	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	7444000000-E
												INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	1½" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	INDUCTIVE LOOP SAWCUT
								MI	FT			TONS	SMI	TON	SY	SY	TONS	TONS	TON	TONS	LF
2026CPT.05.12.10911.1	Vance	1	US-1 BUS	FROM US 1 TO PAVEMENT JOINT	2	2	2WU	4.437	24	0.000	4.437	184	7.36	680	58,589	5,444		5,539	332	100	450
TOTAL FOR PROJ NO. 2026CPT.05.12.10911.1								4.437				184	7.36	680	58,589	5,444		5,539	332	100	450
2026CPT.05.12.20911.1	Vance	2	SR-1513 / S COKESBURY RD	FROM TOWER RD TO SR 1510	1	2	2WU	0.628	18	1.007	1.635	26	1.02	95		1,504	481		32	25	
2026CPT.05.12.20911.1	Vance	3	SR-1515 / S COKESBURY RD	FROM TOWER RD TO SR 1533	1	2	2WU	2.172	18	0.000	2.172	98	3.94	364		896	1,665		111	50	
TOTAL FOR PROJ NO. 2026CPT.05.12.20911.1								2.800				124	4.96	459		2,400	2,146		143	75	
2026CPT.05.12.20912.1	Vance	4	SR-1100 / EGYPT MOUNTAIN RD	FROM US 1 TO SR 1101	1	2	2WU	4.485	20	0.000	4.485	212	8.47	783		1,678	3,819		249	11	
2026CPT.05.12.20912.1	Vance	5	SR-1107 / S LAKE LODGE RD EXT/S LAKE LODGE RD/BRIGGS RD/COMMUNITY HOUSE RD	FROM US 1 BUS TO SR 1110	1	2	2WU	5.106	20	0.000	5.106	236	9.44	873		3,220	4,347		284	20	
TOTAL FOR PROJ NO. 2026CPT.05.12.20912.1								9.591				448	17.91	1,656		4,898	8,166		533	31	
GRAND TOTAL								16.828				756	30.23	2,795	58,589	12,742	10,312	5,539	1,008	206	450