

8/17/99

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, Fine Grading, Clearing and Grubbing, and the Removal of Existing Pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L- LT04	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -L- LT04	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -L- MD_05	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -L- RT04	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -Y11- LT01	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -Y12- RT01	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
75+50.00	0	0	100+50.00	0	71	84+50.00	0	54	84+50.00	0	292	11+50.00	2	25	10+12.02	0	0
76+00.00	18	10	101+00.00	0	50	Station Uncl. Exc. Embt -L- MD_06 (cu. yd.) (cu. yd.)			85+00.00	0	274	11+75.00	3	20	10+50.00	0	46
76+50.00	20	15	101+50.00	0	37				85+50.00	0	257	12+00.00	3	20	10+75.00	2	61
77+00.00	15	33	102+00.00	0	31				86+00.00	0	235	12+25.00	4	22	11+00.00	5	59
77+50.00	4	60	102+35.00	0	10				86+50.00	0	251	12+50.00	5	23	11+25.00	11	49
78+00.00	4	83	102+50.00	0	0	93+50.00	0	0	87+00.00	0	263	12+75.00	5	26	11+50.00	17	30
78+50.00	3	92	103+00.00	0	3	94+00.00	2	23	87+50.00	0	214	13+00.00	5	29	11+75.00	9	24
79+00.00	1	89	103+50.00	0	24	94+50.00	2	34	88+00.00	0	153	13+25.00	5	30	12+00.00	5	22
79+25.00	1	42	104+00.00	0	41	95+00.00	2	46	88+50.00	0	100	13+50.00	5	32	12+25.00	8	14
79+50.00	1	39	104+50.00	0	39	95+50.00	1	63	89+00.00	0	84	13+75.00	5	29	12+50.00	6	12
79+75.00	0	45	105+00.00	0	47	96+00.00	0	75	89+50.00	3	82	14+00.00	4	23	12+75.00	6	9
80+00.00	0	68	105+50.00	0	45	96+50.00	0	79	90+00.00	12	47	14+25.00	4	24	13+00.00	5	7
80+50.00	1	139				97+00.00	0	78	90+50.00	12	37	14+50.00	10	32	13+25.00	5	8
81+00.00	1	94				97+50.00	0	65	91+00.00	5	51	14+75.00	17	44	13+50.00	7	7
81+50.00	2	65	Station Uncl. Exc. Embt -Y10- LT (cu. yd.) (cu. yd.)			98+00.00	0	46	91+50.00	3	54	15+00.00	21	54	13+75.00	7	5
81+75.00	3	32				92+00.00	8	45	15+25.00	14	54	14+00.00	8	4			
82+00.00	4	28	10+90.00	0	0	Station Uncl. Exc. Embt -L- MD_07A (cu. yd.) (cu. yd.)			92+50.00	13	44	15+50.00	3	55	14+25.00	10	3
82+50.00	6	26							93+00.00	9	45	15+75.00	0	61	14+50.00	12	2
83+00.00	4	52	11+00.00	1	0	103+00.00	0	0	93+50.00	9	38	16+00.00	0	64	14+75.00	10	2
83+50.00	1	93	11+25.00	16	1				94+00.00	8	46	16+25.00	0	43	14+95.13	2	1
84+00.00	0	107	11+50.00	30	1	103+50.00	1	52	94+50.00	7	62	16+50.00	0	21			
84+50.00	0	70	11+75.00	36	1	95+00.00	5	106	16+75.00	0	23						
85+00.00	0	73	12+00.00	38	1	104+00.00	2	48	95+50.00	5	184	Station Uncl. Exc. Embt -Y11- LT02 (cu. yd.) (cu. yd.)			16+75.00	0	0
85+50.00	0	104	12+25.00	40	0	104+50.00	1	44	96+00.00	4	216						
86+00.00	0	63	12+50.00	44	0	105+00.00	2	42	96+50.00	1	241	-Y12- LT01	(cu. yd.)	(cu. yd.)	17+00.00	0	24
86+50.00	0	63	12+75.00	50	0	105+50.00	2	43	97+00.00	0	282				17+25.00	0	50
87+00.00	0	100	13+00.00	25	0				97+50.00	0	263	10+12.02	0	0	17+50.00	0	74
87+50.00	0	105	13+60.16	0	0				98+00.00	0	272	10+50.00	0	281	17+75.00	0	71
88+00.00	0	104				Station Uncl. Exc. Embt -L- RT04 (cu. yd.) (cu. yd.)	99+00.00	0	258	10+75.00	0	72	18+00.00	0	69		
88+50.00	7	92														99+50.00	0
89+00.00	18	84	Station Uncl. Exc. Embt Y14 (cu. yd.) (cu. yd.)			100+00.00	0	275	11+25.00	0	71	18+50.00	0	79			
89+50.00	12	95				75+50.00	0	0	100+50.00	0	288	11+50.00	0	62	18+75.00	0	97
90+00.00	0	103	10+70.00	0	0	76+00.00	14	0	101+00.00	0	298	11+75.00	4	38	19+00.00	0	107
90+50.00	0	104	10+75.00	3	0	76+50.00	5	37	101+50.00	0	274	12+00.00	4	17	19+25.00	0	104
91+00.00	0	100	11+00.00	25	1	77+00.00	1	85	102+00.00	0	200	12+25.00	0	10	19+50.00	0	98
91+50.00	0	106	11+25.00	13	0	77+50.00	1	93	102+35.00	0	53	12+50.00	0	7	19+75.00	0	90
92+00.00	0	106	11+50.00	5	15	78+00.00	1	96	102+50.00	0	20	12+75.00	0	6	20+00.00	0	86
92+50.00	0	115	11+59.06	0	5	78+50.00	8	121	103+00.00	1	179	13+00.00	0	6	20+25.00	0	86
93+00.00	0	119				79+00.00	18	149	103+50.00	1	235	13+25.00	3	5	20+50.00	0	81
93+50.00	0	125				79+25.00	6	57	104+00.00	2	232	13+50.00	7	5	20+75.00	0	68
94+00.00	55	132	Station Uncl. Exc. Embt -L- MD_05 (cu. yd.) (cu. yd.)			79+50.00	5	76	104+50.00	1	242	14+00.00	9	3	21+00.00	0	58
94+50.00	103	150				79+75.00	5	82	105+00.00	2	257	14+25.00	10	2	21+25.00	0	55
95+00.00	97	171	80+00.00	0	0	80+50.00	21	272	Station Uncl. Exc. Embt -Y11- LT01 (cu. yd.) (cu. yd.)			14+50.00	12	1	21+50.00	0	54
95+50.00	61	229	81+00.00	1	31	81+00.00	34	227				14+75.00	14	1	21+75.00	0	52
96+00.00	12	195	81+50.00	2	38	81+50.00	48	186	14+95.13	6	1				22+00.00	0	46
96+50.00	0	138	81+75.00	1	20	81+75.00	16	68							22+25.00	0	42
97+00.00	0	150	82+00.00	1	21	82+00.00	14	91	22+50.00	0	45						
97+50.00	0	120	82+50.00	2	47	82+50.00	25	301	22+75.00	0	46						
98+00.00	0	103	83+00.00	1	55	83+00.00	1	286	23+00.00	0	49						
98+50.00	0	70	83+50.00	0	68	83+50.00	0	284	23+25.00	0	51						
99+00.00	0	50	84+00.00	0	69	84+00.00	0	308	23+50.00	1	45						

11/25/2025
U:\Roadway\CorridorModeling\U3609B_rdy-X-B-X-E_XSC_Summary.dgn
A13181