ADA SUMMARY OF QUANTITIES - HILLANDALE RD FROM SR 1320 TO I-85

Municipality:	**Durham**
WBS Number:	2026CPT.05.14.10321.1, etc.
County:	**Durham**

Sheet No.
39

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2738000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
18842**	1	SR-1320 (Erwin Rd)	SR-1321 (Fulton St)												1		Standard - 848.06
18843**	1	SR-1320 (Erwin Rd)	SR-1321 (Fulton St)												1		Standard - 848.06
18887**	1	SR-1320 (Erwin Rd)	SR-1321 (Fulton St)												1		Type 1A - 848.06
18888**	1	SR-1320 (Erwin Rd)	SR-1321 (Fulton St)												1		Standard - 848.06
18889	2	SR-1321 (Fulton St)	Elba St												1		Type 2B - 848.06
18890	2	SR-1321 (Fulton St)	Elba St												1		Type 2B - 848.06
18891	2	SR-1321 (Fulton St)	Elba St												1		Type 2B - 848.06
18892	2	SR-1321 (Fulton St)	Elba St												1		Type 2B - 848.06
18917	2	SR-1321 (Fulton St)	Elba St												1		Type 2B - 848.06
18919**	2	SR-1321 (Fulton St)	Elba St												1		Type 1C - 848.06
18913	3	SR-1321 (Fulton St)	Elder St			15					4					1	Remove Ramp
18914	3	SR-1321 (Fulton St)	Elder St			14					4					1	Remove Ramp
18915	3	SR-1321 (Fulton St)	Elder St												1		Type 2B - 848.06
18916	3	SR-1321 (Fulton St)	Elder St												1		Type 2B - 848.06
18910	4	SR-1321 (Fulton St)	Pratt St												1		Type 2B - 848.06
18911	4	SR-1321 (Fulton St)	Pratt St												1		Type 2B - 848.06
18912	4	SR-1321 (Fulton St)	Pratt St			20			14	4						1	Remove Ramp
18908	5	SR-1321 (Fulton St)	Duke North Pavillion (2400 Pratt St) Fulton St Service Entrance												1		Type 1A - 848.06
18909	5	SR-1321 (Fulton St)	Duke North Pavillion (2400 Pratt St) Fulton St Service Entrance												1		Type 2B - 848.06
18893	6	SR-1321 (Fulton St)	Shirley St												1		Type 2B - 848.06
18894	6	SR-1321 (Fulton St)	Shirley St												1		Type 2B - 848.06
18895	6	SR-1321 (Fulton St)	Shirley St			20			11							1	Remove Ramp
18896	6	SR-1321 (Fulton St)	Shirley St			20			11							1	Remove Ramp
Sub-Total				**0**	**0**	**89**	**0**	**0**	**36**	**4**	**8**	**0**	**0**	**0**	**18**	**5**	

*Contingency line item amount provided for adjustments outside of curb ramp pay limits.

**While ramp is compliant upon initial inspection, it is to be improved in order to create a more resilient curb ramp.

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted.