

ADA SUMMARY OF QUANTITIES - MASSEY CHAPEL/BARBEE RD. FROM NC 54 TO SR 1118

Municipality:	Durham
WBS Number:	2026CPT.05.14.10321.1, etc.
County:	Durham

Sheet No.
42

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2738000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
26403	1	SR-1104 (Herndon Rd)	SR-1106 (Massey Chapel Rd)	9											1		Type 7 - 848.06
26404	1	SR-1104 (Herndon Rd)	SR-1106 (Barbee Rd)	9											1		Type 7 - 848.06
26406	1	SR-1106 (Barbee Rd)	SR-1104 (Herndon Rd)												1		Standard - 848.06
26407	1	SR-1106 (Barbee Rd)	SR-1104 (Herndon Rd)	6											1		Type 7 - 848.06
26408	1	SR-1106 (Barbee Rd)	SR-1105 (Herndon Rd)	6											1		Type 7 - 848.06
Sub-Total for Massey Chapel/Barbee Rd. From NC 54 To SR 1118				30	0	0	0	0	0	0	0	0	0	0	5	0	

*Contingency line item amount provided for adjustments outside of curb ramp pay limits.

**While ramp is compliant upon initial inspection, it is to be improved in order to create a more resilient curb ramp.

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted.