Docusign Envelope ID: E34754C5-7036-4B59-88AD-A70B05D5F156

TIP NO.	SHEET NO.
HL-0025	SIGN-1

APPROVED: _____

DATE: _____

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 030740 ENGINEER STEVEN MATHEW KARNIS

Signed by: Steve Karnis 2/4/2026
1DAB4E64B005484F...

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

A. MORTON THOMAS AND ASSOCIATES, INC.
10735 DAVID TAYLOR DRIVE, SUITE 310•CHARLOTTE, NC 28262
(704) 595-9975•NC LICENSE NO. F-1049
WWW.AMTENGINEERING.COM

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
MECKLENBURG COUNTY

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
903.10	GROUND MOUNTED SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	SIGNING - MOUNTING OF TYPE 'D', 'E', AND 'F' SIGNS ON 'U' CHANNEL POSTS
1264.01	OBJECT MARKERS - TYPES
1264.01	OBJECT MARKERS - INSTALLATION
1264.02	OBJECT MARKERS - INSTALLATION

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	SIGNING PLAN TITLE AND SCHEDULE SHEET
SIGN-2	SPECIAL SIGN DESIGN
SIGN-3	TYPE "E" SIGNS
SIGN-4	EXISTING AND PROPOSED SIGNS

SIGNING SUMMARY OF QUANTITIES

ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4025000000	901	CONTRACTOR FURNISH, TYPE D SIGN	25.2	S.F.
4025000000	901	CONTRACTOR FURNISH, TYPE E SIGN	123.3	S.F.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	369	L.F.
4096000000	904	SIGN ERECTION, TYPE D	2	EA.
4102000000	904	SIGN ERECTION, TYPE E	23	EA.
4116100000	904	SIGN ERECTION, RELOCATE SIGN TYPE E	4	EA.
4151000000	907	STOCKPILE SIGN SYSTEM, STEEL BEAM	2	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	14	EA.

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) SIGNS FURNISHED BY CONTRACTOR

B) CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE CONTRACTOR FURNISHED SIGNS WILL BE REQUIRED.

C) IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

D) SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING OR PAVEMENT MARKINGS. SEE TRAFFIC CONTROL PLANS.

E) WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

F) ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE HANDLED WITH CARE AND RELOCATED TO AVOID CONFLICT WITH PROPOSED IMPROVEMENTS.

G) WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

H) THE BACKGROUND FOR TYPE 'E' SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

I) CONTRACTOR TO RELOCATE EXISTING SIGNS WITH CARE. DAMAGED SIGNS TO BE REPLACED.

J) SEE ROADWAY PLANS FOR GUARDRAIL DETAILS.

PLAN SUBMITTED TO:

KELVIN JORDAN	SIGNING & DELINEATION REGIONAL ENGINEER
ASHLEY MATTHEWS	SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN PREPARED BY: AMT

STEVE KARNIS, PE	PROJECT MANAGER
DAN MORGAN, EI	PROJECT DESIGN ENGINEER

A. MORTON THOMAS AND ASSOCIATES, INC.
10735 DAVID TAYLOR DRIVE, SUITE 310•CHARLOTTE, NC 28262
(704) 595-9975•NC LICENSE NO. F-1049
WWW.AMTENGINEERING.COM

2/4/2026
X:\Raleigh\17-1112.013 - HL-0025 - Greylock Ridge Rd Ext\05-CAD\Greylock_Ridge_Ext\Traffic\Signing\CADD\Greylock_TMP_SIGN01.dgn
dmorgan