Docusign Envelope ID: E34754C5-7036-4B59-88AD-A70B05D5F156

TIP NO.	SHEET NO.
HL-0025	SIGN-3

APPROVED: _____

DATE: _____

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 030740 ENGINEER STEVEN MATHEW KARNIS

Signed by: Steve Karnis 2/4/2026
1DAB4E64B00546F

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

AMT
A. MORTON THOMAS AND ASSOCIATES, INC.
10735 DAVID TAYLOR DRIVE, SUITE 310 • CHARLOTTE, NC 28262
(704) 595-9975 • NC LICENSE NO. F-1049
WWW.AMTENGINEERING.COM

(401) QUANTITY REQ'D 4

24" X 30"
R2-1

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 3

30" X 30"
R1-1

ONE "U" POSTS PER SIGN

(403) QUANTITY REQ'D 2

24" X 12"
W16-7P

YELLOW/GREEN REFLECTIVE SHEETING
ONE "U" POSTS PER SIGN
TO BE MOUNTED BELOW SIGN 405

(404) QUANTITY REQ'D 2

36" DIA.
W10-1

ONE "U" POST PER SIGN

(405) QUANTITY REQ'D 2

30" X 30"
W11-2

YELLOW/GREEN REFLECTIVE SHEETING
ONE "U" POST PER SIGN

(406) QUANTITY REQ'D 6

18" X 18"
OM4-3

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 1

36" X 36"
W8-26

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D 2

36" X 36"
W10-4L

ONE "U" POSTS PER SIGN

(409) QUANTITY REQ'D 2



30" X 30"
W3-3

ONE "U" POSTS PER SIGN

(410) QUANTITY REQ'D 2

24" X 24"
R3-4

ONE "U" POSTS PER SIGN

TYPE "E" SIGNS

2/4/2026
X:\Raleigh\17-1112.013 - HL-0025 - Greylock Ridge Rd Ext\05-CAD\Greylock_Ridge_Ext\Traffic\Signing\CADD\Greylock_TMP_SIGN03.dgn
dmorgan